POWERJACKS

PRECISION ACTUATION



SCREW JACK DESIGN GUIDE

POWERJACKS

Best engineered solution for precision linear actuation, power transmission & jacking systems.



Capability



OUR EXPERTISE HAS BEEN BUILT ON A HISTORY OF MORE THAN 100 YEARS OF ENGINEERING, CRAFTSMANSHIP, VISIONARY DESIGN, QUALITY MANUFACTURE AND CUSTOMER CARE.



Power Jacks is a manufacturing/engineering company specialising in the design and manufacture of actuation, lifting and positioning solutions for applications in Industrial Automation, Energy, Defence, Medical, Transport, and the Civil Engineering sectors.

Headquartered near Aberdeen in the UK, the company is the UK's largest screw jack manufacturing facility, that uses the latest engineering technologies to deliver quality products (ISO 9001) that offer reliability, performance and economy.


Power Jacks deliver this high quality service in a safe (ISO 45001) and environmentally friendly (ISO 14001) working environment thanks to the highly trained, flexible and motivated teams that work throughout the business driving the company to higher levels of performance.

We know our customers demand our engineering expertise to help find a solution for their applications. We take pride in designing and delivering the best solution using standard or special designs that help improve your business.

Our Vision is to become the partner of choice for our products globally Our Mission is to provide high quality lifting & positioning solutions.

Global Reach

Power Jacks has local representation in 26 countries and supplies its products to more than 80 countries worldwide.



Contents - Part 1

1. Introduction		
Compare Screw Jack Sizes	8	E-Series Translating Machine Scre
Translating Screw Jack Building System	10	E-Series Rotating Machine Screw
Rotating Screw Jack Building System	11	Variants
Jacking Systems		Anti-Backlash
Screw Jack Product Code	14	Anti-Rotation (Keyed)
Selecting a Screw Jack	18	Anti-Backlash & Anti-Rotation (Ke
•		Safety Nuts
2. C-Series - Machine Screw Jack	22	Double Hub Nut for Rotating Screv
Features		Double Clevis Screw Jacks
Application Focus	26	
Performance	27	4. E-Series - Stainless Steel Scre
C-Series Translating Machine Screw Jack 10kN	28	Features
C-Series Rotating Machine Screw Jack 10kN		Application Focus
C-Series Translating Machine Screw Jack 25kN		Performance
C-Series Rotating Machine Screw Jack 25kN		E-Series Translating Stainless Ste
C-Series Translating Machine Screw Jack 50kN		E-Series Rotating Stainless Steel 9
C-Series Rotating Machine Screw Jack 50kN		E-Series Translating Stainless Ste
C-Series Translating Machine Screw Jack 100kN		E-Series Rotating Stainless Steel S
C-Series Rotating Machine Screw Jack 100kN		E-Series Translating Stainless Ste
Anti-Backlash	36	E-Series Rotating Stainless Steel S
Anti-Rotation (Keyed)		E-Series Translating Stainless Ste
Safety Nuts		E-Series Rotating Stainless Steel 9
End Fittings for Translating Screw		E-Series Translating Stainless Ste
Trunnion Mounts		E-Series Rotating Stainless Steel S
Motor Adaptor		E-Series Translating Stainless Ste
Limit Switches on Screw Jack Cover Pipe		E-Series Rotating Stainless Steel 9
Rotary Limit Switches for Screw Jacks		E-Series Translating Stainless Ste
,		E-Series Rotating Stainless Steel S
3. E-Series - Machine Screw Jack	44	E-Series Translating Stainless Ste
Features		E-Series Rotating Stainless Steel S
Application Focus		Variants
Performance	52	Anti-Backlash
E-Series Translating Machine Screw Jack 5kN	54	Anti-Rotation (Keyed)
E-Series Rotating Machine Screw Jack 5kN		Anti-Backlash & Anti-Rotation (Ke
E-Series Translating Machine Screw Jack 10kN Type-1		Safety Nuts
E-Series Rotating Machine Screw Jack 10kN Type-1		Double Hub Nut for Rotating Screv
E-Series Translating Machine Screw Jack 10kN Type-2		Double Clevis Screw Jack
E-Series Rotating Machine Screw Jack 10kN Type-2		
E-Series Translating Machine Screw Jack 25kN		
E-Series Rotating Machine Screw Jack 25kN		5. E-Series - Ball Screw Jack
E-Series Translating Machine Screw Jack 50kN		Features
E-Series Rotating Machine Screw Jack 50kN		Application Focus
E-Series Translating Machine Screw Jack 100kN		Performance
E-Series Rotating Machine Screw Jack 100kN		E-Series Translating Ball Screw Ja
E-Series Translating Machine Screw Jack 200kN		E-Series Rotating Ball Screw Jack
E-Series Rotating Machine Screw Jack 200kN		E-Series Translating Ball Screw Ja
E-Series Translating Machine Screw Jack 300kN		E-Series Rotating Ball Screw Jack
E-Series Rotating Machine Screw Jack 300kN		E-Series Translating Ball Screw J
E-Series Translating Machine Screw Jack 500kN		E-Series Rotating Ball Screw Jack
E-Series Rotating Machine Screw Jack 500kN		E-Series Translating Ball Screw J
E-Series Translating Machine Screw Jack 1000kN		E-Series Rotating Ball Screw Jack
E-Series Rotating Machine Screw Jack 1000kN		E-Series Translating Ball Screw J
E-Series Translating Machine Screw Jack 1500kN		E-Series Rotating Ball Screw Jack
<u> </u>		E-Series Translating Ball Screw Ja

E-Series Translating Machine Screw Jack 2000kN	76
E-Series Rotating Machine Screw Jack 2000kN	77
Variants	78
Anti-Backlash	80
Anti-Rotation (Keyed)	82
Anti-Backlash & Anti-Rotation (Keyed)	84
Safety Nuts	86
Double Hub Nut for Rotating Screw Jacks	88
Double Clevis Screw Jacks	89
4. E-Series - Stainless Steel Screw Jacks	90
Features	91
Application Focus	94
Performance	95
E-Series Translating Stainless Steel Screw Jack 10kN	
E-Series Rotating Stainless Steel Screw Jack 10kN	97
E-Series Translating Stainless Steel Screw Jack 25kN	
E-Series Rotating Stainless Steel Screw Jack 25kN	
E-Series Translating Stainless Steel Screw Jack 50kN	
E-Series Rotating Stainless Steel Screw Jack 50kN	
E-Series Translating Stainless Steel Screw Jack 100kN	
E-Series Rotating Stainless Steel Screw Jack 100kN	
E-Series Translating Stainless Steel Screw Jack 200kN	
E-Series Rotating Stainless Steel Screw Jack 200kN	
E-Series Translating Stainless Steel Screw Jack 300kN	
E-Series Rotating Stainless Steel Screw Jack 300kN	
E-Series Translating Stainless Steel Screw Jack 500kN	
E-Series Rotating Stainless Steel Screw Jack 500kN	
E-Series Translating Stainless Steel Screw Jack 1000kN	
E-Series Rotating Stainless Steel Screw Jacks 1000kN	
Variants	
Anti-Backlash	
Anti-Rotation (Keyed)	
Anti-Backlash & Anti-Rotation (Keyed)	
Safety Nuts	
Double Hub Nut for Rotating Screw Jacks	
Double Clevis Screw Jack	123
5. E-Series - Ball Screw Jack	12/
Features	
Application Focus	
Performance	
E-Series Translating Ball Screw Jack 10kN	
E-Series Rotating Ball Screw Jack 10kN	
E-Series Translating Ball Screw Jack 25kN	
E-Series Rotating Ball Screw Jack 25kN	
E-Series Translating Ball Screw Jack 50kN	
E-Series Rotating Ball Screw Jack 50kN	
E-Series Translating Ball Screw Jack 100kN	
E-Series Rotating Ball Screw Jack 100kN	
E-Series Translating Ball Screw Jack 200kN	
E-Series Rotating Ball Screw Jack 200kN	
E-Series Translating Ball Screw Jack 300kN	

www.powerjacks.com

POWERJACKS -

-Series Rotating Ball Screw Jack 300kN		Screw Jack Key Torque	
ariants		Side Load Rating	
Oouble Clevis Screw Jack		Radial Loads on Screw Jack Worm Shaft	
nti-Rotation	147	Axial Backlash Ratings	
E Carica Ballan Carron Inch	1/0	Lateral Movement Ratings	
. E-Series - Roller Screw Jackeatures		Operation	
eatures	149	Calculations Formulae	197
. E-Series - Screw Jack Accessories	152		
nd Fittings	154	T D V O	
Machine Screw Jack Bellow Boots	156	TRYO	U
Jpright Machine Screw Jack Bellows Boots	157		
nverted Machine Screw Jack Bellows Boots	158		
Ball Screw Jack Bellows Boots	159	3D C	
Jpright Ball Screw Jack Bellows Boots	160		
nverted Ball Screw Jack Bellows Boots	161		
top Nuts	162		
land Wheels & Rotation Indicators	162	PORT	
runnion Mounts		FURI	
Notor Adaptors		ite -	
imit Switches on Cover Pipe			
Rotary Limit Switch - RLS	169	6 6	
. Screw Jack Special Designs	170	⊕®	
Custom Design Process			
pecial Design Examples		POWERJACKS	
J-Series Subsea Screw Jacks		POW=K	
pplication Focus	176	Anna W. Market S. America Science	-
		Engineering CAD Configur	20000
. Engineering Guide		Engineering	15° 12
crew Jack Performance		Ια.	
Machine Screw Jack Column Strength Charts		NG THE	
Ball Screw Jack Column Strength Charts		The second secon	683
critical Screw Speed Charts	185	10 mm	- "
		S. B.	9
2D CAD Drawings		TIACK!	
• 3D CAD Models	PO'	VERJACK!	
11 0, 12	PACE	A PROPERTY OF THE PROPERTY OF	Control Property Control
 Dimensioned Data Sheet 		ng naaring CVD Con	
	E	ng/nam	-
		to some local	- 134
		- L L	dia The
		The state of the s	Salara Maria
	-	ELL MAN TO WE	State Color State State
		4 1 TO	100.00

Contents - Part 2

POWERJACKS

10. Bevel Gearbox Range-C	00
Features	01
Basic Range Overview	04
Product Code	05
How to Select a Bevel Gearbox	08
Performance21	10
Torque and Power Rating21	11
Load Factors21	12
Permissible Shaft Loading21	14
Shaft & Gear Configurations21	15
Bevel Gearbox Range-C35 - Ratio 1:1 & 1.5:121	
Bevel Gearbox Range-C35 - Ratio 2:1 & above21	
Bevel Gearbox Range-C35 - Hollow Shaft - All Ratios22	20
Bevel Gearbox Range-C37 - Ratio 1:1 & 1.5:1	22
Bevel Gearbox Range-C37 - Ratio 2:1 & above	
Bevel Gearbox Range-C37 - Hollow Shaft - All Ratios22	
Bevel Gearbox Range-C38 - Ratio 1:1 & 1.5:1	
Bevel Gearbox Range-C38 - Ratio 2:1 & above23	
Bevel Gearbox Range-C38 - Hollow Shaft - All Ratios23	
Bevel Gearbox Range-C39 - Ratio 1:1 & 1.5:123	
Bevel Gearbox Range-C39 - Ratio 2:1 & above	
Bevel Gearbox Range-C39 - Hollow Shaft - All Ratios23	
Bevel Gearbox Range-C40 - Ratio 1:1 & 1.5:1	
Bevel Gearbox Range-C40 - Ratio 2:1 & above	
Bevel Gearbox Range-C40 - Hollow Shaft - All Ratios24	
Bevel Gearbox Range-N42 - Ratio 1:1 & 1.5:1	
Bevel Gearbox Range-N42 - Ratio 1:1 & 1.5:1	
Bevel Gearbox Range-N42 - Hollow Shaft - All Ratios	
Motors Adapters	
Optional Features	
Subsea Gearbox	
Custom Applications	
Sustain Applications20	50
44.0	- 1
11. System Components	
Electric Motors	
Couplings & Drive Shafts	
Flexible Coupling	
Jaw Type Flexible Coupling	
Flexible Spacer Couplings (Self-Supporting Drive Shafts) 28	
Steel Gear Couplings	
Steel Gear Couplings - Continuous Sleeve	
Steel Gear Couplings - Flanged Sleeve	
Solid Drive Shafts	
Plummer Blocks	
Hand Wheels	
Rotation Indicators28	37
Motion Control	
RLS-51 Geared Cam Limit Switches	90
RLS-51 Features29	
RLS-51 Performance29	92
RLS-51 Switching Contacts29	93
RLS-51 Dimensions29	94

Proximity Sensors......296

Compact Electro-Mechanical Contact Limit Switches......297

Safety Related Electro-Mechanical Contact Limit Switches	. 298
Safety Related Contact Limit Switches Dimensions	. 299
Incremental Encoders	.300
Absolute Encoders	.301
12. Engineers Reference - Useful Information	302
Conversion Factors	.304
Enclosure Ratings	.306
Metric Nuts and Bolts	.307
Metric Square and Rectangular Parallel Keys	.308
Useful Formulae for Actuator Calculations	.309
Limitation of Responsibility	.310

Warranty......311

12.

Note:


- 1. Designs subject to change without notice.
- 2. All colours for illustrative purposes only.

NEED HELP SELECTING A GEARBOX? THEN TRY OUR PRODUCT SELECTOR


Just enter your application details and the Product Selector will recommend a suitable product with a calculation summary and links to the associated CAD and Data Sheets. An ideal tool if you are not familiar with the products or need answers fast.




C-Series - Translating Screw




E-Series - Translating Screw








Translating Screw Jack Building System



■ Special Screw Jacks Design Available when you need more than the standard solution.

Rotating Screw Jack Building






■ Special Screw Jacks Design Available when you need more than the standard solution.

Screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearboxes, drive shafts, couplings, plummer blocks and motion control devices.

Four of the most popular system configurations are the 'H', 'U', 'T' and 'I' configured jacking systems. Note that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.

Typical 'H' configuration System



- 1. Screw Jack
 - C-Series Rotating Machine Screw Jack shown here.
- 2. Bevel Gearbox
 - Range-N Spiral Bevel Gearboxes
- 3. Flexible Coupling
 - A range of couplings are available to suit each systems requirements including Jaw, Spacer and Geared types.
- 4 Drive Shaft
 - Every drive shaft is manufactured to order for each system design. Self supporting drive shafts (spacer couplings) are also available.
- 5. Shaft Supports (plummer blocks).
- 6. Electric Motor
 - Standard electric motors in 3 phase, 1 phase, DC and servo designs. Supplied as a basic motor or as part of a geared motor. Brakes are available for all motors.

Jacking Systems

Jacking systems are not limited to the number of screw jacks shown here. They are regularly supplied to clients with 2, 4, 6, 8 jack systems. Larger systems can extend up to 16 or higher. With the use of electronic synchronisation/control multiple systems or screw jacks can be used in unison. Extending the possible number of screw jacks used in unison in excess of 100.

To facilitate electronic control of screw jacks, feedback devices (eg encoder, limit switch) are available, mounted on the screw jack or its motor or another system component.

'U' Configuration System





'I' Configuration System






'T' Configuration System





- 1 GROUP-1 Screw Jack Gearbox Definition
- 2 GROUP-2 Screw Jack Features
- 3 GROUP-3 Accessories



1 GROUP-1 - Screw Jack Gearbox Definition

1-9	Screw Jack Series
Е	Series
С	Series

2 - Screw Type				
М	Machine Screw			
В	Ball Screw			

3- Screw Configuration			
R	Rotating Screw		
Т	Translating Screw		

4-7 - Capacity	0005	0010	0025	0050	0100	0200	0300	0500	1000	1500	2000
kN	5	10	25	50	100	200	300	500	1000	1500	2000

8 - Character Space

9-Gearbo	х Туре
U	Upright (Standard, Type-1 Housing)
I	Inverted (Standard, Type-1 Housing)
V	Upright - All Stainless Steel Screw Jack #16 (Standard, Type-1 Housing)
J	Inverted - All Stainless Steel Screw Jack #16 (Standard, Type-1 Housing)
С	Cubic
Т	Upright (Type-2 Housing Option)
Н	Inverted (Type-2 Housing Option)
S	Upright - All Stainless Steel Screw Jack #16 (Type-2 Housing Option)
G	Inverted - All Stainless Steel Screw Jack #16 (Type-2 Housing Option)

10 - Gearbox Feature - 1		
0	None	
K	Anti-Rotation (Keyed)	
С	Secondary Guide	
E	Anti-Rotation (keyed) with Secondary Guide	
Н	Double Hub Nut #1. #12	
Т	Trunnion Nut	
U	Trunnion Nut with Feet	

11 - Gearbo	11 - Gearbox Feature - 2		
0	None		
Α	Anti-Backlash (this option is zero backlash for ball screws)		
В	Anti-Backlash with wear monitor - Visual		
С	Anti-Backlash with wear monitor - Sensor		
R	Safety Nut Tension		
S	Safety Nut Compression		
Т	Safety Nut Tension with Wear Monitor - visual		
U	Safety Nut Compression with wear monitor - visual		
V	Safety Nut Tension with Wear Monitor - Sensor		
W	Safety Nut Compression with wear monitor - Sensor		

12 - Gear Ratio		
1	Option 1 Ratio	
2	Option 2 Ratio	
Α	Option 1 Ratio with gear rotation monitor #12	
В	Option 2 Ratio with gear rotation monitor #12	

_					
ĺ	13 - Lifting Screw Lead				
I	1	Option 1 Lead - Right Hand (Standard) #4			
	2	Option 2 Lead - Right Hand ^{#4}			
ĺ	Α	Option 1 Lead - Left Hand ^{#5}			
ĺ	B Option 2 Lead - Left Hand #5				

14 - Worm Shaft Type #16		
0	0 Standard Material	
N	Nickel Plated Worm Shaft	
S	S Stainless Steel Worm Shaft	

15 - Worm Shaft Ends		
0	Both	
L	Left Hand Only	
R	Right Hand Only	
Х	Both with Protective Cap on LHS #11	
Υ	Both with Protective Cap on RHS #11	

	16 - Character Space	
--	----------------------	--

Screw Jack Product Code

- POWERJACKS

2

GROUP-2 - Screw Jack Features

17-20 - Stroke	0000
Stroke in mm	0-9999

21 - Character Space

22 - End Type #16 #17				
Е	Threaded End			
С	Clevis End			
Т	Top Plate			
F	Fork End (standard available up to 200kN)			
R	Rod End (standard available up to 200kN)			
J	Plain End			
Р	Pilot End #1			
N	No Pilot End #1			

23 - Gearbox Mounting			
В	Base Mount		
С	Second Clevis on Cover Pipe Standard #6 #9		
Е	Second Clevis on Cover Pipe 90 degree #9		
T	Trunnion Mount Standard #2		
U	T + Trunnion Feet		
Х	Trunnion Mount 90 degree #3		
Y	X + Trunnion Feet		

24 - Lifting Screw Material #16		
0 Standard		
S	S Stainless Steel	
М	M Standard with Low Friction Coating (Molycote)	
A Standard with Protective Coating (Armaloy)		

25 - Lifting Screw Covers				
0	Cover Pipe & No Bellows Boot #15			
В	Cover Pipe & Fabric Bellows Boot #9			
F	Fabric Bellows Boot x 2 - Rotating Screw			
R	Cover Pipe & Rubber Bellows Boot #9			
S	Rubber Bellows Boot x 2 - Rotating Screw			
N	No Cover Pipe & No Bellows Boot #9			
W	Cover Pipe & PU Waterproof Bellows Boot #9			
Х	PU Waterproof Bellows Boot x2 - Rotating Screw			

26 - Character Space

3

GROUP-3 - Accessories

27 - Drive Type #11					
0	None, Standard Features (tapped holes on gearbox side if present)	Н	Hand Wheel - LHS		
А	Motor Adapter Only, B14 - LHS	J	Hand Wheel - RHS		
В	Motor Adapter Only, B14 - RHS	R	Rotation Indicator (Visual) on worm shaft - LHS		
С	Motor Adapter B14 & Coupling - LHS	Т	Rotation Indicator (Visual) on worm shaft - RHS		
Е	Motor Adapter B14 & Coupling - RHS				

28- Motor Frame Size / Drive Interface Size #11				
0	Not Applicable	F	112 Size IEC Frame	
А	63 Size IEC Frame	G	132 Size IEC Frame	
В	71 Size IEC Frame	Н	160 Size IEC Frame	
С	80 Size IEC Frame	I	180 Size IEC Frame	
D	90 Size IEC Frame	J	200 Size IEC Frame	
Е	100 Size IEC Frame			

29 - Mounting	Kit for Limit Switches & Stop Nuts #18		
0	None	Р	Inductive Proximity Sensor, 2, End of Stroke, Adjustable #9
С	RLS-51 Rotary Cam Limit Switch - RHS #11	S	SKA Rotary Cam Limit Switch - RHS #11
D	RLS-51 Rotary Cam Limit Switch - LHS #11	Т	SKA Rotary Cam Limit Switch - LHS #11
E	RLS-51 Rotary Cam Limit Switch - RHS with Stop Nut #11	U	SKA Rotary Cam Limit Switch - RHS with Stop Nut #11
F	RLS-51 Rotary Cam Limit Switch - LHS with Stop Nut #11	V	SKA Rotary Cam Limit Switch - LHS with Stop Nut #11
М	Electro-Mechanical Limit Switch, 2, End of Stroke, Adjustable #9	W	Stop Nut

20 Pair	nt, Lubricant, Seals #13 #14
0	Standard Paint, Lubricant & Seals
1	Standard Paint & Food Grade Lubricant & Standard Seals
2	Standard Paint, Nuclear Grade Lubricant & Seals
3	Standard Paint, High Temperature Lubricant & Seals
4	Standard Paint, Low Temperature Lubricant & Seals
5	Standard Paint, Biodegradable Lubricant & Standard Seals
А	No Paint, Standard Lubricant & Seals
В	No Paint & Food Grade Lubricant & Standard Seals
С	No Paint, Nuclear Grade Lubricant & Seals
D	No Paint, High Temperature Lubricant & Seals
E	No Paint, Low Temperature Lubricant & Seals
F	No Paint, Biodegradable Lubricant & Standard Seals
G	Standard Primer, Lubricant & Seals
Н	Standard Primer & Food Grade Lubricant & Standard Seals
1	Standard Primer, Nuclear Grade Lubricant & Seals
J	Standard Primer, High Temperature Lubricant & Seals
К	Standard Primer, Low Temperature Lubricant & Seals
L	Standard Primer, Biodegradable Lubricant & Standard Seals
М	Epoxy Paint, Standard Lubricant & Seals
N	Epoxy Paint & Food Grade Lubricant & Standard Seals
Р	Epoxy Paint, Nuclear Grade Lubricant & Seals
R	Epoxy Paint, High Temperature Lubricant & Seals
S	Epoxy Paint, Low Temperature Lubricant & Seals
Т	Epoxy Paint, Biodegradable Lubricant & Standard Seals

Notes:

- #1 Rotating screw models only.
- #2 Trunnions on same side as worm shaft (standard).
- #3 Trunnions at 90° to worm shaft.
- #4 Standard right hand thread form. Worm shaft turns clockwise to extend screw
- #5 Left hand thread form. Worm shaft turns anti-clockwise to extend screw.
- #6 Standard is clevis axis parallel to worm shaft.
- #7 Limit switch mounting included.
- #8 Plain End "A" has same dimensions as "E threaded end" except no thread form.
- #9 Translating screw models only.
- #10 Basic Translating and Rotating units in both Upright and Rotating versions (all variant & accessories on application).
- #11 All models except E-Series 5 kN & 10 kN Type-1 models
- #12 Models 10kN to 100kN only
- #13 Power Jacks defined standard paint available as a data sheet.
- #14 Power Jacks defined standard lubricant.
- #15 For Rotating Screw Jacks the "Cover Pipe" may actually be a "Plug"
- #16 All Stainless Steel Screw Jack by default defines the worm shaft, lifting screw and end fitting as Power Jacks standard stainless steel material.
- #17 If Lifting Screw is Stainless Steel material then the End Fitting is Stainless Steel as well by default.
- #18 Limit Switches not included. Limit switch specification to be detailed as separate item.

Product Code Example

CMT0050-C0A1100-0810-CT00-0000 C-Series, Machine Screw, Translating, 50kN, Cubic, Anti-Backlash mechanism, 6:1 gear ratio, 9mm lead on screw, 810mm Stroke, Clevis End, Trunnion Mount, standard drive features, standard paint and lubrication.

,	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
	С	М	т	0	0	5	0	-	С	0	Α	1	1	0	0	_	0	8	1	0	_	С	Т	0	0	_	0	0	0	0

EMT0100-U001100-0790-TB00-0000 E-Series, Machine Screw, Translating, 100kN, Upright, No extra gearbox features, 8:1 gear ratio, 12mm lead on screw, 790mm Stroke, Top Plate, Base Mount, standard drive features, standard paint and lubrication.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
E	М	Т	0	1	0	0	-	U	0	0	1	1	0	0	-	0	7	9	0	-	Т	В	0	0	-	0	0	0	0

EMT0200-V002100-1250-CB00-0000 E-Series, Machine Screw, Translating, 200kN, Upright, Stainless Steel Screw Jack, No extra gearbox features, 8:1 gear ratio, 12mm lead on screw, 1250mm Stroke, Clevis End, Base Mount, standard drive features, standard paint and lubrication.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
Е	М	Т	0	2	0	0	-	٧	0	0	2	1	0	0	-	1	2	5	0	-	С	В	0	0	-	0	0	0	0

EBR0025-I001200-0500-FB0B-CAE0 E-Series, Ball Screw, Rotating, 25kN, Inverted, No extra gearbox features, 6:1 gear ratio, 10mm lead on screw, 500mm Stroke, Fork End, Base Mount, Bellows Boot screw protection, Motor Adapter & Coupling Kit for IEC 63 Frame size on Left Hand Side (LHS), RLS-51 rotary cam limit switch on Right Hand Side (RHS) with Stop Nut, standard paint and lubrication.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
E	В	R	0	0	2	5	-	ı	0	0	1	2	0	0	-	0	5	0	0	-	F	В	0	В	-	С	Α	E	0

Five Step Guide to Initial Screw Jack Selection

The following selection procedure is applicable for Machine Screw and Ball Screw Jacks.

Calculate Power and Torque Requirements

Select a screw jack from the tables with adequate load carrying capacity and note the screw jack static and dynamic efficiency for required input speed.

Step 1 - Screw Jack Input Speed

Input speed should not exceed 1800 rpm. Number of starts on lifting screw is usually 1, unless otherwise stated.

Note: Screw Lead = Pitch x No of Starts

Step 2 - Operating Input Power (kW), Pin

$$P_{in}(kW) = \frac{\text{Load (kN) x Linear Speed (mm/min)}}{60000 \times \eta_{d}}$$

 η_d = Dynamic Screw Jack Efficiency

Step 3 - Operating Input Torque

$$T_{ino}$$
 [Nm] = $\frac{P_{in}$ (kW) x 9550 N (rpm)

Step 4 - Screw Jack Start-Up Torque

$$T_{ins} = \frac{\text{Load (kN) x Pitch (mm) x N° of Starts on Lifting Screw}}{2 \times \pi \times \eta_s \times \text{Gear Ratio}}$$

 η_s = Static Screw Jack Efficiency

Note: Screw Lead = Pitch x No of Starts

Step 5 - Mechanical Power and Torque Check

Check whether the screw jack power and torque required for the application is not greater than the maximum allowable mechanical input power [P_{mechanical}] and Start-Up Torque at Full Load (T_s) values specified in the screw jack performance tables.

If $P_{mechanical} > P_{in} \& T_s > T_{ins}$ then the screw jack selected is acceptable for power requirements.

Example Selection

Application Constraints

- Load on Screw Jack = 15 kN in Tension
- Linear Speed required = 100 mm/min

Consider all application constraints then choose a screw jack that looks suitable for the application with a load rating equal to or greater than the maximum working load. For this example, a 25 kN E-Series Machine Screw Jack (refer P60) with translating screw, 6:1 gear ratio, single start lifting screw (6 mm lead).

Calculate Power and Torque Requirements

Step 1 - Screw Jack Input Speed

N = 100 rpm Input speed should not exceed 1800 rpm.

Step 2 - Operating Input Power (kW), Pin

$$P_{in}[kW] = \frac{15 (kN) \times 100 (mm/min)}{60000 \times 0.264}$$

 $\eta_{d} = 0.264 \text{ (Refer P60)}$ $P_{in} = 0.095 \text{ kW}$

Step 3 - Operating Input Torque

$$T_{ino}$$
 (Nm) = $\frac{0.095 \text{ (kW) x } 9550}{100 \text{ (rpm)}}$

 $T_{inc} = 9.1 \text{ Nm}$

Step 4 - Screw Jack Start-Up Torque

$$T_{ins} = \frac{15 \text{ (kN)} \times 6 \text{ (mm)} \times 1 \text{ (N° of starts on Lifting Screw)}}{2 \times \pi \times 0.201 \times 6 \text{ (Gear Ratio)}} \qquad T_{ins} = 11.9 \text{ Nm}$$

$$\eta_s = 0.201 \text{ (refer P60)}$$

Step 5 - Mechanical Power and Torque Check

Find the screw jacks mechanical power and torque rating from the performance data tables (refer P60).

$$\mathbf{P}_{\text{mechanical}}$$
 = 1.5 kW > \mathbf{P}_{in} and \mathbf{T}_{s} = 19 Nm > \mathbf{T}_{ins}

Therefore the screw jack selected is suitable for application for initial constraints tested, further analysis may be required to ensure the screw jack is suitable for all application conditions. Continue with further selection calculations or consult Power Jacks Ltd.

Screw Jack Constraints for Detailed Selection

Lifting Screw Column Strength

For compressive loads on the screw jack lifting screw column strength calculations are required to check for buckling. As a screw jack selection guide use the following process:

- 1. Determine the maximum column strength (L) for the screw jack being considered.
- 2. Referring to the relevant column buckling chart determine the permissible compressive load (Wp) corresponding to the column length (L) for the appropriate end constraints. This permissible compressive load is the maximum load (inclusive of shock loads) which may be applied to the screw jack for a given column length.
- 3. Where an application involves human cargo or there is a risk to personnel, it is highly recommended that the permissible compressive load (as calculated above) be factored by 0.7 to enhance working safety. (Equivalent to a column strength safety factor of 5).

$$W_{phc} = W_{p} \times 0.7$$
 (Permissible compressive load for personnel risk applications)

- Note 1. For detailed analysis of screw jacks and their systems consult Power Jacks.
 - 2. Safety factor of 3.5 for column strength's used for normal industrial cargo.

Lifting Screw Critical Speed


For fast operating rotating screw jacks, the critical speed (rotational speed) of the lifting screw needs to be considered in case of shaft whirling. To calculate the critical speed for rotating screw jacks:

- 1. Refer to the appropriate critical speed chart.
- 2. Select the correction factor F_{cc} corresponding to the end support conditions for the application.
- 3. From the critical speed chart, select the critical speed corresponding to the unsupported screw length (m) and the screw jack load rating (kN).
- 4. Calculate the limiting critical speed with the formula: Limiting Critical Speed = Critical screw speed $x F_{cs}$


Lifting Screw Deflection

The lifting screw of a screw jack mounted horizontally will deflect under its own weight to some extent. The amount of deflection tolerable (y_{τ}) should be less than 0.5 mm per metre.


Deflection Factors, F



Deflection, y, (mm) =
$$\frac{6 \times 10^{-9} \times L^4}{F_{\odot} (d-p)^2}$$



Deflection Tolerable,
$$y_T$$
, (mm) = $\frac{0.5 \text{ x}}{1000}$



L = Lifting Screw Length (mm)
d = Diameter of Lifting Screw (mm)

p = Pitch of Lifting Screw (mm)

If $y < y_{\tau}$ then the lifting screw deflection is acceptable.

Note: This is only a deflection guide. For detailed analysis, including methods to reduce deflections, consult Power Jacks Ltd.

Screw Jack Input Torque

Start up/static torque values are listed in all performance tables. Whereas dynamic torque values are either calculated using the tabulated dynamic efficiencies or taken direct from torque tables where listed. For detailed screw jack analysis consult Power Jacks Ltd.

Side Loads on Screw Jacks

It is recommended that all side loads (F_{sl}) are carried by guides in your arrangement and not by the lifting screw and nut. If there are any side loads on the screw jack, they must not exceed those tabulated in the Engineering Guide, Side Load Rating Section, and it must be noted that any such loads will adversely affect the life of the lifting screw and nut.

Radial Forces on Screw Jack Worm Shaft

For applications where a screw jack is belt driven, radial force (F_R) values exerted on the worm shaft must not exceed those tabulated in the Engineering Guide Section. Values are tabulated for the metric machine screw jacks and ball screw jacks. The values are maximum values for the screw jacks at rated load regardless of worm speed or load direction.

Screw Jack Self-Locking

Approximately 50% of machine screw jacks are self-locking either in the gearbox or the lifting screw, however to ensure there is no self-lowering and to reduce drift due to the motor slowing, a brake is recommended. Standard motor frame size brakes will be suitable for most applications with only slight vibration and thermal fluctuation present. Motor selection as normal. For dynamic braking consult Power Jacks.

Ball screw jacks and roller screw jacks always require a brake as their high efficiency makes them self-lowering.

Use the closest standard brake size that is greater or equal to the motor brake torque required.

- Note 1. Self lowering can occur in any jacking system not fitted with a brake, where high levels of vibration are present in the application.
 - 2. Power Jacks recommend the use of a brake on single screw jack applications in the vertical position.

Jacking System Power Input

Total Input Power for Jacking Systems (kW), P.:

Number of Screw Jacks in System	2	3		6-8
Jacking System Efficiency	0.95	0.90	0.85	0.80

Gearbox Efficiency = Bevel Gearbox Efficiency x Reduction Gearbox Efficiency

Bevel Gearbox Efficiency = 0.95 typical

Reduction Gearbox Efficiency = Consult unit details, if no reduction gearbox present assume efficiency of 1.


Note

For Screw Jacks connected in-line, the worm shaft can transmit up to 3 times the torque for a single screw jack at its maximum capacity, except the E--0200 (200kN) Unit which can transmit 1.5 times the torque.

2

C-Series - Machine Screw Jack

MODULAR CONTEMPORARY CUBIC DESIGN WITH BOLT-ON ACCESSORIES TO TAILOR SCREW JACK FOR YOUR EXACT APPLICATION NEEDS.




Key Features

- Metric Cubic Machine Screw Jacks
- Capacities 10N to 100kN as standard
- Translating and Rotating Screw
- Precision Worm Gear Set
- Standard Performance Power Jack
- 2 Gear ratios and 2 screw lead as standard
- Anti-backlash and anti-rotation (keyed) options
- 6 mounting options including trunnion and double clevis
- Special custom designs available



Features



Features

Translating Screw Rotating Screw





Typical Applications

Conventional Machine Screw Jacks are most widely used for intermittent duty cycles, as the screw jack incorporates a precision worm gear set in a rugged casting delivering positive, precise actuation. Available in a comprehensive range of materials and fittings with the option for special designs for specific application requirements. Used in a wide variety of industry sectors including metal processing, automotive, energy, civil and aerospace.

Standard Designs

The standard C-Series screw jack is available in translating and rotating screw designs in capacity sizes from 10kN to 100kN. It's design is compact and versatile with a large selection of standard options and accessories so you can configure a standard design that is just right for your application. These variants include Anti-Backlash, Anti-Rotation (Keyed) and Safety Nut designs.

Special Designs

We can fully customise our screw jacks so that your application can be the best.

Customisation can be anything from a small modification such as an extra bolt hole on an end fitting to a completely new design of screw jack based on our class leading technology.

For more details please see the Special Screw Jack information in Section-8 or contact us today with your requirements. Our team are looking forward to working with you.

Selecting the Right Screw Jack

Consider all application constraints then choose a product that looks suitable for the intended application. Calculate the power and torque requirements. This is a 5 step process:

- Screw Jack Input Speed (RPM)
- Operating Input Power (kW)
- Operating Input Torque (Nm)
- Screw Jack Start-up Torque (Nm)
- Mechanical Power and Torque Check

Systems

The screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearbox, drive shafts, couplings, plummer blocks and motion control devices.

The use of bevel gearboxes allows the distribution of drive throughout a jacking system. The gearboxes come in 2,3 and 4 way drive types. See Bevel Gearbox Section-10 for more details.

Bevel gearboxes and other system components can also be supplied in stainless steel or other corrosion resistant designs.



Two of the most popular system configurations are the 'H' and 'U' configured jacking systems. Remember that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.

If multiple machine screw jacks are connected in a mechanically linked system then the complete system may be considered self-locking. If you would like this checked consult Power Jacks. Alternatively, to be sure, include a brake on the system either as a stand alone device or as a brake motor.









SPECIAL EFFECT CAR REVEAL SYSTEM

C-Series Screw Jack System was pivotal to a dramatic 'magic mirror' effect that slowly unveiled the car to impressed onlookers during the UK launch.

The car sat inside a ring of pillars of coloured LED light, and was covered by a mirrored box that had a horizontal split. To make the car appear and disappear, the sides of the mirrored box were moved up and down in synchronisation so the top and bottom halves of the car were revealed at the same time. To keep the mirror operation simple yet effective, a four screw jack system in an H-configuration using 50kN C-Series rotating machine screw jacks was used. To move the mirrors in different directions at the same time using 1 lifting screw per screw jack required a customised design.

A special lifting screw which had right hand and left hand threads on the same screw was built into each of the screw jacks. The screw length matched the height of the installation: the upper half had a right hand thread form and the lower half had a left hand thread form.

A lifting nut with corresponding thread ran on each thread form portion of the screw, so each screw had two lifting nuts. In total the system had eight lifting nuts (two per screw jack) – four connected to the top mirror section and four to the bottom mirror section. As the jacking system was operated, the nuts ran in opposing directions so the mirror sections did likewise at the same speed in a mechanically synchronised manner.

By using a mechanically linked system, the whole operation was controlled by one motor which greatly simplified the control system and minimised costs.

The four C-Series cubic machine screw jacks selected for the system were mechanically linked to the electric motor via three bevel gearboxes from the ultra compact Range-N design.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.

POWERJACKS

Screw Jack Model 4			СМ-	0010	СМ-	0025	CM-	0050	СМ-	0100
Capacity	k1	1	1	0	2	:5	5	0	10	00
	Diamete	r (mm)	2	20	3	0	4	.0	5	5
Lead Screw		Option	1	2	1	2	1	2	1	2
	Lead	mm	5	10	6	12	9	18	12	24
0 5 .:	Optio	n 1	5	:1	6	:1	6:	:1	8	:1
Gear Ratios	Optio	n 2	20):1	24	i:1	24	i:1	24	:1
Turn of worm for travel	Option 1	1 Turn	1mm	2mm	1mm	2mm	1.5mm	3mm	1.5mm	3mm
of lead screw	Option 2	4 Turn	1mm	2mm	1mm	2mm	1.5mm	3mm	2mm	4mm
Maximum Input Power	Optio	n 1	0.3	375	1	.5	3	3	3.	75
(kW)	Optio	n 2	0.	19	0.3	375	0.	55	1.1	25
Start up torque at full	Optio	n 1	6.8	9.4	19.8	26.4	56.0	76.0	115.9	156.6
load (Nm) ²	Optio	n 2	3.0	4.1	8.7	11.7	25.5	34.7	60.5	81.9
Maximum Through	Optio	n 1	20).4	59	9.4	16	8.0	34	7.7
Torque (Nm) ⁷	Optio	n 2	9	.0	26	5.1	76	5.5	18	1.5
Challe Efficience	Optio	n 1	0.236	0.339	0.201	0.302	0.213	0.314	0.206	0.305
Static Efficiency ^a	Optio	n 2	0.133	0.192	0.113	0.171	0.117	0.172	0.132	0.195
D	Optio	n 1	0.306	0.424	0.264	0.383	0.281	0.398	0.272	0.388
Dynamic Efficiency ³	Optio	n 2	0.194	0.268	0.167	0.242	0.172	0.244	0.190	0.271
Lead Screw Restraining Torque (Nm) ⁵	-		22	30	76	102	210	290	575	780
Worm Shaft Radial Load (N):			3:	25	38	30	74	40	10	00
Maximum Input Speed (rpm)	-		18	800	18	00	18	00	18	00
Gear Case Material			Alum	inium	SG	Iron	SG	Iron	SG	Iron
Weight (kg) – stroke =	Transl	ating	3	.0	8	.3	19	2.5	19	2.5
150mm	Rota	ting	3	.1	8	.7	20).2	20	1.2
Weight (kg) – per extra	Transl	ating	0.	11	0.	21	0.	32	0.	32
25mm	Rota	ting	0.	05	0.	11	0.	19	0.	19


Notes:

- 1. All metric machine screws have a trapezoidal thread form.
- 2. For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw.
- 4. All C-Series screw jacks have grease lubricated gearbox and lead screw as standard.
- 5. Torque required to prevent the lead screw or lead nut from rotating if no anti-rotation device fitted.
- 6. Radial force applied midway along worm shaft key at 90° to key.
- 7. Maximum transmittable torque through worm shaft, not through gear set.

Performance

Screw Jack Model			CM-	0010
Capacity	k	N	1	0
	Diamete	er (mm)	2	0
Lead Screw	Lead	(mm)	5	10
O Butin	Opti	on 1	5	:1
Gear Ratios	Opti	on 2	20):1
Turn of worm for travel of lead screw	Option 1	1 Turn	1mm	2mm
Turn of worm for travel of lead screw	Option 2	4 Turn	1mm	2mm
Maniana Industry David (LAM)	Opti	on 1	0.3	375
Maximum Input Power (kW)	Opti	on 2	0.	19
Chart was to account to the land (Nam)	Opti	on 1	6.8	9.4
Start up torque at full load (Nm)	Opti	on 2	3.0	4.1
Maximum Through Torque (Nm)	Opti	on 1	20).4
Maximum imrough forque (Min)	Opti	on 2	9	.0
Static Efficiency	Opti	on 1	0.236	0.339
Static Efficiency	Opti	on 2	0.113	0.192
Dynamic Efficiency	Opti	on 1	0.306	0.424
Dynamic Efficiency	Opti	on 2	0.194	0.268
Lead Screw Restraining Torque (Nm)	-	-	22	30
Worm Shaft Radial Load (N)			32	25
Maximum Input Speed (rpm)	-	-	18	00
Gear Case Material			Alum	inium
Weight (kg) – stroke = 150mm	Trans	lating	3.	.0
weight (kg) - Stroke = 13011111	Rota	iting	3.	.1
Weight (kg) – per extra 25mm	Trans	lating	0.	11
weight (kg) – per extra zomm	Rota	iting	0.	05

CMT0010 Closed Heights



Closed Height 'C'	Threaded End	Top Plate	Clevis End	Fork End	Rod End
CMT0010	130	130	150	153	155
Stroke (mm)		With	Bellow Boot	s (B)	
0 - 500	150	150	170	173	175
501 - 1000	180	180	200	203	205
1001 - 1500	210	210	230	233	235
1501 - 2000	290	290	310	313	315

CMT0010 Stop Nut




Stop nut provides a full power mechanical stop at the end of the lead screw. To be used as a safety feature in emergency conditions. SN = Stroke + 25mm

Note:

- 1. All dimension in millimetres unless otherwise stated.
- 2. Designs subject to change without notice.


CMT0010-C00







CMR0010-C00









Column Strength



Critical Screw Speed



Bellows Boot



	ØA	ØB	ØC	D	Е
CMT0010	30	39	110	15	15
CMT0010 (Rod End)	22	39	110	15	15
CMR0010	35	39	110	15	15

Stroke	1 – 500	501 – 1000	1001 – 1500	1500 – 2000
F	30	60	90	170*

Accessories & Options




25kN Translating

Performance

Screw Jack Model			CM-	0025
Capacity	k	N	25	
Lead Screw	Diamete	er (mm)	3	0
Lead Screw	Lead	(mm)	6	12
Gear Ratios	Opti	on 1	6	:1
Geal Natios	Opti	on 2	24	::1
Turn of worm for travel of lead screw	Option 1	1 Turn	1mm	2mm
Turri or worm for travet or tead screw	Option 2	4 Turn	1mm	2mm
Maximum Input Dawas (I/W)	Opti	on 1	1	.5
Maximum Input Power (kW)	Opti	on 2	0.3	375
Start up targue at full load (Nm)	Opti	on 1	19.8	26.4
Start up torque at full load (Nm)	Opti	on 2	8.7	11.7
Maximum Through Torque (Nm)	Option 1		59.4	
Maximum Tillough Torque (Nill)	Option 2		26.1	
Static Efficiency	Option 1		0.201	0.302
Static Efficiency	Option 2		0.113	0.171
Dynamic Efficiency	Option 1		0.264	0.383
Dynamic Eniciency	Option 2		0.167	0.242
Lead Screw Restraining Torque (Nm)	-	-	76	102
Worm Shaft Radial Load (N)			38	30
Maximum Input Speed (rpm)	-		18	00
Gear Case Material			SG	Iron
Weight (kg) – stroke = 150mm	Trans	lating	8	.3
weight (kg) - Stroke = 130mm	Rotating		8.7	
Weight (kg) – per extra 25mm	Trans	lating	0.21	
weight (kg) – per extra zonnin	Rotating		0.11	

CMT0025 Closed Heights



Closed Height 'C'	Threaded End	Top Plate	Clevis End	Fork End	Rod End	
CMT0025	145	145	170	195	192	
Stroke (mm)		With Bellow Boots (B)				
0 - 500	165	165	190	215	212	
501 - 1000	190	190	215	240	237	
1001 - 1500	215	215	240	265	262	
1501 - 2000	245	245	270	295	292	

CMT0025 Stop Nut



Stop nut provides a full power mechanical stop at the end of the lead screw. To be used as a safety feature in emergency conditions.


SN = Stroke + 21mm


Note:

- 1. All dimension in millimetres unless otherwise stated.
- 2. Designs subject to change without notice.

CMT0025-C00









CMR0025-C00







Column Strength



Critical Screw Speed



Bellows Boot



Stroke	1 – 500	501 – 1000	1001 – 1500	1500 – 2000
F	30	55	80	110*

Accessories & Options




50kN

Performance

Screw Jack Model			CM-	0050
Capacity	kl	N	5	0
	Diamete	er (mm)	40	
Lead Screw	Lead	(mm)	9	18
Gear Ratios	Opti	on 1	6	:1
Gear Ratios	Opti	on 2	24	::1
Turn of worm for travel of lead screw	Option 1	1 Turn	1.5mm	3mm
Turn of worm for travel of lead screw	Option 2	4 Turn	1.5mm	3mm
Maximum Input Dawar (kW)	Opti	on 1	(3
Maximum Input Power (kW)	Opti	on 2	0.	55
Start up torque at full load (Nm)	Opti	on 1	56.0	76
Start up torque at rutt toau (NIII)	Opti	on 2	25.5	34.7
Maximum Through Torque (Nm)	Option 1		168.0	
Maximum fillough forque (Nill)	Option 2		76.5	
Static Efficiency	Option 1		0.213	0.314
Static Efficiency	Option 2		0.117	0.172
Dynamic Efficiency	Option 1		0.281	0.398
Dynamic Emclency	Option 2		0.172	0.244
Lead Screw Restraining Torque (Nm)	-	-	210	290
Worm Shaft Radial Load (N)				40
Maximum Input Speed (rpm)	-		18	00
Gear Case Material			SG	ron
Weight (kg) – stroke = 150mm	Trans	lating	19	.5
Weight (kg) - Stroke - 130mm	Rotating		otating 20.2	
Weight (kg) – per extra 25mm	Trans	lating	0.	32
Treight (kg) - per extra zonnin	Rota	iting	0.	19

CMT0050 Closed Heights



Closed Height 'C'	Threaded End	Top Plate	Clevis End	Fork End	Rod End	
CMT0050	195	195	220	260	254	
Stroke (mm)		With Bellow Boots (B)				
0 - 500	215	215	240	280	274	
501 - 1000	235	235	260	300	294	
1001 - 1500	260	260	285	325	319	
1501 - 2000	325	325	350	390	384	

CMT0050 Stop Nut



Stop nut provides a full power mechanical stop at the end of the lead screw. To be used as a safety feature in emergency conditions.


SN = Stroke + 21mm


Note:

- 1. All dimension in millimetres unless otherwise stated.
- 2. Designs subject to change without notice.

CMT0050-C00










CMR0050-C00









Column Strength



Critical Screw Speed



Bellows Boot



	ØA	ØB	ØC	D	Е
CMT0050	50	60*	140	15	15
CMT0050 (Rod End)	42	60	140	15	15
CMR0050	55	60	140	15	15

Stroke	1 – 500	501 – 1000	1001 – 1500	1500 – 2000
F	30	50	75	140**

Accessories & Options




100kN Translating

Performance

Screw Jack Model			CM-0100	
Capacity	k	N	10	00
Lead Screw	Diamete	er (mm)	55	
Lead Screw	Lead	(mm)	12	24
Gear Ratios	Opti	on 1	8	:1
Geal Ratios	Opti	on 2	24	::1
Turn of worm for travel of lead screw	Option 1	1 Turn	1.5mm	3mm
Turn of worm for travel of lead screw	Option 2	4 Turn	2mm	4mm
Maniana Industry David (LAM)	Opti	on 1	3.	75
Maximum Input Power (kW)	Opti	on 2	1.1	25
Chart we to see a fail load (Nes)	Opti	on 1	115.9	156.6
Start up torque at full load (Nm)	Option 2		60.5	81.9
Mayimum Through Targue (Nm)	Option 1		347.7	
Maximum Through Torque (Nm)	Option 2		181.5	
Ct-ti- Efficiency	Option 1		0.206	0.305
Static Efficiency	Option 2		0.132	0.195
Dunania Efficiana	Option 1		0.272	0.388
Dynamic Efficiency	Option 2		0.190	0.271
Lead Screw Restraining Torque (Nm)	-		575	780
Worm Shaft Radial Load (N)			10	00
Maximum Input Speed (rpm)	-		18	00
Gear Case Material			SG	Iron
W-i-b+ (l) -+l 150	Trans	lating	19	2.5
Weight (kg) – stroke = 150mm	Rotating		20	1.2
William Commence	Trans	lating	0.	32
Weight (kg) – per extra 25mm	Rota	ting	0.	19

CMT0100 Closed Heights



Closed Height 'C'	Threaded End	Top Plate	Clevis End	Fork End	Rod End	
CMT0100	250	250	295	354	335	
Stroke (mm)		With Bellow Boots (B)				
0 - 500	270	270	315	374	355	
501 - 1000	290	290	335	394	375	
1001 - 1500	315	315	360	419	400	
1501 - 2000	380	380	425	484	465	

CMT0100 Stop Nut




Stop nut provides a full power mechanical stop at the end of the lead screw. To be used as a safety feature in emergency conditions. SN = Stroke + 37mm


Note:

- 1. All dimension in millimetres unless otherwise stated.
- 2. Designs subject to change without notice.

CMT0100-C00









100kN Rotating


CMR0100-C00









Column Strength



Critical Screw Speed



Bellows Boot



	ØA	ØB	ØC	D	Е
CMT0100	65	85	150	15	15
CMT0100 (Rod End)	58	85	150	15	15
CMR0100	80	85	150	15	15

Stroke	1 – 500	501 – 1000	1001 – 1500	1500 – 2000
F	30	50	75	140*

Accessories & Options




Adjustable Shell Cap

Minimise Axial Backlash When Load Changes Direction

The Anti-Backlash feature provides a reliable method to regulate the axial backlash in a screw jack for applications where there is a reversal of loading from tension to compression. The amount of backlash between the screw and worm gear nut can be adjusted (adjust shell cap) to a desired amount or a practical minimum. To avoid binding and excessive wear do not adjust backlash to less than 0.025mm.


The Anti-Backlash feature also acts as a safety device, providing dual nut load carrying unit, when the worm gear becomes worn.


A visual wear indicator is included as standard on all models and a "feeler" gauge can be used to measure the wear. This can be upgraded to use a sensor on request (consult Power Jacks).



The dimensions for these screw jacks are the same as the standard units except those detailed below.

Model	CMT0010-C0A	CMT0025-C0A	CMT0050-C0A	CMT0100-C0A
А	140	155	205	260
В	32	32	40	50
С	10	22	28	37
ØD	39	55	70	85
ØE	54	70	95	110





Removable cap

to check wear of by eye & gauge

Anti-Backlash Gear

How it works - refer p193


Performance for Anti-Backlash

Model		CMT010-C0A		CMT025-C0A		CMT050-C0A		CMT100-C0A	
Lead Screw	Lead (mm)	5	10	6	12	9	18	12	24
Start-Up Torque at Full Load (Nm)	Gear Ratio Option 1	7.5	10.4	21.9	29.2	62	85	129	175
	Gear Ratio Option 2	3	4.6	9.8	13.0	28	39	67	90
Static Efficiency	Gear Ratio Option 1	0.212	0.305	0.181	0.272	0.192	0.283	0.185	0.274
	Gear Ratio Option 2	0.120	0.173	0.102	0.154	0.105	0.154	0.119	0.175
Dynamic Efficiency	Gear Ratio Option 1	0.275	0.381	0.238	0.344	0.253	0.358	0.245	0.349
	Gear Ratio Option 2	0.174	0.242	0.151	0.218	0.155	0.219	0.171	0.244
Weight (kg) - stroke = 150mm		3.4		8.8		20.2		36.8	

Note: Efficiency values for standard grease lubricated worm gear box and lifting screw.



POWERJACKS



Note: Efficiency values for standard grease lubricated worm gear box and lifting screw. Weight is the same as standard unit.

Linear Movement for Rotationally Unconstrained Loads


The Anti-Rotation feature for translating screw jacks stops the lead screw from rotating without the need for end fixing. This is done by keying the lifting screw.

- Dimensions are the same as the standard translating screw jack
- Compact unit integrates anti-rotation into gearbox
- Standard round cover pipe for easy installation
- Proven industrial anti-rotation design

Model		СМТ	0010	СМТ	0025	СМТ	0050	СМТ	0100
Lead Screw	Lead (mm)	5	10	6	12	9	18	12	24
Start-Up	Gear Ratio Opt 1	7.2	9.9	20.8	27.7	59	80	122	165
Torque at Full Load (Nm)	Gear Ratio Opt 2	3.2	4.4	9.2	12.2	27	37	64	86
Static	Gear Ratio Opt 1	0.224	0.322	0.191	0.287	0.203	0.299	0.196	0.290
Efficiency	Gear Ratio Opt 2	0.124	0.182	0.107	0.162	0.111	0.163	0.125	0.185
Dynamic	Gear Ratio Opt 1	0.291	0.403	0.251	0.364	0.267	0.378	0.258	0.368
Efficiency	Gear Ratio Opt 2	0.184	0.255	0.159	0.230	0.164	0.232	0.180	0.257

Anti-Rotation with Anti-Backlash or Safety Nut

The anti-backlash and safety nut features can be combined with the anti-rotation feature into one screw jack. For this option the anti-rotation device is located in-line with the cover pipe.



Dimensions for Anti-Backlash with Anti-Rotation (Keyed)

Model	CMT0010-CKA	CMT0025-CKA	CMT0050-CKA	CMT0100-CKA
F	Stroke +5	Stroke +10	Stroke +15	Stroke +20
G	30	35.5	40	48
ØН	42.5	60	75	90

Dimensions for Safety Nut with Anti-Rotation (Keyed)

Load Direction - Tension

Model	CMT0010-CKR	CMT0025-CKR	CMT0050-CKR	CMT0100-CKR
F	Stroke +5	Stroke +10	Stroke +15	Stroke +20
G	35	50	59	57
ØН	45	55	70	89

DETAIL A = Same as standard CMT screw jack

Load Direction - Compression

Model	CMT0010-CKS	CMT0025-CKS	CMT0050-CKS	CMT0100-CKS
F	Stroke +5	Stroke +10	Stroke +15	Stroke +20
G	30	35.5	40	48
ØН	42.5	60	75	90

DETAIL A = Same as standard safety nut screw jack with compression load (Refer P44)

Performance for Anti-Rotation with Anti-Backlash or Safety Nut

Model		СМТ	0010	СМТ	0025	СМТ	0050	СМТ	0100
Lead Screw	Lead (mm)	5	10	6	12	9	18	12	24
Start-Up Torque	Gear Ratio Opt 1	8.3	11.5	24.8	33.0	65.6	89.3	136	184
at Full Load (Nm)	Gear Ratio Opt 2	3.8	5.3	10.3	13.7	30.0	40.9	70.3	95.2
Static Efficiency	Gear Ratio Opt 1	0.201	0.290	0.172	0.258	0.182	0.269	0.176	0.263
Static Efficiency	Gear Ratio Opt 2	0.114	0.164	0.097	0.146	0.100	0.146	0.113	0.166
Dynamic	Gear Ratio Opt 1	0.261	0.362	0.226	0.330	0.240	0.340	0.233	0.332
Efficiency	Gear Ratio Opt 2	0.165	0.230	0.143	0.207	0.147	0.208	0.162	0.232
Weight (kg) – stroke = 150mm		3.	15	8.	75	2	0	37	7.3

Note: Efficiency values for standard grease lubricated worm gear box and lifting screw. Anti-Rotation with Safety Nut performance is the same as the Anti-Rotation unit.

Extra Safety for Critical Applications

Power Jacks machine screw jacks can be fitted with a safety nut, which provides 2 safety roles:

- In the event of excessive wear on the nut thread the load will be transferred
 from the standard nut to the safety nut. This will also provide visual wear
 indication as the gap between the safety nut decreases to zero as the
 standard lifting nut wears.
- 2. In the unlikely event of nut thread failure the safety nut will sustain the load. The safety of industrial and human cargo is therefore improved.

There are several configurations for each safety nut device as they only work in one load direction. For this reason when ordering please supply a sketch of your application showing load directions.

Translating Screw Jack with Safety Nut

The dimensions for these screw jacks are the same as the standard units except those detailed below.

Load Direction - Compression (C)

Model	CMT0010	CMT0025	CMT0050	CMT0100
Α	140	155	205	250
В	32	33	40	40
С	10	22	28	40
ØD	39	55	70	85
ØE	54	70	95	85

DETAIL A = As per table above

DETAIL B = Same as standard CMT screw jack (Dimension F, G, ØH not applicable)

Load Direction - Tension

Model	CMT0010	CMT0025	CMT0050	CMT0100
F	Stroke + 5	Stroke + 10	Stroke + 15	Stroke + 20
G	35	50	59	57
ØН	45	55	70	89

DETAIL A = Same as standard CMT screw jack (Dimension A, B, C, \emptyset D, \emptyset E not applicable) DETAIL B = As per table above

Model	CMT0010	CMT0025	CMT0050	CMT0100
Weight (kg)	2.9	8.0	18.6	34.7

Rotating Screw Jack with Safety Nut


The dimensions for these screw jacks are the same as the standard units except those detailed below. A bellows boot hub can be provided on the flanged half of the safety nut.

Model	CMR0010	CMR0025	CMR0050	CMR0100
Α	Stroke +76	Stroke +95	Stroke +140	Stroke +170
В	66.5	75	125	145
С	30	33.5	58	67
D	12	15	20	25
ØE	80	90	115	160
ØF	35	40	55	80
G	4 x Ø11	4 x Ø13.5	4 x Ø18	4 x Ø22
6	Ø57 PCD	Ø65 PCD	Ø85 PCD	Ø120 PCD


PCD = Pitch Circle Diameter


Nut must be orientated correctly for load direction

Model	CMT0010	CMT0025	CMT0050	CMT0100
Weight (kg)	3.3	9.0	21.1	42.2



Top Plate







Capacity	10kN	100kN	50kN	100kN
ØA	Ø80	Ø100	Ø120	Ø150
ØВ	Ø30	Ø40	Ø50	Ø65
С	24	31.5	36.5	42
D	10	12	16	20
ØE	Ø11	Ø13.5	Ø18	Ø22
ØF (PCD)	Ø55	Ø70	Ø85	Ø110
G	8	10	10	12
Н	M6 x 1	M8 x 1.25	M8 x 1.25	M10 x 1.5
Weight (kg)	0.43	0.79	1.5	2.82

PCD = Pitch Circle Diameter

Clevis End








Capacity	10kN	25kN	50kN	100kN
ØA	Ø12	Ø16	Ø20	Ø22
ØB	Ø30	Ø40	Ø50	Ø65
С	63	79.5	991.5	120
D	36	46	60	66
E	18	23	30	33
F	M10 X 1.75 25 Deep	M20 X 2.5 32 Deep	M24 X 3 37 Deep	M36 X 4 42 Deep
G	M6 X 1	M8 X 1.25	M8 X 1.25	M10 X 1.5
Н	15	15	15	20
J	20	30	35	40
Weight (kg)	0.26	0.57	1.0	2.1

Fork End






Capacity	10kN	25kN	50kN	100kN
ØA	Ø12	Ø20	Ø25	Ø35
В	12	20	25	35
С	24	40	50	70
D	48	80	100	144
E	24	40	50	72
F	18	30	36	54
G	62	105	132	188
Н	M12 x 1.75	M20 x 2.5	M24 x 3	M36 x 4
Ø٦	20	34	42	60
K	M6 x 1	M8 x 1.25	M8 x 1.25	M10 x 1.5
L	10	10	15	20
Weight (kg)	0.12	0.55	1.1	2.93

Rod End






Capacity	10kN	25kN	50kN	100kN
А	50	77	94	125
ØB	Ø12	Ø20	Ø25	Ø35
С	18	27	32	42
ØD	Ø34	Ø53	Ø64	Ø82
E	M12 x 1.75	M20 x 1.75	M24 x 2	M36 x 3
F	20	23	48	60
ØG	Ø22	Ø35	Ø42	Ø58
Н	10	16	20	25
J	8	13	17	21
K	19	32	36	50
Weight (kg)	0.096	0.35	0.64	1.3

Note: Lead screw threaded end made to suit rod end.






Trunnion mounts provide a pivot point at the gearbox of the screw jack.


- 2 Pivot Plane Options
- Supplied with or without Trunnion Feet
- Option of Male or Female Trunnions
- Trunnion mounts can be mounted on either side of the screw jacks gearbox


When the trunnions are on the same side as the worm shaft multiple screw jacks can be linked in line with a drive shaft and pivot around a common axis.

The trunnion mounts are connected to the screw jacks gearbox with $4\ \mathrm{bolts}.$

Model	CMT0010 CMR0010	CMT0025 CMR0025	CMT0050 CMR0050	CMT0100 CMR0100	
Α	70	100	140	170	
В	42	70	100	120	
С	34	40	55	70	
D	21	26	35.5	43.5	
ØE	11	13.5	18	22	
F	12	14	20	25	
G	65	85	120	130	
Н	20	30	42.5	47.5	
I	30	36	50	60	
J	134	164	226	265	
K	67	82	113	132.5	
L	149	189	261	300	
М	64.5	83.5	118.5	133	
N	84.5	105.5	142.5	167	
0	90	100	142	190	
ØP	124	156.5	210	242	
ØQ	216.5	251.5	350	446.5	
ØR	20 f7	25 f7	35 f7	45 f7	
ØS	30	35	47	58	
Т	20	20	20	35	
U	2.5	2.5	2.5	5	
ØV	20	25	35	45	
ØW	30	35	47	74	
Х	1.5	1.5	2	2	
Y	16.5	16.5	26	32	
Z	22	26	39	40	








Motor Adaptor







Mount an electric motor to the C-Series screw jack with the extensive range of motor adaptors designed to be used in conjunction with a flexible jaw coupling that connects the motor drive shaft to the screw jacks worm shaft.

Model		CMT0010 CMR0010						
IEC Frame	Α	В	ØC	ØD	Coupling	Available		
63 B5 D140	122.5	10	140	65	19/24 A14 A11	OR		
63 B14 C90	122.5	10	90	65	19/24 A14 A11	S		
71 B5 D160	122.5	10	160	65	19/24 A14 A14	OR		
71 B14 C105	122.5	10	105	65	19/24 A14 A14	S		
80 B5 D200	132.5	12	200	65	19/24 A14 A19	OR		
80 B14 C120	132.5	12	120	65	19/24 A14 A19	S		

Model		CMT0025 CMR0025						
IEC Frame	Α	В	ØC	ØD	Coupling	Available		
71 B5 D160	145.5	10	160	75	19/24 A16 A14	OR		
71 B14 C105	145.5	10	105	75	19/24 A16 A14	S		
80 B5 D200	145.5	12	200	75	19/24 A16 A19	OR		
80 B14 C120	145.5	12	120	75	19/24 A16 A19	S		
90 B5 D200	162.5	12	200	75	24/30 A16 A24	OR		
90 B14 C140	162.5	12	140	75	24/30 A16 A24	S		
100 B5 D250	174.5	12	250	75	24/30 A16 B28	OR		
100 B14 C160	174.5	12	160	75	24/30 A16 B28	5		

Model		CMT0050 CMR0050						
IEC Frame	Α	В	ØC	ØD	Coupling	Available		
80 B5 D200	172.5	12	200	86	19/24 A19 A19	OR		
80 B14 C120	172.5	12	120	86	19/24 A19 A19	OR		
90 B5 D200	192.5	12	200	95	24/30 A19 A24	OR		
90 B14 C140	192.5	12	140	95	24/30 A19 A24	S		
100 B5 D250	192.5	12	250	95	24/30 A19 B28	OR		
100 B14 C160	192.5	12	160	95	24/30 A19 B28	S		
112 B5 D250	192.5	12	250	95	24/30 A19 B28	OR		
112 B14 C160	192.5	12	160	95	24/30 A19 B28	S		
132 B5 D300	222.5	12	300	95	28/38 A19 B38	OR		
132 B14 C200	222.5	12	200	95	28/38 A19 B38	S		

Model		CMT0100 CMR0100							
IEC Frame	Α	В	ØC	ØD	Coupling	Available			
90 B5 D200	208.5	12	200	100	24/30 A25 B24	OR			
90 B14 C140	208.5	12	140	100	24/30 A25 B24	S			
100 B5 D250	218.5	12	250	100	24/30 A25 B28	OR			
100 B14 C160	218.5	12	160	100	24/30 A25 B28	S			
112 B5 D250	218.5	12	250	100	24/30 A25 B28	0R			
112 B14 C160	218.5	12	160	100	24/30 A25 B28	S			
132 B5 D300	239.5	12	300	100	28/38 A25 B38	0R			
132 B14 C200	239.5	12	200	100	28/38 A25 B38	S			

Note:

- 1. NEMA Motor adaptors available on request
- 2. Motor adaptors are for the support of motor weight only
- 3. OR = On Request
- 4. S = Standard

Limit Switches on Cover Pipe

Limit switches can be mounted on the screw jacks cover pipe to signal stroke positions such as end of travel. The switch is triggered by a cam or target disc on the end of the lifting screw.

Features:

- 1. Inductive Proximity Sensors as standard. Others including electro-mechanical and safety rated available on request.
- 2. No contact, so no wearing parts.
- 3. 2 Wire sensor 24VDC for either Normally Closed (NC) or Normally Open (NO) switching.
- 4. Sensor has rugged one-piece Metal housing.
- 5. Optical setting aid
- 6. M12 Plug in connection for fast change-ability.
- 7. Sensor kit includes-sensor, mounting ring, target ring and modification to screw jack cover pipe.
- 8. Switch can have a fixed or adjustable mounting.
- 9. More sensor details in System Components section of Design Guide.





Dimensions


Model	CMT0010	CMT0025	CMT0050	CMT0100
Switch Size	M8	M12	M12	M12
A (mm)	Stroke + 15	Stroke + 15	Stroke + 12	Stroke + 24
B (mm)	50	50	50	50
C (mm)	10	15	15	20
D (mm)	34	36	41	46
E (mm)± 5	78.5	84	89	100
F Adjustment (mm)	5	5	5	5
ØG (mm)	34	49	61	73

Note:

- *Structure dimension (C) only required when screw jack is secured on this face. Not required if secured on opposite face.
- 2. All dimensions in mm unless otherwise stated.
- 3. Dimensions subject to change without notice.







0

0

RLS-51 Rotary cam limit switches can be used as end of travel limit switches with the option of intermediate switches. Each limit switch is individually adjustable over the entire stroke of the screw jack.

- 2 to 8 limit switches in one unit
- Usable revolutions from 4 to 16000
- Switch types include: Changeover (Normally Closed/Open), Normally Closed, Gold or Silver contacts
- Maintenance free rotary cam gearbox
- Enclosure IP66 as standard
- Mounting options for B14 (face), B5 (flange) and B3 (foot)
- Available in 3 voltages 250VAC, 24VDC & 80VDC
- Maximum input speed 1800rpm
- Operating temperature –40°C to +80°C
- Options for potentiometer, anti-condensation heaters and encoders
- Stage technology option to VBG70

Mounted onto a screw jacks free worm shaft as an alternative where cover pipe mounted limit switches are not possible e.g. rotating screw jacks.

More RLS-51 rotary limit switch details in System Components section of Design Guide.

Туре	CMT-0010 CMR-0010	CMT-0025 CMR-0025	CMT-0050 CMR-0050	CMT-0100 CMR-0100
А	109	119	139	154
ØС	86	86	86	100
ØD	120	120	120	160
Е	11	11	11	10

	В	Switches					
Size	Revolutions	2	4	6	8		
1	4.1, 6.5, 11	132	132	157	157		
2	17.5, 29, 48	132	132	157	182		
3	75, 125, 205	132	132	157	182		
4	323, 540, 880	132	157	182	207		
5	1384, 2288, 3735	132	157	182	207		
6	5900, 9800, 16000	157	157	182	207		

		All l	Jnits		
F	G	Н	I	J	K
4	128	153	59	35	18


Note:

- 1. All dimension in millimeters unless otherwise stated.
- 2. Designs subject to change without notice.
- 3. More information on RLS-51 limit switch see System Component section.

E-Series Machine Screw Jack

AVAILABLE IN MANY
STANDARD MODELS
WITH A WIDE RANGE OF
CAPABILITIES, THERE IS
A STANDARD MODEL FOR
ALMOST ANY REQUIREMENT.





Features

Translating Screw





Rotating Screw





Typical Applications

Conventional Machine Screw Jacks are most widely used for intermittent duty cycles, as the screw jack incorporates a precision worm gear set in a rugged casting delivering positive, precise actuation. Available in a comprehensive range of materials and fittings with the option for special designs for specific application requirements. They are used in wide variety of automation applications including those in steel, automotive, communications, civil, defence, energy, glass and aerospace sectors.

Standard Designs

The standard E-Series screw jack is available in translating and rotating screw designs in capacity sizes from 5kN to 2000kN. The design is optimised for performance, function and reliability with a highly flexible platform for customisation in addition to the standard options. The options and accessories (section-7) list is long and varied and allows you to configure a standard design that is just right for your application. These options include Anti-Backlash, Anti-Rotation (Keyed) and Safety Nut designs.

There are 2 types of screw jack housing available:

- Type-1 (Standard Housing) Has bolt-on worm shaft flanges that secure the worm shaft bearings on 25kN to 2000kN models and for 5kN & 10kN designs no flange, no bolt connections at worm shaft and circlips secure bearings.
- Type-2 Has a PCD of tapped bolt holes around the worm shaft ends with the worm shaft bearings secured by circlips. Currently only available for 10kN models.

Special Designs

We can fully customise our screw jacks so that your application can be the best.

Customisation can be anything from a small modification such as an extra bolt hole on an end fitting to a completely new design of screw jack based on our class leading technology.

For more details please see the Special Screw Jack information in Section-8 or contact us today with your requirements. Our team are looking forward to working with you.

Systems

The screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearbox, drive shafts, couplings, plummer blocks and motion control devices.

The use of bevel gearboxes allows the distribution of drive throughout a jacking system. The gearboxes come in 2,3 and 4 way drive types. Bevel Gearbox Section-10 for more details.

Bevel gearboxes and other system components can also be supplied in stainless steel or other corrosion resistant designs. Two of the most popular system configurations are the 'H' and 'U'



configured jacking systems. Remember that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.

If multiple machine screw jacks are connected in a mechanically linked system then the complete system may be considered self-locking. If you would like this checked consult Power Jacks. Alternatively, to be sure, include a brake on the system either as a stand alone device or as a brake motor.

Selecting the Right Screw Jack

Consider all application constraints then choose a product that looks suitable for the intended application. Calculate the power and torque requirements. This is a 5 step process:

- Screw Jack Input Speed (RPM)
- Operating Input Power (kW)
- Operating Input Torque (Nm)
- Screw Jack Start-up Torque (Nm)
- Mechanical Power and Torque Check

POWERJACKS









ADJUSTABLE TABLE STOPS FOR TATA STEEL PRODUCTION

E-Series Machine Screw Jacks are installed on the adjustable table and centring stops for the Rectangular Hollow Sections (RHS) department at TATA Steel Europe 20" pipe mill in Hartlepool.


Automated adjustable stop mechanisms use 50kN E-Series translating machine screw jacks in inverted screw configuration. Each stop mechanism uses a four screw jack system that is driven by one electric motor. The electric motor is positioned in the centre of the system with 2 screw jacks either side.

A bevel gearbox is used to split the drive line to each side from the motor with self-supporting drive shafts (spacer couplings) used to connect each screw jack to the system. One screw jack in each system is fitted with an encoder for speed and position feedback, which is displayed on an electronic display.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.














BRONX METAL SECTION STRAIGHTENER

Variable centre straighteners for moving the centre straightening rollers, end pinch rollers and the landing legs.

A jacking system for each straightening roller has two special design screw jacks and a strengthened gearbox, rated for a 700kN dynamic capacity in compression. The pinch rollers have their position adjusted by two horizontally opposing screw jacks, driven individually by motorised helical gearboxes.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.













MAINTAINING TENSION FOR SUBSEA CABLE LAYING

For submarine cable laying maintaining tension in the cable within required tolerances is critical during the laying process to minimise the risk of cable damage due to cable cores being crushed or the minimum bend radius being exceeded.

To regulate this tension specialist machines are used to handle the cable as it is laid. One such machine is the MAATS 45Te 4-Track Tensioner, which features electro-mechanical screw jacks for the positioning of the lower tracks. This gives this tensioner the advantage of more accurate positioning for better tension control compared to hydraulic only systems.


4 sets of 2 x EMT0500 (500kN) screw jacks arranged in "in-line" jacking system pairs position the 2 lower tracks. With one jacking system installed at each end of the lower tracks. Each jacking system pair is driven by an electric motor with speed and position feedback from an absolute encoder. With 1 motor revolution equal to 0.06mm linear movement, the system can provide some very accurate positioning. By using pairs of screw jacks the track is supported on each side for an even load distribution over the structure.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.









SAFE WORK ACCESS FOR NUCLEAR CONTAINERS

As part of the decommissioning process at Dounreay, Scotland, drums containing waste pass through the import / export section of the cementation facility where they need to be removed from their transportation container. Before this can happen the lid of each container is removed or attached. In order to carry out safe operations while working around the container for the lid removal / attachment process workers need a removable safe access platform that is height adjustable.

The solution was to use a jacking system to lift and lower the access platform over the nuclear containers once in position. The jacking system is configured with 4 x EMT0050 (50kN) screw jacks arranged in an "H-configuration" with each screw jack at a corner of the platform. The screw jacks are equipped with saftey nuts, wear monitors and secondary guides to meet nuclear process safety requirements. They are mechanically linked together using bevel gearboxes, drive shafts and couplings and driven by one electric motor. Normally the drive motor is placed centrally, however for this platform the cross drive shaft and drive motor are placed at one end of the system to provide the central access hole in the platform for the nuclear container.



E-Series - Machine Screw Jacks - Standard Performance

		Mode	l			0005 0005		0010 0010		0025 0025		0050 0050	EMT0100 EMR0100	
Capacit	ty		kN		!	5	1	0	2	5	50		100	
			mm		1	6	2	0	3	0	4	.0	5	5
Lifting Screw ¹	1		Opt	ion	1	2	1	2	1	2	1	2	1	2
	Lead		m	m	3	6	5	10	6	12	9	18	12	24
Gear		Option 1			5	:1	5	:1	6	:1	6	:1	8	:1
Ratios	;		Option 2		20):1	20	1:1	24	i:1	24:0	1:00	24	:1
Turn of		Ratio 0	ption 1	1 Turn	0.6mm	1.2mm	1mm	2mm	1mm	2mm	1.5mm	3mm	1.5mm	3mm
for trave of lifting screw	g	Ratio 0	ption 2	4 Turn	0.6mm	1.2mm	1mm	2mm	1mm	2mm	1.5mm	3mm	2mm	4mm
Max. Inp Power		Gear	Ratio Opt	ion 1	0.	25	0.3	375	1	.5	3	.0	3.	75
(kW)		Gear Ratio Option 2		ion 2	0.	12	0.19		0.375		0.55		1.125	
Start up		Gear	Ratio Opt	ion 1	2.5	3.3	6.8	9.4	19.8	26.3	56	76	115.9	156.5
full load (Nm		Gear	Ratio Opt	ion 2	1.1	1.4	3	4.2	8.7	11.6	25.5	34.7	60.5	81.8
Maximur Torque (1	m Thro Nm) ⁷	ugh			7	.5	20		59		168		34	47
Lead Scr Torque (1	rew Res Nm) ⁵	strainir	ng		8	11	22	30	76	102	210	34.7	575	780
Worm Sh Radial Lo			l		18	30	32	25	38	30	74	40	1000	
Maximur	n Input	t Speed	l (rpm)		18	00	18	00	18	00	18	00	18	00
Gear Cas	se Mate	erial			Alum	inium	Alum	inium	SG	Iron	SG	Iron	SG	Iron
Housing	Type A	Available			,		1 8		,	•	<u> </u>	1		1
Weight (k		_	EM			.3		36		45		4.9		3
		_	EM			36		.6		85		.54		3.8
Weight (leextra 25r		· -	EM EM			08		11 05		21 11		32 19		58 36
		Go	ar Ratio			:1		:1		:1		:1		:1
Gear Ratio	Scre		Static Eff	iciency	0.189	0.291	0.233	0.339	0.201	0.302	0.213	0.314	0.206	0.305
Option 1		Screw J	ack Dynaı		0.252	0.370	0.306	0.424	0.264	0.383	0.281	0.398	0.272	0.388
			ficiency ar Ratio):1		0:424		i:1				
Gear -			ui i\allU 		20	/. I	20	7.1	24	. 1	24:1		24:1	
Ratio Option 2			Static Eff		0.107	0.165	0.130	0.192	0.115	0.171	0.117	0.172	0.132	0.195
	S		ack Dynaı ficiency	mic	0.160	0.235	0.194	0.268	0.167	0.242	0.172	0244	0.190	0.271

Notes 1-3 of 7

- 1. Efficiency values for standard grease lubricated worm gear box and lifting screw.
- 2. For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw.

www.powerjacks.com

E-Series - Machine Screw Jacks - Standard Performance

		Mode	l			0200 0200			EMT0500 EMR0500		EMT1000 EMR1000	EMT1500 EMR1500	EMT2000 EMR2000
Capaci	ty		kN		20	00	300		500		1000	1500	2000
		mm		65		95		120		160	180	220	
Lifting Screw	,1	Lead	Ор	tion	1	2	1	2	1	2	1	1	1
		Leau	m	nm	12	24	16	32	16	32	20	20	24
Gear			Option 1		8	:1	10 2	2/3:1	10 2	2/3:1	12:1	11 2/3:1	18:1
Ratios	5		Option 2	!	24	:1	32	2:1	32	2:1	36:1	N/A	N/A
Turn o worm for trav	ا ۱	Ratio 0	ption 1	1 Turn	1.5mm	3mm	1.5mm	3mm	1.5mm	3mm	1.67mm	1.71	1.33
of liftin screw	ng	Ratio 0	ption 2	4 Turn	2mm	4mm	2mm	4mm	2mm	4mm	6.67mm	N/A	N/A
Max. Inp Power		Gear	Ratio Op	tion 1	3.	75	6	.0	11	.25	18.5	25.3	32.5
(kW)		Gear Ratio Option 2		1.1	25	19		4.5		8.25	N/A	N/A	
Start u		Gear	Ratio Op	tion 1	263.8	343	480	618	904	1113	2025	3655	3895
full load (Nr	m)²	Gear	Ratio Op	tion 2	137	179	284	365	504	618	1119	N/A	N/A
	Maximum Through Torque (Nm) ⁷			39	96	1440		27	12	6075	7310	7790	
Lead Sci Torque (estraini	ng		1300	1705	5645	6975	5645	6975	14890	24610	39995
Worm SI Radial L			n		16	00	21	70	21	90	2220	4450	7800
Maximui	m Inpu	ut Spee	d (rpm)		18	00	18	100	18	100	1800	1000	600
Gear Ca	se Mat	terial			Ste	eel	St	eel	St	eel	Steel	Steel	Steel
Housing		Availab	le			l		1	1		1	1	1
Weight (- stroke	kg) =		EM	Г	42	2.4	92	2.4	18	3.7	459.1	563	1172
150mm			EMF	?	49.	.58	113	3.78	2:	24	560.4	708	1534
Weight (r	EM	Г	0.	84	1.	55	2.	48	4.11	5.8	9
extra 25	mm		EMF	?	0.	52	1.	13	1.	94	3.38	4.4	6.5
		Gea	ar Ratio		8	:1	10 2	2/3:1	10 2	2/3:1	12:1	11 2/3:1	18:1
Gear Ratio Option	Scre	w Jack	Static Ef	ficiency	0.181	0.279	0.149	0.232	0.132	0.215	0.131	0.112	0.109
1	S		ack Dyna iciency	amic	0.242	0.357	0.205	0.308	0.181	0.284	0.178	0.155	0.151
Gear		Gea	ar Ratio		24	:1	32	2:1	32:1		36:1	N/A	N/A
Ratio Option	Scre	w Jack	Static Ef	ficiency	0.116	0.178	0.084	0.131	0.079	0.129	0.079	N/A	N/A
2	S		ack Dyna iciency	amic	0.169	0.250	0.128	0.192	0.120	0.188	0.123	N/A	N/A

Notes 4-7 of 7


- 4. All E-Series screw jacks have grease lubricated gearbox and lead screw as standard.
- 5. Torque required to prevent the lead screw or lead nut from rotating if no anti-rotation device fitted to screw jack.
- 6. Radial force applied midway along worm shaft key at 90° to key.
- 7. Maximum transmittable torque through worm shaft, not through gear set.


www.powerjacks.com



Upright EMT0005-U00

Inverted EMT0005-I00





Performance

Closed Height

Model			EMT EMR	0005 0005	
Capacity		kN	5		
	Diame	ter (mm)	1	6	
Lifting Screw	Lead	Option	1	2	
	Leau	mm	3	6	
	Gear Ratio		5:	:1	
Gear Ratio Option 1	Static Effic	iency	0.189	0.291	
	Dynamic E	fficiency	0.252	0.370	
	Gear Ratio		20:1		
Gear Ratio Option 2	Static Effic	iency	0.107	0.165	
	Dynamic E	fficiency	0.160	0.235	
Max. Input	Gear Ratio	Option 1	0.25		
power (kW)	Gear Ratio	Option 2	0.12		
Start up torque	Gear Ratio	Option 1	2.5	3.3	
(Nm)	Gear Ratio	Option 2	1.1	1.4	


Model	Model				
Capacity	kN		5		
Lifting Screw I	3	6			
Turn of worm for	Gear Ratio 1	1 Turn	0.6mm	1.2mm	
travel of lifting screw	Gear Ratio 2	4 Turn	0.6mm	1.2mm	
Maximum Thre	7.5				
Lifting Screw F	8	11			
Worm Shaft M (N)	aximum Radial I	_oad	180		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Alum	inium	
\\\ainht (l.a) a			EMT	1.3	
weight (kg) - S	stroke = 150mm		EMR	1.36	
Waight (kg)	or outro 25mm	troko	EMT	0.08	
Weight (kg) - p	stroke	EMR	0.03		
Note: All dimension	on in millimetres un	less otherv	vise stated.		


Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	


Upright EMR0005-U00

Inverted EMR0005-I00










Closed Height & Bellows Boots


Column Strength

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0005	95	40	95	40	115	60	114	59	117	62
Stroke (mm)		EMT0005 with Bellows Boots								
1-150	95	70	95	70	115	90	114	89	132	107
151-300	120	90	120	90	140	110	139	109	157	127
301-600	120	90	120	90	140	110	139	109	157	127



Model	А	В	D	Е	G
EMT0005	25	60	13	13	100
	*				

Stroke	1-150	151-300	301-600	601-900	901-1050
EMT0005	10	20	30	-	-




Note

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.



Upright EMT0010-U00

31.83 Ø 14 h8 KEY 25 x 5 x 5 LHS 130 150 100 20 65 75 35 RHS 35 102 M12 x 1.75 24 STROKE + 9 Ø 33

Inverted EMT0010-I00




Performance

Model				0010 0010	
Capacity		kN	10		
	Diame	ter (mm)	20		
Lifting Screw	Lead	Option	1	2	
	Leau	mm	5	10	
	Gear Ratio		5	:1	
Gear Ratio Option 1	Static Effic	iency	0.233	0.339	
	Dynamic E	fficiency	0.306	0.424	
	Gear Ratio		20:1		
Gear Ratio Option 2	Static Effic	iency	0.130	0.192	
	Dynamic E	fficiency	0.194	0.268	
Max. Input	Gear Ratio	Option 1	0.375		
power (kW)	Gear Ratio	Option 2	0.19		
Start up torque	Gear Ratio	Option 1	6.8	9.4	
(Nm)	Gear Ratio	Option 2	3	4.2	


Model	EMT0010 EMR0010				
Capacity	kN		10		
Lifting Screw L	5	10			
Turn of worm for travel of lifting screw	Gear Ratio 1	1 Turn	1mm	2mm	
	Gear Ratio 2	4 Turn	1mm	2mm	
Maximum Thro	20				
Lifting Screw F	Restraining Torq	ue (Nm)	22	30	
Worm Shaft M (N)	aximum Radial l	_oad	325		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Mat	terial		Aluminium		
Woight (kg)	traka - 150mm		EMT	2.36	
weight (kg) - s	troke = 150mm		EMR 2.6		
Woight (kg) p	or outro 25mm	rtroleo	EMT	0.11	
vveigiii (kg) - p	er extra 25mm s	stroke	EMR	0.05	
loto: All dimensio	n in millimetree un	loop others	ina stated		

Note: All dimension in millimetres unless otherwise stated. Designs subject to change without notice


Closed Height



Upright EMR0010-U00



Inverted EMR0010-I00




Closed Height & Bellows Boots

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0010	125	45	125	45	145	65	148	98	150	70
Stroke (mm)	EMT0010 with Bellows Boots									
0-150	125	75	125	75	145	95	148	98	165	115
151-300	130	95	130	95	150	115	153	118	170	135
301-600	140	95	140	95	160	115	163	118	180	135
751-1000	-	-	-	-	-	-	-	-	-	-

Model	А	В	D	Е	G
EMT0010	30	70	15	15	110

Stroke	1-150	151-300	301-600	601-900	901-1050
EMT0010	8	20	35	-	-



Note:

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply


- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.

- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

Column Strength

Fixed



Pinned


10kN MACHINE SCREW JACK

Fixed

Upright EMT0010-**T**00

112 31.83 31.75 Ø14 h8 (4x) Ø 8.50 HS THE 35 150 82 70 35 75 35 KEY 25 x 5 x 5 128 Ø20 M12 x 1.75 24 Ø46 P.C.D. 125 0 90 40.13 (4x) M6 x 1 x 10 DEEP STROKE +9 Ø33.

Inverted EMT0010-H00



Ø32 10

Ø20

\Box					
re.	rto	rm	а	nc	:е

Model (Housing		EMT0010 EMR0010			
Capacity		kN	10		
	Diame	ter (mm)	2	0	
Lifting Screw	Lead	Option	1	2	
	Leau	mm	5	10	
	Gear Ratio		5	:1	
Gear Ratio Option 1	Static Effic	iency	0.233	0.339	
·	Dynamic E	fficiency	0.306	0.424	
	Gear Ratio		20:1		
Gear Ratio Option 2	Static Effic	iency	0.130	0.192	
	Dynamic E	fficiency	0.194	0.268	
Max. Input	Gear Ratio	Option 1	0.375		
power (kW)	Gear Ratio	Option 2	0.	19	
Start up torque	Gear Ratio	Option 1	6.8	9.4	
(Nm)	Gear Ratio	Option 2	3	4.2	

Model (Housi	EMT0010 EMR0010					
Capacity	kN		1	0		
Lifting Screw I	Lead (mm)		5	10		
Turn of	Gear Ratio 1	1 Turn	1mm	2mm		
travel of lifting screw	Gear Ratio 2	1mm	2mm			
Maximum Thr	20					
Lifting Screw I	Restraining Torq	ue (Nm)	22	30		
Worm Shaft M (N)	aximum Radial	Load	325			
Maximum Inpi	ut Speed (rpm)		18	1800		
Gear Case Ma	terial		Alum	inium		
\\/a:abt(.a)	EMT	2.36				
Weight (kg) - s	EMR	2.6				
Waight (kg)	EMT	0.11				
vveigiit (kg) - p	er extra 25mm :	stroke	EMR	0.05		

Note: All dimension in millimetres unless otherwise stated. Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Ø46 P.C.D.

40.13 39.87

M12 x 1.75


Closed Height


(4x) M6 x 1 x 10 DEEP

86

Upright EMR0010-T00

Inverted EMR0010-H00





Closed Height & Bellows Boots

Column Strength

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0010	125	45	125	45	145	65	148	98	150	70
Stroke (mm)	EMT0010 with Bellows Boots									
0-150	125	75	125	75	145	95	148	98	165	115
151-300	130	95	130	95	150	115	153	118	170	135
301-600	140	95	140	95	160	115	163	118	180	135
751-1000	-	-	-	-	-	-	-	-	-	-

Model	А	В	D	Е	G
EMT0010	30	70	15	15	110
			ſ		
Stroke	1-150	151-300	301-600	601-900	901-1050
EMT0010	8	20	35	-	-





- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.





Upright EMT0025-U00

135 43.28 43.23 7 LHS 27 081

KEY 30 x 5 x 5/


•

RHS


Ø 16 h8

90

27.



Inverted EMT0025-I00



Performance

Model	EMT0025 EMR0025				
Capacity		kN	2	5	
	Diame	ter (mm)	3	0	
Lifting Screw	Lead	Option	1	2	
	Leau	mm	6	12	
	Gear Ratio		6	:1	
Gear Ratio Option 1	Static Effic	iency	0.201	0.302	
	Dynamic E	fficiency	0.264	0.383	
	Gear Ratio		24:1		
Gear Ratio Option 2	Static Effic	iency	0.115	0.171	
	Dynamic E	fficiency	0.167	0.242	
Max. Input	Gear Ratio	Option 1	1.5		
power (kW)	Gear Ratio	Option 2	0.375		
Start up torque	Gear Ratio	Option 1	19.8	26.3	
(Nm)	Gear Ratio	Option 2	8.7	11.6	


Model	EMT0025 EMR0025				
Capacity	kN		25		
Lifting Screw l	_ead (mm)		6	12	
Turn of worm for	Gear Ratio 1	1 Turn	1mm	2mm	
travel of lifting screw	Gear Ratio 2	4 Turn	1mm	2mm	
Maximum Thre	59				
Lifting Screw F	Restraining Torq	ue (Nm)	76 102		
Worm Shaft M (N)	aximum Radial l	_oad	380		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Aluminium		
Waight (kg)	traka - 150mm		EMT	8.45	
Weight (kg) - s	EMR	8.85			
Waight (kg)	EMT	0.21			
weight (kg) - p	er extra 25mm s	stroke	EMR 0.11		
Note: All dimension	n in millimetres un	less other	vice stated		


Note: All dimension in millimetres unless otherwise stated Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EMR0025-U00

Inverted EMR0025-I00






Closed Height & Bellows Boots


Column Strength

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0025	145	55	145	55	170	80	194	104	190	100
Stroke (mm)	EMT0025 with Bellows Boots									
1-300	145	80	145	80	170	105	194	129	205	140
301-600	145	80	145	80	170	105	194	129	205	140
601-1050	170	105	170	105	195	130	219	154	230	165
1051-1500	195	130	195	130	220	155	244	179	255	190

Model	А	В	D	E	G
EMT0025	40	90	15	23	120

Stroke	1-150	151-301	301-600	601-1050	1051-1500
EMT0025	8	20	30	50	70






Note


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.

- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.










Upright EMT0050-U00

Inverted EMT0050-I00



Ø 60.3






Performance

Model	Model					
Capacity		kN	5	0		
	Diame	ter (mm)	4	.0		
Lifting Screw	Lead	Option	1	2		
	Leau	mm	9	18		
	Gear Ratio		6	:1		
Gear Ratio Option 1	Static Efficiency		0.213	0.314		
	Dynamic E	fficiency	0.281	0.398		
	Gear Ratio		24:1			
Gear Ratio Option 2	Static Effic	iency	0.117	0.172		
	Dynamic E	fficiency	0.172	0.244		
Max. Input	Gear Ratio	Option 1	3.0			
power (kW)	Gear Ratio Option 2		0.	55		
Start up torque	Gear Ratio	Option 1	56	76		
at full load (Nm)	Gear Ratio	Option 2	25.5	34.7		

Model	EMT EMR				
Capacity	kN		5	0	
Lifting Screw (mm)		9	18	
Turn of worm for travel of	Gear Ratio 1	1 Turn	1.5mm	3mm	
lifting screw	Gear Ratio 2	4 Turn	1.5mm	3mm	
Maximum Thro	168				
Lifting Screw F	Restraining Torq	ue (Nm)	210	290	
Worm Shaft M (N)	74	40			
Maximum Inpu	ıt Speed (rpm)		1800		
Gear Case Mat		SG Iron			
Waight (kg)	traka – 150mm		EMT	14.9	
Weight (kg) - stroke = 150mm			EMR	16.54	
Woight (kg) p	er extra 25mm s	troko	EMT	0.32	
weight (kg) - p	er extra 25mm s	stroke	EMR	0.19	
lote: All dimension in millimetres unless otherwise stated					


Note: All dimension in millimetres unless otherwise stated. Designs subject to change without notice


Closed Height



Upright EMR0050-U00

Inverted EMR0050-I00






Closed Height & Bellows Boots

Fork End Rod End Top Plate Clevis End Closed Height "C" Upright Upright Inverted Upright Inverted Upright Inverted Upright EMT0050 Stroke (mm) EMT0050 with Bellows Boots 1-150 151-300 301-600 601-1050 1051-1500

Model	А	В	D	Ε	G
EMT0050	50	115	15	31	140

Stroke	1-150	151-300	301-600	601-1050	1051-1500
EMT0050	8	20	30	50	70




Note


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply
- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.


Column Strength







Upright EMT0100-U00

Inverted EMT0100-I00







Performance

Closed Height

Model				0100 0100
Capacity		kN	10	00
	Diame	ter (mm)	5	5
Lifting Screw	Lead	Option	1	2
	Leau	mm	12	24
	Gear Ratio		8:	:1
Gear Ratio Option 1	Static Efficiency		0.206	0.305
	Dynamic E	fficiency	0.272	0.388
	Gear Ratio		24:1	
Gear Ratio Option 2	Static Effic	iency	0.132	0.195
	Dynamic E	fficiency	0.190	0.271
Max. Input	Gear Ratio Option 1		3.75	
power (kW)	Gear Ratio Option 2		1.1	25
Start up torque	Gear Ratio	Option 1	115.9	156.5
at full load (Nm)	Gear Ratio	Option 2	60.5	81.8


Model	EMT EMR				
Capacity	kN		10	00	
Lifting Screw (mm)		12	24	
Turn of worm for travel of lifting screw	Gear Ratio 1	1 Turn	1.5mm	3mm	
	Gear Ratio 2	4 Turn	2mm	4mm	
Maximum Thr	347				
Lifting Screw F	ue (Nm)	575	780		
Worm Shaft M (N)	1000				
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma		SG Iron			
\\\ainht (l.a) a	t		EMT	24.3	
vveignt (kg) - S	troke = 150mm		EMR	28.8	
Waight (kg)	or outro 25mm	troko	EMT	0.58	
vveignt (kg) - p	er extra 25mm s	ыоке	EMR	0.36	
Note: All dimension in millimetres unless otherwise stated.					


Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EMR0100-U00

Inverted EMR0100-I00






Closed Height & Bellows Boots


Column Strength

Closed	Thread	ed End	Top I	Plate	Clevi	s End	Fork	End	Rod	End
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0100	200	80	200	80	245	125	302	182	283	163
Stroke (mm)	EMT0100 with Bellows Boots									
1-300	200	105	200	105	245	150	302	207	298	203
301-600	200	130	200	130	245	175	302	232	298	228
601-1050	225	130	225	130	270	175	327	232	323	228
1051-1500	250	155	250	155	295	200	352	257	348	253

Model	А	В	D	Е	G
EMT0100	65	136	15	31	150

Stroke	1-300	301-600	601-1050	1051-1500
EMT0100	20	30	50	70






Note


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply


- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.






Upright EMT0200-U00



Inverted EMT0200-I00



Performance

Model				0200 0200
Capacity		kN	20	00
	Diame	ter (mm)	6	5
Lifting Screw	Lead	Option	1	2
	Leau	mm	12	24
	Gear Ratio		8	:1
Gear Ratio Option 1	Static Efficiency		0.181	0.279
	Dynamic Efficiency		0.242	0.357
	Gear Ratio		24:1	
Gear Ratio Option 2	Static Effic	iency	0.116	0.178
	Dynamic E	fficiency	0.169	0.250
Max. Input	Gear Ratio Option 1		3.75	
power (kW)	Gear Ratio Option 2		1.1	25
Start up torque	Gear Ratio	Option 1	263.8	343
at full load (Nm)	Gear Ratio	Option 2	137	179

Model	EMT EMR				
Capacity	kN		20	00	
Lifting Screw (mm)		12	24	
Turn of worm for travel of lifting screw	Gear Ratio 1	1 Turn	1.5mm	3mm	
	Gear Ratio 2	4 Turn	2mm	4mm	
Maximum Thr	396				
Lifting Screw F	Restraining Torq	ue (Nm)	1300	1705	
Worm Shaft M (N)	16	00			
Maximum Inpu	ut Speed (rpm)		18	00	
Gear Case Ma	Steel				
Woight (kg)	traka – 150mm		EMT	42.4	
weight (kg) - S	troke = 150mm		EMR	49.58	
Waight (kg)	or outro 25mm	troko	EMT	0.84	
weight (kg) - p	er extra 25mm s	stroke	EMR	0.52	
lote: All dimension in millimetres unless otherwise stated					


Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	


Closed Height

Upright EMR0200-U00

Inverted EMR0200-I00








Closed Height & Bellows Boots

Column Strength

Closed	Thread	ed End	Top I	Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EMT0200	265	95	265	95	310	140	400	230	367	197	
Stroke (mm)		EMT0200 with Bellows Boots									
1-300	265	120	265	120	310	165	400	255	387	242	
301-600	265	145	265	145	310	190	400	280	387	267	
601-1050	290	145	290	145	335	190	425	280	412	267	
1051-1500	315	170	315	170	360	215	450	305	437	292	

Model	А	В	D	Е	G
EMT0200	75	165	20	20	165
Stroke	1 200	201 /	00 /0	1 1050	1051 15



Note

EMT0200


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.


 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).


 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.







Upright EMT0300-U00





Inverted EMT0300-I00





Performance

Model		EMT0300 EMR0300			
Capacity		kN	30	00	
	Diame	ter (mm)	9	5	
Lifting Screw	Lead	Option	1	2	
	Leau	mm	16	32	
	Gear Ratio		10 2	/3:1	
Gear Ratio Option 1	Static Effic	iency	0.149	0.232	
	Dynamic E	fficiency	0.205	0.308	
	Gear Ratio		32:1		
Gear Ratio Option 2	Static Effic	iency	0.084	0.131	
	Dynamic E	fficiency	0.128	0.192	
Max. Input	Gear Ratio	Option 1	6.0		
power (kW)	Gear Ratio	Option 2	1	.9	
Start up torque	Gear Ratio	Option 1	480	618	
(Nm)	Gear Ratio	Option 2	284	365	


Model		0300 0300			
Capacity	kN		30	00	
Lifting Screw (mm)		16	32	
Turn of	Gear Ratio 1	1 Turn	1.5mm	3mm	
travel of lifting screw	Gear Ratio 2	4 Turn	2mm	4mm	
Maximum Thro	ough Torque (Nn	n)	1440		
Lifting Screw F	Restraining Torq	ue (Nm)	2805 3610		
Worm Shaft M (N)	aximum Radial l	_oad	21	70	
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Steel		
\\\ainht (l.a) a	t		EMT	92.4	
weight (kg) - S	troke = 150mm		EMR	113.78	
Waight (kg)	or outro 25mm	stroko	EMT	1.55	
vveignt (kg) - p	er extra 25mm s	Stroke	EMR	1.13	
Note: All dimension	on in millimetres un	less otherv	vise stated.		


Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EMR0300-U00

Inverted EMR0300-I00





Closed Height & Bellows Boots

Column Strength

Closed	Thread	ed End	Top I	Plate	Clevi	s End	Fork	End	Rod	End
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0300	325	115	325	115	365	155	on re	quest	on request	
Stroke (mm)		EMT0300 with Bellows Boots								
1-300	325	140	325	140	365	180	-	-	-	-
301-600	325	165	325	165	365	205	-	-	-	-
601-1050	350	165	350	165	390	205	-	-	-	-
1051-1500	375	190	375	190	415	230	-	-	-	-

Model	А	В	ı	כ	Е		3
EMT0300	110	220	2	:0	20	19	91
Stroke	1-300	301-6	00	601	-1050	1051-1	500
EMT0300	20	30			50	70	


Note:

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.


 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.




300kN MACHINE SCREW JACK





500kN

Upright EMT0500-U00

Inverted EMT0500-I00







Performance

Closed Height

Model	Model					
Capacity		kN	50	00		
	Diame	ter (mm)	12	20		
Lifting Screw	Lead	Option	1	2		
	Leau	mm	16	32		
	Gear Ratio		10 2	/3:1		
Gear Ratio Option 1	Static Effic	iency	0.132	0.215		
	Dynamic E	fficiency	0.181	0.284		
	Gear Ratio		32	2:1		
Gear Ratio Option 2	Static Effic	iency	0.079	0.129		
	Dynamic E	fficiency	0.120 0.188			
Max. Input	Gear Ratio	Gear Ratio Option 1 11.25				
power (kW)	Gear Ratio	Option 2	4	.5		
Start up torque	Gear Ratio	Option 1	904	1113		
(Nm)	Gear Ratio	Option 2	504	618		

Model	EMT EMR				
Capacity	kN		500		
Lifting Screw (mm)		16	32	
Turn of worm for	Gear Ratio 1	1 Turn	1.5mm	3mm	
travel of lifting screw	Gear Ratio 2	4 Turn	2mm	4mm	
Maximum Thre	n)	2712			
Lifting Screw F	Restraining Torq	ue (Nm)	5645 6975		
Worm Shaft M (N)	aximum Radial l	_oad	21	90	
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Steel		
\\\ainht (l.a) a	t		EMT	183.7	
weight (kg) - S	troke = 150mm		EMR	224	
Waight (kg)	or outro 25mm	troko	EMT	2.48	
vveignt (kg) - p	er extra 25mm s	ыоке	EMR	1.94	
Note: All dimension	on in millimetres un	less otherv	vise stated.		


Note: All dimension in millimetres unless otherwise stated Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	


Upright EMR0500-U00


435 135.07 135.00 175 200 100 150 230 6 HOLES Ø33 RHS ON 220 PCD 99 KEY 60 x 12 x 8 Ø40 h8 535

Ø90



Inverted EMR0500-I00






Closed Height & Bellows Boots


Closed	Thread	led End	Тор	Plate	Clevi	s End	F
Height "C"	Unright	Inverted	Unright	Inverted	Unright	Inverted	Unric

Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0500	390	150	390	150	440	200	on re	quest	on re	quest
Stroke (mm)	EMT0500 with Bellows Boots									
1-300	390	175	390	175	440	225	-	-	-	-
301-600	415	200	415	200	465	250	-	-	-	-
601-1050	440	225	440	225	490	275	-	-	-	-
1051-1500	465	250	465	250	515	300	_	_	_	_

Model	А	В	D	Е	G
EMT0500	150	285	20	45	210

Stroke	1-300	301-600	601-1050	1051-1500
EMT0500	20	30	50	70





Fork End

Rod End

Note


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.


 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.






Upright EMT1000-U00

Inverted EMT1000-I00





Performance

Closed Height

Model	EMT1000 EMR1000			
Capacity		kN	1000	
	Diame	ter (mm)	160	
Lifting Screw	Lead	Option	1	
	Leau	mm	20	
	Gear Ratio	1	12:1	
Gear Ratio Option 1	Static Effic	ciency	0.131	
	Dynamic E	fficiency	0.178	
	Gear Ratio)	36:1	
Gear Ratio Option 2	Static Effic	ciency	0.079	
	Dynamic E	fficiency	0.123	
Max. Input	Gear Ratio	Option 1	18.5	
power (kW)	Gear Ratio	Option 2	8.25	
Start up torque	Gear Ratio	Option 1	2025	
(Nm)	Gear Ratio	Option 2	1119	

Model	EMT1000 EMR1000			
Capacity	kN	10	00	
Lifting Screw (20			
Turn of worm for	Gear Ratio 1	1 Turn	1.67	mm
travel of lifting screw	Gear Ratio 2	tio 2 4 Turn 6.67mr		mm
Maximum Thre	6075			
Lifting Screw F	14890			
Worm Shaft M (N)	2220			
Maximum Inpu	1800			
Gear Case Ma	Steel			
Weight (kg) - stroke = 150mm			EMT	459.1
			EMR	560.4
Weight (kg) - per extra 25mm stroke			EMT	4.11
			EMR	3.38
Note: All dimension in millimetres unless otherwise stated.				


Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	


POWERJACKS

Upright EMR1000-U00

Inverted EMR1000-I00







Closed Height & Bellows Boots


Column Strength

Fixed

Closed	Thread	ed End	Top I	Plate	Clevi	s End	Fork	End	Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT1000	560	260	560	260	625	325	on re	quest	on re	quest
Stroke (mm)		EMT1000 with Bellows Boots								
1-300	560	260	560	260	625	325	-	-	-	-
301-600	560	260	560	260	625	325	-	-	-	-
601-1050	585	285	585	285	650	350	-	-	-	-
1051-1500	610	310	610	310	675	375	-	-	-	-

Model	А	В	D	Е	G
EMT1000	200	220	20	20	244

Stroke	1-300	301-600	601-1050	1051-1500
EMT1000	20	30	50	70




Note

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.

- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.



Pinned

1000kN MACHINE SCREW JACK


Fixed


1500kN

1500kN Translating

Upright EMT1500-U00

Inverted EMT1500-I00





Performance

Model			EMT1500 EMR1500
Capacity		kN	1500
	Diame	ter (mm)	180
Lifting Screw	Lead	Option	1
	Leau	mm	20
	Gear Ratio		11.67:1
Gear Ratio Option 1	Static Effic	iency	0.112
Option 1	Dynamic Efficiency		0.155
	Gear Ratio		on request
Gear Ratio Option 2	Static Effic	iency	on request
	Dynamic E	fficiency	on request
Max. Input	Gear Ratio	Option 1	25.3
power (kW)	Gear Ratio	Option 2	on request
Start up torque	Gear Ratio	Option 1	3655
(Nm)	Gear Ratio	Option 2	on request

Model		EMT EMR			
Capacity	kN		15	00	
Lifting Screw (mm)		2	0	
Turn of worm for	Gear Ratio 1	1 Turn	1.71mm		
travel of lifting screw	Gear Ratio 2	quest			
Maximum Thr	n)	7310			
Lifting Screw F	Restraining Torq	ue (Nm)	24610		
Worm Shaft M (N)	aximum Radial l	_oad	4450		
Maximum Inpu	ut Speed (rpm)		1000		
Gear Case Ma	terial		Steel		
Waight (kg)	troke = 150mm		EMT	563	
weight (kg) - S	EMR	708			
Waight (kg)	or ovtra 25mm	stroko	EMT	5.80	
vveigitt (kg) - p	er extra 25mm s	stroke	EMR	4.40	
Moto: All dimonoid	n in millimetree un	loop othory	viae stated		

Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice

Threaded Er	
Top Plate	
Clevis End	
Fork End	
Rod End	

Inverted


Upright

Upright EMR1500-U00

POWERJACKS

420 190.58 190.50 150 210 (6x) Ø51 KEY 18 x 11 x 88 LHS 82.5 620 580 510 82.5 255 290 RHS (6x) Ø 51 ON 330 P.C.D. 205 Ø65h8 530 Ø140 40 Ø 180 340 + STROKE Ø240 Ø420 80 Ø 165 P.C.D. (6x) M16 x 2 x 28 DEEP 440 195. 194.

Inverted EMR1500-I00




Closed Height & Bellows Boots

Ø295

Closed	Top I	Plate	Clevi	s End	Fork	End	Rod	End		
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT1500	620	230	620	230	760	370	on re	quest	on request	
Stroke (mm)		EMT1500 with Bellows Boots								
1-500	620	230	620	230	760	370	-	-	-	-
501-1000	630	255	630	255	770	395	-	-	-	-
1001-2000	665	290	665	290	805	430	-	-	-	-
2001-4000	745	370	745	370	885	510	-	-	-	-

Model	А	В	D	Е	G
EMT1500	215	410	25	25	480

Stroke	1-500	751-1000	1001-2000	2001-4000
EMT1500	20	45	80	160



Note:

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.


 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

Column Strength

 $1.7.10^4$ $1.6.10^4$ $1.5.10^4$ $1.4.10^4$ $1.3.10^4$ $1.1.10^4$ 1.10^4 9.10^4 8.10^4 7.10^4 6.10^4 4.10^4





6000


1.104 1.2.10 2000kN Translating

Upright EMT2000-U00

Inverted EMT2000-I00







Performance


Model			EMT2000 EMR2000
Capacity		kN	2000
	Diame	ter (mm)	220
Lifting Screw	Lead	Option	1
	Leau	mm	24
	Gear Ratio		18:1
Gear Ratio Option 1	Static Effic	iency	0.109
	Dynamic Efficiency		0.151
	Gear Ratio		on request
Gear Ratio Option 2	Static Effic	Static Efficiency	
	Dynamic E	fficiency	on request
Max. Input	Gear Ratio	Option 1	32.5
power (kW)	Gear Ratio	Option 2	on request
Start up torque	Gear Ratio	Option 1	3895
at full load (Nm)	Gear Ratio	Option 2	on request

Model	EMT: EMR				
Capacity	kN		2000		
Lifting Screw (mm)		2	4	
Turn of worm for	Gear Ratio 1	1 Turn	1.33mm		
travel of lifting screw	Gear Ratio 2	4 Turn	on re	quest	
Maximum Through Torque (Nm)			7790		
Lifting Screw F	Restraining Torq	ue (Nm)	39995		
Worm Shaft M (N)	aximum Radial l	_oad	78	00	
Maximum Inpu	ut Speed (rpm)		600		
Gear Case Ma	terial		Steel		
Waight (kg)	traka – 150mm		EMT	1172	
Weight (kg) - s		EMR	1534		
Woight (kg)	stroko	EMT	9.00		
weight (kg) - p	er extra 25mm s	Stroke	EMR	6.50	

Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice


Closed Height




POWERJACKS

Upright EMR2000-U00

Inverted EMR2000-I00






Closed Height & Bellows Boots


Column Strength

Closed	Thread	led End	Top Plate Clevis End Fork End					Rod End		
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT2000	690	280	690	280	880	470	on re	on request on request		quest
Stroke (mm)		EMT2000 with Bellows Boots								
1-500	690	280	690	280	880	470	-	-	-	-
501-1000	690	280	690	280	880	470	-	-	-	-
1001-2000	695	285	695	285	885	475	-	-	-	-
2001-4000	795	350	795	350	985	540	-	-	-	-

Model	А	В	D	Е	G
EMT2000	265	396	25	25	470

Stroke	1-500	751-1000	1001-2000	2001-4000
EMT2000	25	40	75†	145†







Note:

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply
- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.





3

E-Series Metric Machine Screw Jack

PERFORMANCE
ENHANCED VARIANTS
TO SOLVE SPECIFIC
APPLICATION
REQUIREMENTS

Variants



Minimise Axial Backlash for Reversing Loads

The Anti-Backlash feature provides a reliable method to regulate the axial backlash in a screw jack for applications where there is a reversal of loading from tension to compression. The amount of backlash between the screw and worm gear nut can be adjusted (adjust shell cap) to a desired amount or a practical minimum. To avoid binding and excessive wear do not adjust backlash to less than 0.025mm.

The Anti-Backlash feature also acts as a safety device, providing dual nut load carrying unit, when the worm gear becomes worn.

A visual wear indicator is available on request for all models and a "feeler" gauge can be used to measure the wear. This can be upgraded to use a sensor for wear monitoring. Consult Power Jacks for either option.



Dimensions

Upright Inverted Tension Compression Load Load Load A C How it works - refer p193

The dimensions for these screw jacks are the same as the standard units except those detailed below.

Model	EMT0005	ЕМТ	0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
Туре	1	1	2	1	1	1	1	1	1	1	1	1
А	95	125	125	145	185	200	265	340	415	585	833	910
В	20	24	24	30	35	40	55	65	90	125	160	170
С	65	86	90	103.5	138	146.5	195	250	295	415	652	709
D	Stroke + 34	Stroke + 35	Stroke + 35	Stroke + 30	Stroke + 20	Stroke + 3	Stroke + 24	Stroke +38	Stroke + 28	Stroke + 3	Stroke + 7	Stroke - 46

E-Series - Machine Screw Jacks - Anti-Backlash - Performance

		Model			05-U0A 105-I0A		U0A & T0A I0A & H0A	EMT00: EMT00	25-U0A 125-I0A		50-U0A 150-I0A		00-U0A 00-I0A
Capac	ity		kN		5	1	0	2	5	5	0	10	00
		mm		1	6	2	0	3	0	4	.0	5	5
Lifting S	crew ¹	Lead -		1	2	1 2		1	2	1	2	1	2
		Lead mm		3	6	5	10	6	12	9	18	12	24
O D .		Option 1		5	:1	5	:1	6	:1	6	:1	8	:1
Gear Ra	atios	Option 2		20):1	20):1	24	i:1	24	i:1	24	::1
Max. In	put	<u>'</u>		0.	25	0.3	375	1.	.5	3	.0	3.75	
Power ((kW)			0.12		0.19		0.375		0.55		1.1	25
Start	'	Gear Ratio Option 1		2.9	3.8	7.8	10.9	23.5	31.3	62.3	84.9	129.2	147.8
torque a load (N		Gear	Ratio Option 2	1.3 1.7		3.6	5.1	9.8	13.0	28.5	38.8	66.8	90.4
Weight (k	kg) - str	oke = 150	0mm	1.	48	2.72		8.62		16.78		26.12	
Weight (k	kg) per	extra 25r	nm	0.0)73	0.	13	0.21		0.	32	0.	57
Gear		Gea	ır Ratio	5	:1	5	:1	6	:1	6	:1	8	:1
Ratio Option	Scr	ew Jack !	Static Efficiency	0.164	0.249	0.203	0.291	0.169	0.254	0.192	0.281	0.185	0.273
1	Screw Jack Dynamic Efficiency		0.216	0.317	0.263	0.365	0.222	0.322	0.251	0.356	0.243	0.325	
Gear		Gear Ratio		20):1	20):1	24	i:1	24	::1	24	:1
Ratio	Scr	ew Jack :	Static Efficiency	0.090	0.137	0.109	0.157	0.102	0.153	0.105	0.154	0.119	0.176
2	ption Caracia Last Director Efficiency		ynamic Efficiency	0.133	0.195	0.159	0.220	0.150	0.217	0.154	0.218	0.172	0.245

		Model		EMT02 EMT02			300-U0A 3300-I0A		500-U0A 500-I0A	EMT1000-U0A EMT1000-I0A	EMT1500-U0A EMT1500-I0A	EMT2000-U0A EMT2000-I0A
Capac	city		kN	20	00		300	5	500	1000	1500	2000
			mm	6	5		95	1	20	160	180	220
Lifting S	crew ¹	اممما	Option	1	2	1	2	1	2	1	1	1
		Lead	mm	12	24	16	32	16	32	20	20	24
0 D	Option 1		Option 1	8	:1	10	2/3:1	10	2/3:1	12:1	11 2/3:1	18:1
Gear Ra	Gear Ratios Option 2		Option 2	24:1			32:1	3	2:1	36:1	N/A	N/A
Max. In	Max. Input Gear Ratio Option 1		Ratio Option 1	3.	75		6.0	1	1.25	18.5	25.3	32.5
Power	Power (kW) Gear Ratio Option 2		Ratio Option 2	1.1	1.125 1.9		4.5		8.25	N/A	N/A	
Start		Gear	Ratio Option 1	281.2	368.5	534	687	1000	1236	2243	4061	4328
torque a load (N		Gear	Gear Ratio Option 2		201.4	315	405	568	702	1244	N/A	N/A
Weight (k	kg) - str	oke = 150)mm	4	9	91		209		610	620	1290
Weight (k	kg) per	extra 25n	nm	0.	86		1.58	2.49		4.31	5.80	9.00
Gear		Gea	r Ratio	8	:1	10	2/3:1	10	2/3:1	12:1	11 2/3:1	18:1
Ratio Option	Scr	ew Jack S	Static Efficiency	0.170	0.259	0.134	0.209	0.119	0.193	0.118	0.100	0.098
1	Scre	w Jack Dy	ynamic Efficiency	0.226	0.332	0.184	0.277	0.163	0.256	0.160	0.139	0.136
Gear		Gea	r Ratio	24	:1		32:1	3	2:1	36:1	N/A	N/A
Ratio Option	Scr	ew Jack S	Static Efficiency	0.104	0.158	0.076	0.118	0.070	0.113	0.071	N/A	N/A
2	Scre	w Jack Dy	ynamic Efficiency	0.151	0.222	0.115	0.173	0.105	0.165	0.106	N/A	N/A

Note


- 1. All metric machine screws have a trapezoidal thread form.
- $2. \ For loads of 25\% \ to \ 100\% \ of \ screw \ jack \ capacity, \ torque \ requirements \ are \ approximately \ proportional \ to \ the \ load.$
- ${\it 3. Efficiency \, values \, for \, standard \, grease \, lubricated \, worm \, gear \, box \, and \, lifting \, screw.}$
- ${\it 4. All E-Series screw\ jacks\ have\ grease\ lubricated\ gearbox\ and\ lead\ screw\ as\ standard.}$

Linear Movement for Rationally Unconstrained Loads


The Anti-Rotation feature for translating screw jacks stops the lifting screw from rotating without the need for end fixing. This is done by keying the lifting screw.


Benefits:

- · Compact unit integrates anti-rotation into gearbox
- Dimensions are the same as the standard translating screw jack
- Standard round cover pipe for easy installation
- · Proven industrial anti-rotation design



Dimensions





Dimensions for Upright Models with Anti-Rotation (Keyed)

Dimensions for upright E-Series machine screw jacks with anti-rotation (keyed) mechanism are the same as the standard screw jacks without the feature.

Dimensions for Inverted Models with Anti-Rotation (Keyed)

The dimensions for these screw jacks are the same as the standard units except those detailed below.

Model	EMT0005	ЕМТ	0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
Туре	1	1	2	1	1	1	1	1	1	1	1	1
А	79	78	86	125.5	159	167.5	210	267	307	445	440	486
В	Stroke + 9	Stroke + 35	Stroke + 35	Stroke + 30	Stroke + 20	Stroke + 3	Stroke -1	Stroke + 15	Stroke + 13	Stroke + 3	Stroke + 7	Stroke - 46
øС	35	N/A	52	60	75	90	102	141.5	180	236	295	396

E-Series - Machine Screw Jacks - Anti-Rotation (Keyed) - Performance

		Model			05-UK0 05-IK0		UK0 & TK0 IK0 & HK0	EMT00: EMT00	25-UK0 125-IK0		50-UK0 50-IK0		00-UK0 00-IK0
Capac	ity	kN mm		!	5	1	0	2	:5	5	0	11	00
				1	6	2	0	3	0	4	0	5	5
Lifting So	crew ¹	v ¹ Lead Option		1	2	1	2	1	2	1	2	1	2
	Lead mm		mm	3 6		5 10		6	12	9	18	12	24
Gear Ra		Option 1		5	:1	5	:1	6	:1	6	:1	8	:1
Gear Ra	itios	Option 2		20	0:1	20):1	24	i:1	24	::1	24	::1
Max. In	put	Gear Ratio Option 1		0.	25	0.3	375	1.	.5	3.	.0	3.75	
Power (kW)	Gear Ratio Option 2		0.12		0.	19	0.3	375	0.	55	1.1	25
Start		Gear Ratio Option 1		2.9	3.8	7.1	9.9	20.8	27.7	58.7	80	121.7	164.7
torque a		Gear	Ratio Option 2	1.3 1.7		3.1	4.4	9.2	12.2	26.8	36.6	63.6	86.1
Weight (k	(g) - sti	roke = 150)mm	1.	03	2.27		8.17		15.88		24.72	
Weight (k	(g) per	extra 25n	nm	0.0)73	0.	13	0.21		0.:	32	0.57	
Gear		Gea	r Ratio	5	:1	5	:1	6	:1	6	:1	8	:1
Ratio Option	Scr	ew Jack S	Static Efficiency	0.182	0.277	0.224	0.322	0.191	0.287	0.203	0.299	0.196	0.290
1	Screw Jack Dynamic Efficiency		namic Efficiency	0.240	0.352	0.291	0.403	0.251	0.364	0.267	0.378	0.258	0.368
Gear	Gear Ratio		20):1	20):1	24	i:1	24	::1	24	::1	
Ratio	Scr	ew Jack S	Static Efficiency	0.103	0.157	0.127	0.182	0.108	0.162	0.111	0.163	0.125	0.185
2	Option Carry Jack Dura		namic Efficiency	0.152	0.223	0.184	0.255	0.159	0.230	0.164	0.232	0.180	0.257

		Model		EMT02 EMT02	00-UK0 00-IK0		00-UK0 100-IK0		00-UK0 600-IK0	EMT1000-UK0 EMT1000-IK0	EMT1500-UK0 EMT1500-IK0	EMT2000-UK0 EMT2000-IK0
Capac	ity		kN	20	00	31	00	50	00	1000	1500	2000
			mm	6	5	9	5	1:	20	160	180	220
Lifting S	crew ¹	Land	Option	1	2	1	2	1	2	1	1	1
		Lead	mm	12 24		16 32		16	32	20	20	24
0	Option 1		Option 1	8	:1	10 2	/3:1	10 2	2/3:1	12:1	11 2/3:1	18:1
Gear Ra	Gear Ratios Option 2		Option 2	24	::1	32	2:1	32	2:1	36:1	N/A	N/A
Max. In	nput	Gear	Ratio Option 1	3.	75	6	.0	11	.25	18.5	25.3	32.5
Power (Power (kW) Gear Ratio Option		Ratio Option 2	1.1	25	1.9		4.5		8.25	N/A	N/A
Start		Gear	Ratio Option 1	275.3	360.7	506	651	947	1170	2125	3847	4100
torque a load (N		Gear	Gear Ratio Option 2		188.7	298	384	526	650	1126	N/A	N/A
Weight (k	kg) - str	oke = 150	0mm	4	5	86		195		553	563	1172
Weight (k	kg) per	extra 25n	nm	0.	86	1.	58	2.49		4.31	5.80	9.00
Gear		Gea	r Ratio	8	:1	10 2	2/3:1	10 2	2/3:1	12:1	11 2/3:1	18:1
Ratio Option	Scr	ew Jack S	Static Efficiency	0.173	0.265	0.142	0.220	0.126	0.204	0.125	0.106	0.103
1	Scre	w Jack Dy	ynamic Efficiency	0.230	0.34	0.195	0.292	0.172	0.270	0.169	0.147	0.143
Gear		Gea	r Ratio	24	::1	32	2:1	32	2:1	36:1	N/A	N/A
Ratio Option	Scr	ew Jack S	Static Efficiency	0.111	0.169	0.080	0.124	0.076	0.122	0.079	N/A	N/A
2	Scre	w Jack Dy	ynamic Efficiency	0.161	0.237	0.121	0.182	0.144	0.178	0.117	N/A	N/A


Note

- 1. All metric machine screws have a trapezoidal thread form.
- $2. For loads of 25\% \ to \ 100\% \ of \ screw \ jack \ capacity, torque \ requirements \ are \ approximately \ proportional \ to \ the \ load.$
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw.
- ${\it 4. All E-Series screw jacks have grease lubricated gearbox and lead screw as standard.}\\$

3

Anti-Backlash & Anti-Rotation (Keyed)

Combine Anti-Backlash & Anti-Rotation in One Screw Jack



Dimensions for E-Series Machine Screw Jacks with Anti-Backlash & Anti-Rotation

Model	EMT0005-UKA EMT0005-IKA	EMT0010-UKA & TKA EMT0010-IKA & HKA	EMT0025-UKA EMT0025-IKA	EMT0050-UKA EMT0050-IKA	EMT0100-UKA EMT0100-IKA	EMT0200-UKA EMT0200-IKA
ØE	36	38	60	75	90	102
F	Stroke + 9	Stroke + 9	Stroke + 30	Stroke + 20	Stroke + 28	Stroke + 24
G	25	30	37	40	37	58
Н	20	24	30	35	30	55
1	40	45	55	65	55	110
J	16	16	19.5	24	19.5	39

Model	EMT0300-UKA EMT0300-IKA	EMT0500-UKA EMT0500-IKA	EMT1000-UKA EMT1000-IKA	EMT1500-UKA EMT1500-IKA	EMT2000-UKA EMT2000-IKA
ØE	138	206	264	295	396
F	Stroke + 15	Stroke + 13	Stroke + 28	Stroke + 7	Stroke - 15
G	73	58	180	50	201
Н	65	55	125	160	170
1	115	110	405	286	395
J	43	39	145	106	200

The dimensions for these screw jacks are the same as the Anti-Backlash units except those detailed above.

E-Series - Machine Screw Jacks - Anti-Backlash & Anti-Rotation (Keyed) - Performance

		Model			05-UKA 05-IKA	EMT0010-U EMT0010-	JKA & TKA IKA & HKA		25-UKA 25-IKA	EMT009 EMT00	50-UKA 50-IKA	EMT010 EMT01	00-UKA 00-IKA
Capac	ity	kN mm		į	5	1	0	2	5	5	0	10	00
				1	6	2	0	3	0	4	0	5	5
Lifting So	crew ¹	v ¹ Option		1	2	1	2	1	2	1	2	1	2
		Lead mm		3	6	5 10		6	12	9	18	12	24
Gear Ra			Option 1	5	:1	5:	:1	6	:1	6:	:1	8	:1
Gear Ra	itios		Option 2	20	1:1	20	1:1	24	::1	24	::1	24	:1
Max. In	put	Gear	Ratio Option 1	0.	 25	0.3	375	1	.5	3.	.0	3.	75
Power (kW)			0.12		0.19		0.375		0.!	55	1.125	
Start		Gear Ratio Option 1		3.1	4	8.3	11.5	24.8	33	65.6	89.3	136	184
torque a		Gear	Ratio Option 2	1.4 1.8		3.8	5.3	10.3	13.7	30	40.9	70.3	958.2
Weight (k	(g) - str	oke = 150)mm	1.	48	2.72		8.62		16.78		26.12	
Weight (k	(g) per	extra 25n	nm	0.0	173	0.13		0.21		0.3	32	0.57	
Gear		Gea	r Ratio	5	:1	5:	:1	6	:1	6:	:1	8	:1
Ratio Option	Scr	ew Jack S	Static Efficiency	0.156	0.237	0.193	0.277	0.161	0.241	0.182	0.267	0.176	0.259
1	Screw Jack Dynamic Efficiency		0.205	0.301	0.250	0.346	0.211	0.306	0.239	0.338	0.231	0.330	
Gear		Gear Ratio		20	1:1	20	1:1	24	::1	24	::1	24	:1
Ratio Option	I Screw Jack Static Efficiency		Static Efficiency	0.086	0.130	0.104	0.149	0.097	0.145	0.100	0.146	0.113	0.167
2	tion Carry Jack Dynamia Efficiency		rnamic Efficiency	0.126	0.185	0.151	0.209	0.142	0.206	0.146	0.208	0.163	0.233

		Model		EMT020 EMT02			00-UKA 800-IKA		00-UKA 500-IKA	EMT1000-UKA EMT1000-IKA	EMT1500-UKA EMT1500-IKA	EMT2000-UKA EMT2000-IKA
Capac	city		kN	20	00	31	00	51	00	1000	1500	2000
			mm	6	5	9	5	1:	20	160	180	220
Lifting S	crew ¹	Load	Option	1	2	1	2	1	2	1	1	1
	Lead		mm	12	24	16	32 16 32		20	20	24	
Gear Ra	Option 1		Option 1	8:	1	10 2	2/3:1	10 2/3:1		12:1	11 2/3:1	18:1
Gear Ra	atios		Option 2	24	:1	32	2:1	32:1		36:1	N/A	N/A
Max. In	nput	Gear	Ratio Option 1	3.	75	6	.0	11.25		18.5	25.3	32.5
Power (ower (kW) Gear Ratio Option 2		Ratio Option 2	1.125 1.9		4	.5	8.25	N/A	N/A		
Start		Gear	Ratio Option 1	296	387.9	562	723	1052 1301		2361	4275	4555
torque a load (N		Gear	Ratio Option 2	161.8	387.9	331	426	598	739	1309	N/A	N/A
Weight (k	kg) - sti	oke = 150)mm	4	9	91		209		610	620	1290
Weight (k	kg) per	extra 25n	nm	0.8	36	1.	58	2.49		4.31	5.80	9.00
Gear		Gea	r Ratio	8:	1	10 2	2/3:1	10 2	2/3:1	12:1	11 2/3:1	18:1
Ratio Option	Scr	ew Jack S	Static Efficiency	0.161	0.246	0.128	0.198	0.113	0.184	0.112	0.096	0.093
1	Scre	w Jack Dy	ynamic Efficiency	0.214	0.316	0.175	0.263	0.155	0.243	0.152	0.132	0.129
Gear	ear Gear Ratio		24	:1	32	2:1	32	2:1	36:1	N/A	N/A	
Ratio Option	Scr	ew Jack S	Static Efficiency	0.098	0.150	0.072	0.112	0.067	0.108	0.068	N/A	N/A
2	Scre	w Jack Dy	namic Efficiency	0.143	0.211	0.109	0.164	0.100	0.157	0.100	N/A	N/A

Note


- 1. All metric machine screws have a trapezoidal thread form.
- 2. For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- ${\it 3. Efficiency \, values \, for \, standard \, grease \, lubricated \, worm \, gear \, box \, and \, lifting \, screw.}$
- ${\it 4. All E-Series screw\ jacks\ have\ grease\ lubricated\ gearbox\ and\ lead\ screw\ as\ standard.}$

Extra Safety for Critical Applications

Power Jacks machine screw jacks can be fitted with a safety nut, which provides 2 safety roles:

- In the event of excessive wear on the nut thread the load will be transferred from the standard nut to the safety nut. This will also provide visual wear indication as the gap between the safety nut decreases to zero as the standard lifting nut wears.
- 2. In the unlikely event of catastrophic nut thread failure the safety nut will sustain the load. The safety of industrial and human cargo is therefore improved.

There are several configurations for each safety nut device as they only work in one load direction. For this reason when ordering please supply a sketch of your application showing load directions.





All Safety Nuts are BS EN 1570 Compliant


Translating Screw Jacks with Safety Nuts


Tension Safety Nut

Compression Safety Nut










Dimensions - Translating Screw

Model	Rating (kN)	Туре	А	В	С	D	ØE	F	G	Н	I	J
EMT0005	5	1		On Request								
EMT0010	10	1	125	24	86	Stroke + 35	38	Stroke + 9	30	24	45	16
EMITOUTO	10	2	125	24	90	Stroke + 35	38	Stroke + 9	30	24	45	16
EMT0025	25	1	145	30	104	Stroke + 30	60	Stroke +30	37	30	55	20
EMT0050	50	1	185	35	138	Stroke + 20	75	Stroke + 20	40	35	65	24
EMT0100	100	1	200	200 40 146 Stroke +3 90 Stroke + 28 48 40 80 30								
EMT0200	200	1	265	265 55 195 Stroke +24 102 Stroke + 24 58 55 110 39							39	
EMT0300	300	1					On Re	equest				
EMT0500	500	1					On Re	equest				
EMT1000	1000	1		On Request								
EMT1500	1500	1					On Re	equest				
EMT2000	2000	1		On Request								

Rotating Screw Jacks with Safety Nuts




Dimensions - Rotating Screw

Model	Rating (kN)	А	В	С	D	ØE	ØF	G			
EMR0005	5		On Request								
EMR0010	10	Stroke + 76	30	66.5	12	35	80	4 x Ø11, Ø57 PCD			
EMR0025	25	Stroke + 95	33.5	75	15	40	90	4 x Ø13.5, Ø65 PCD			
EMR0050	50	Stroke + 140	58	125	20	55	115	4 x Ø18, Ø85 PCD			
EMR0100	100	Stroke + 170	67	145	25	80	160	4 x Ø22, Ø120 PCD			
EMR0200	200	Stroke + 170	67	145	25	90	185	4 x Ø26, Ø135 PCD			
EMR0300	300	Stroke + 310	126	270	35	125	230	6 x Ø26, Ø175 PCD			
EMR0500	500	Stroke + 335	130	284	50	160	280	6 x Ø33, Ø220 PCD			
EMR1000	1000	Stroke + 410	155	335	60	210	380	6 x Ø45, Ø295 PCD			
EMR1500	1500		On Request								
EMR2000	2000		On Request								

Double Hub Nut for Rotating Screw Jacks







Model	Α	В	С	D	ØE	F	ØG	
EMR0010	Stroke + 55	40	25	10	25	4 x Ø9, Ø42 PCD	60	
EMR0010	Stroke + 61	52	35	12	35	4 x Ø11, Ø57 PCD	80	
EMR0025	Stroke + 80	60	40	15	40	4 x Ø13.5, Ø65 PCD	90	
EMR0050	Stroke + 100	85	65	20	55	4 x Ø18, Ø85 PCD	115	
EMR0100	Stroke + 120	95	75	25	80	4 x Ø22, Ø120 PCD	160	
EMR0200	Stroke + 120	95	75	25	90	4 x Ø26, Ø135 PCD	185	
EMR0300	Stroke + 200	160	140	35	125	6 x Ø26, Ø175 PCD	230	
EMR0500	Stroke + 225	175	150	50	160	6 x Ø33, Ø220 PCD	280	
EMR1000	Stroke + 275	200	175	60	210	6 x Ø45, Ø295 PCD	380	
EMR1500		On Request						
EMR2000	On Request							

Secondary Guide - Greater Lateral Rigidity for Lifting Screw


Secondary Guiding for the screw for greater lateral rigidity aiding screw guidance and improved side load resilience.





Dimensions for Screw Jacks with Secondary Guides

Mode	ι	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
	ØΑ	36	38	60	70	90	100	138	155	225		
Upright	В	Stroke + 34	Stroke + 34	Stroke + 30	Stroke + 20	Stroke + 29	Stroke + 24	Stroke + 40	Stroke + 38	Stroke + 50		
	С	16	20	20	18	20	20	38	38	65	uest	Request
	ØD	36	On Request	60	70	90	100	138	155	est	On Requ	On Req
Inverted	Е	Stroke + 34	Stroke + 34	Stroke + 30	Stroke + 20	Stroke + 29	Stroke + 24	Stroke + 40	Stroke + 38	Request		
	F	16	On Request	20	18	20	20	38	38	00		



Model	EMT0005	EMT	0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000
Capacity (kN)	5	10	10	25	50	100	200	300	500	1000
Housing Type	1	1	2	1	1	1	1	1	1	
Style	1	1	2	2	2	2	2	2	2	
А	150	180	180	213	260	352	428	492	570	
В	115	145	145	170	210	247	313	367	440	
С	35	35	35	43	50	105	115	125	130	On
D	15	20	20	23	30	33	40	60	75	Request
ØE	26.7	33.4	33.4	48.3	60.3	73	102	133	168	<u>'</u>
F	15	20	20	30	35	40	50	80	110	
ØG	10	12	12	16	20	22	30	45	60	
Max Stroke at Rated Load (Compression)	220	175	175	352	420	593	592	1338	1920	


STROKE + A

Note: All dimensions in millimetres unless otherwise stated.

E-Series Stainless Steel Screw Jacks

DESIGNED FOR USE IN HARSH & CORROSIVE ENVIRONMENTS CAPACITIES - 10KN TO 1000KN AS STANDARD.





The stainless steel screw jacks are ideal for use in harsh or corrosive environments such as marine, nuclear, water, food processing or paper making machinery, where standard materials may be inadequate.

Translating Screw





Inverted

Rotating Screw





Typical Applications

Stainless Steel Machine Screw Jacks are typically used in harsh or corrosive environments or those with a regular wash down requirement. Industries such as Marine, Water Treatment, Nuclear, Food Processing, Offshore, Pulp and Paper use stainless steel screw jacks. For each application, variants with different material grades or plated components can be used, tailoring the product for the specific application and budget.

Standard Designs

Stainless steel E-Series machine screw jacks are available in translating and rotating screw designs in capacity sizes from 10kN to 1000kN. The design is optimised for reliable performance in some of the most arduous environments. Plus there is a large selection of standard accessories (section-7) and options so you can configure a standard design that is just right for your application. These options include Anti-Backlash, Anti-Rotation (Keyed) and Safety Nut designs.

Special Designs

We can fully customise our screw jacks so that your application can be the best.

Customisation can be anything from a small modification such as an extra bolt hole on an end fitting to a completely new design of screw jack based on our class leading technology.

For more details please see the Special Screw Jack information in Section-8 or contact us today with your requirements. Our team are looking forward to working with you.

Selecting the Right Screw Jack

Consider all application constraints then choose a product that looks suitable for the intended application. Calculate the power and torque requirements. This is a 5 step process:

- Screw Jack Input Speed (RPM)
- Operating Input Power (kW)
- Operating Input Torque (Nm)
- Screw Jack Start-up Torque (Nm)
- Mechanical Power and Torque Check

Systems

The screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearbox, drive shafts, couplings, plummer blocks and motion control devices.

The use of bevel gearboxes allows the distribution of drive throughout a jacking system. The gearboxes come in 2,3 and 4 way drive types. See the Bevel Gearbox Section-10 for more details.

Bevel gearboxes and other system components can also be supplied in stainless steel or other corrosion resistant designs.



Two of the most popular system configurations are the 'H' and 'U' configured jacking systems. Remember that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.

If multiple machine screw jacks are connected in a mechanically linked system then the complete system may be considered self-locking. If you would like this checked consult Power Jacks. Alternatively, to be sure, include a brake on the system either as a stand alone device or as a brake motor.



Application Focus

POWERJACKS









DRUM POSTING EQUIPMENT (DPE)

Dunreay cementation plant waste transfer facility.

Raise and lower drum transfer table.

Two stainless steel E-Series translating machine screw jacks 100kN capacity with 24:1 gear ratio and 1805mm stroke connected in series by a stainless steel drive shaft and geared couplings.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.




Stainless Steel Screw Jack Standard Performance


Model			EMT0010 EMR0010	EMT0025 EMR0025	EMT0050 EMR0050	EMT0100 EMR0100	EMT0200 EMR0200	EMT0300 EMR0300	EMT0500 EMR0500	EMT1000 EMR1000
Capacity		kN	10	25	50	100	200	300	500	1000
Sustaining	Standard 316 Lifting	Tension	6.6	16.5	33	66	132	200	333	666
Capacity (kN)	Screw	Compression	10	25	50	100	200	300	500	1000
	Duplex L	fting Screw	10	25	50	100	200	300	500	1000
		Steel Worm haft	3.3	8.25	16.5	33	66	100	167	333
Operating Capacity (kN)	Duplex or Plated Worm	Tension	6.6	16.5	33	66	132	200	333	666
Capacity ()	Shaft with 316 Screw	Compression	10	25	50	100	200	300	500	1000
		Plated Worm Duplex Screw	10	25	50	100	200	300	500	1000
1:0: 6	Diame	ter (mm)	20	30	40	55	65	95	120	160
Lifting Screw	Lead	d (mm)	5	6	9	12	12	16	16	20
	Op:	tion 1	5:1	6:1	6:1	8:1	8:1	10 2/3	10 2/3:1	12:1
Gear ratios	Op:	tion 2	20:1	24:1	24:1	24:1	24:1	32:1	32:1	36:1
Turn of worm	Ratio Option Option 1	1 Turn	1mm	1mm	1.5mm	1.5mm	1.5mm	1.5mm	1.5mm	1.67mm
for travel of lifting screw	Ratio Option Option 2	4 Turn	1mm	1mm	1.5mm	2mm	2mm	2mm	2mm	2.22mm
Max. Input	Gear Ra	tio Option 1	0.375	1.5	3.0	3.75	3.75	6.0	11.25	18.5
power (kW)	Gear Ra	tio Option 2	0.19	0.375	0.55	1.125	1.125	1.9	4.5	8.25
Start up torque	Gear Ra	tio Option 1	6.8	19.8	56	115.9	263.8	480	904	2025
at full load (Nm)	Gear Ra	tio Option 2	3	8.7	25.5	60.5	137	284	504	1119
Weight (kg)	E	MT	2.36	8.45	14.9	24.3	42.4	92.4	183.7	459.1
- stroke = 150mm	E	MR	2.6	8.85	16.54	28.8	49.58	113.78	224	560.4
Weight (kg) per		MT	0.11	0.21	0.32	0.58	0.84	1.55	2.48	4.11
extra 25mm		MR	0.05	0.11	0.19	0.36	0.52	1.13	1.94	3.38
		r Ratio	5:1	6:1	6:1	8:1	8:1	10 2/3:1	10 2/3:1	12:1
Gear Ratio Option 1		ack Static ciency	0.233	0.201	0.213	0.206	0.181	0.149	0.132	0.131
5,500		ck Dynamic ciency	0.306	0.264	0.281	0.272	0.242	0.205	0.181	0.178
	Gea	r Ratio	20:1	24:1	24:1	24:1	24:1	32:1	32:1	36:1
Gear Ratio		lack Static ciency	0.130	0.115	0.117	0.132	0.116	0.084	0.079	0.079
Option 2		ck Dynamic ciency	0.194	0.167	0.172	0.190	0.169	0.128	0.120	0.123

Notes

- 1. All metric stainless steel machine screws have a trapezoidal thread form, single start as standard. Other screw lead options are available on request.
- 2. Based on operating capacity for loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw

Inverted EMT0010-J00





Performance

Closed Height

Model					0010 0010	
Capacity (k)	۷)			1	0	
Sustaining	Standard 316	Т	ension	6.6		
Capacity	Lifting Screw	1	0			
(kN)	Duplex Lifting S	1	0			
	Standard 316 W	or	m Shaft	3	.3	
Operating	Duplex or Plated		Tension	6	.6	
Capacity (kN)	316 Screw		Compression	10		
	Duplex or Plate Shaft with Duple	10				
	Diameter (mm)			2	0	
Lifting Screw	Lead		Option	1	2	
Sciew	Lead		mm	5 10		
	Gear Ratio			5	:1	
Gear Ratio Option 1	Screw Jack Stat	ic	Efficiency	0.233	0.339	
Option i	Screw Jack Dyn	0.306	0.424			
0 0 .:	Gear Ratio			20):1	
Gear Ratio Option 2	Screw Jack Stat	ic	Efficiency	0.130	0.192	
Option 2	Screw Jack Dyn	an	nic Efficiency	0.194	0.268	

Model							
Capacity	kN		1	0			
Lifting Screw I	Lead (mm)		5	10			
Turn of worm for	Gear Ratio 1	1 Turn	1mm	2mm			
travel of lifting screw	4 Turn	1mm	2mm				
Maximum Thr	ough Torque (Nn	n)	2	0			
Lifting Screw I	Restraining Torq	ue (Nm)	22	30			
Worm Shaft M (N)	aximum Radial l	_oad	32	25			
Maximum Inpo	ut Speed (rpm)		18	00			
Gear Case Ma	terial		Stainles	ss Steel			
Woight (kg)	Weight (kg) - stroke = 150mm						
vveignt (kg) - s		EMR	2.6				
Weight (kg) - per extra 25mm stroke							
vveigiit (kg) - p	iei extra 25mm s	stroke	EMR	0.05			


Note: All dimension in millimetres unless otherwise stated. Designs subject to change without notice

	5	
Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EMR0010-V00

31.83 31.75 KEY 25 x 5 x 5 Ø 14 h8 LHS 130 150 00 50 9 35 RHS 4 HOLES Ø 11 ON 57 P.C.D. 35 107 Ø20 Ø12 9 <u>Ø3</u>5 STROKE + 7 Ø80 9 40.13 39.87

Inverted EMR0010-J00




Closed Height & Bellows Boots

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0010	125	45	125	45	145	65	148	98	150	70
Stroke (mm)		EMT0010 with Bellows Boots								
0-150	125	75	125	75	145	95	148	98	165	115
151-300	130	95	130	95	150	115	153	118	170	135
301-600	140	95	140	95	160	115	163	118	180	135
751-1000	-	-	-	-	-	-	-	-	-	-

Model	А	В	D	Ε	G
EMT0010	30	70	15	15	110

Stroke	1-150	151-300	301-600	601-900	901-1050
EMT0010	8	20	35	-	-






- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.


10kN MACHINE SCREW JACK COLUMN LENGTH (mm) 300 400 500 600 700 800 900 1000 1100 100 200 300 400 500 600 700 800 50 100 150 200 250 300 350 400 PINNED/PINNED FIXED/FREE



Upright EMT0025-V00

Inverted EMT0025-J00






Model					0025 0025	
Capacity (k)	۷)			2	5	
Sustaining	Standard 316	Т	ension	16	.5	
Capacity	Lifting Screw	C	Compression	2	5	
(kN)	Duplex Lifting S	Scr	ew	2	5	
	Standard 316 W	/or	m Shaft	8.	25	
Operating Capacity (kN)	Duplex or Plate Worm Shaft wit		Tension	16	5.5	
			Compression	25 16.5 25 25 8.25 16.5 59 25 30 1 2 6 12 6:1 0.201 0.302 0.264 0.383		
(KIN)	Duplex or Plate Shaft with Dupl	25				
	Diame	30				
Lifting Screw			Option	1	2	
JCIEW	Lead		mm	6	12	
	Gear Ratio	6:1				
Gear Ratio Option 1	Screw Jack Sta	tic	Efficiency	0.201	0.302	
Option	Screw Jack Dyn	nan	nic Efficiency	0.264	0.383	
	Gear Ratio			24:1		
Gear Ratio Option 2	Screw Jack Sta	tic	Efficiency	0.115	0.171	
Option 2	Screw Jack Dyn	nan	nic Efficiency	0.167	0.242	


Model	EMT0025 EMR0025				
Capacity	kN		2	5	
Lifting Screw I	Lead (mm)		6	12	
Turn of worm for	Gear Ratio 1	1 Turn	1mm	2mm	
travel of lifting screw	Gear Ratio 2	4 Turn	1mm	2mm	
Maximum Thr	ough Torque (Nn	n)	59		
Lifting Screw I	Restraining Torq	ue (Nm)	76 102		
Worm Shaft M (N)	aximum Radial I	_oad	380		
Maximum Inpo	ut Speed (rpm)		1800		
Gear Case Ma	terial		Stainles	ss Steel	
Waisht (les)	.t.a.l.a. 1E0		EMT	8.45	
vveigiit (kg) - S	stroke = 150mm		EMR	8.85	
Waisht (les)	2F		EMT	0.21	
vveignt (kg) - p	er extra 25mm s	stroke	EMR	0.11	


Note: All dimension in millimetres unless otherwise stated.


Designs subject to change without notice



Inverted EMR0025-J00







Closed Height & Bellows Boots

13

_Ø90

Column Strength

200


Closed	Threaded End		Top I	Plate	Clevi	s End	Fork	End	Rod	Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EMT0025	145	55	145	55	170	80	194	104	190	100	
Stroke (mm)		EMT0025 with Bellows Boots									
1-300	145	80	145	80	170	105	194	129	205	140	
301-600	145	80	145	80	170	105	194	129	205	140	
601-1050	170	105	170	105	195	130	219	154	230	165	
1051-1500	195	130	195	130	220	155	244	179	255	190	


103

13 45.

Model	А	В	D	Е	G
EMT0025	40	90	15	23	120

Stroke	1-150	151-301	301-600	601-1050	1051-1500
EMT0025	8	20	30	50	70






Note

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.

- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.



600 800 1000 1200 600 800 1000


25kN MACHINE SCREW JACK


50kN Translating



Upright EMT0050-V00

Inverted EMT0050-J00





Performance

Model					0050 0050		
Capacity (k)	Capacity (kN)						
Sustaining	Standard 316	Т	ension	3	3		
Capacity	Lifting Screw	C	Compression	3	3		
(kN)	Duplex Lifting S	Scr	ew	5	0		
	Standard 316 W	/or	m Shaft	16	.5		
Operating Capacity (kN)	Duplex or Plate Worm Shaft wit		Tension	3	3		
			Compression	50			
(KIN)	Duplex or Plate Shaft with Dupl	50					
1.16.1	Diame	40					
Lifting Screw	Lead		Option	1	2		
Jerew	Lead		mm	9	18		
	Gear Ratio	6:1					
Gear Ratio Option 1	Screw Jack Sta	tic	Efficiency	0.213	0.314		
Option	Screw Jack Dyn	nan	nic Efficiency	0.281	0.398		
	Gear Ratio			24	24:1		
Gear Ratio Option 2	Screw Jack Sta	tic	Efficiency	0.117	0.172		
Option 2	Screw Jack Dyn	an	nic Efficiency	0.172	0.244		

Model		EMT0050 EMR0050			
Capacity	kN		50)	
Lifting Screw I	Lead (mm)		9	18	
worm for travel of	Gear Ratio 1	1 Turn	1.5mm	3mm	
	Gear Ratio 2	4 Turn	1.5mm	3mm	
Maximum Thr	168				
Lifting Screw I	Restraining Torq	ue (Nm)	210	290	
Worm Shaft M (N)	aximum Radial l	_oad	740		
Maximum Inpo	ut Speed (rpm)		1800		
Gear Case Ma	terial		Stainles	s Steel	
\\\ai=h+(₁ =) -	.t1/- 1F0		EMT	14.9	
weight (kg) - s	stroke = 150mm		EMR	16.54	
Wainht (ka)	t 2E		EMT	0.32	
weignt (kg) - p	er extra 25mm s	stroke	EMR	0.19	

Note: All dimension in millimetres unless otherwise stated. Designs subject to change without notice


Threaded End Top Plate Clevis End Fork End Rod End


Inverted

Upright

Upright EMR0050-V00

Inverted EMR0050-J00






Closed Height & Bellows Boots

Clevis End Fork End Rod End Top Plate Closed Height "C" Upright Upright Inverted Upright Inverted Upright Upright EMT0050 EMT0050 with Bellows Boots Stroke (mm) 1-150 151-300 301-600 601-1050 1051-1500

EMT0050	50	115		15		31		140	
Stroke	1-150	151-300	30	01-600	61	01-1050	1	1051-1500	



EMT0050


Model


Inverted Screw Jacks - Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks - Recommended bellows boot mounting plate ØB x (E +5mm) thick.

Inverted Screw Jacks - Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).
 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

Column Strength







100kN Translating

100kN

Upright EMT0100-V00



Inverted EMT0100-J00



Performance

Model					0100 0100		
Capacity (k)	Capacity (kN)						
Sustaining	Standard 316	T	ension	6	6		
Capacity	Lifting Screw	C	Compression	10	00		
(kN)	Duplex Lifting S	cr	ew	10	00		
	Standard 316 W	or	m Shaft	3	3		
Operating Capacity (kN)	Duplex or Plate Worm Shaft wit		Tension	6	6		
	316 Screw		Compression	100			
(KIV)	Duplex or Plate Shaft with Duple	100					
	Diameter (mm)			55			
Lifting Screw			Option	1	2		
Sciew	Lead		mm	12	24		
	Gear Ratio	Gear Ratio			8:1		
Gear Ratio Option 1	Screw Jack Stat	tic	Efficiency	0.206	0.305		
Option	Screw Jack Dyn	ar	nic Efficiency	0.272	0.388		
	Gear Ratio			24	::1		
Gear Ratio Option 2	Screw Jack Stat	tic	Efficiency	0.132	0.195		
Option 2	Screw Jack Dyn	ar	nic Efficiency	0.190	0.271		

Model	Model						
Capacity	kN		10	0			
Lifting Screw I	Lead (mm)		12	24			
Turn of worm for travel of lifting screw	Gear Ratio 1	1 Turn	1.5mm	3mm			
	Gear Ratio 2	4 Turn	2mm	4mm			
Maximum Thr	ough Torque (Nn	n)	347				
Lifting Screw I	Restraining Torq	ue (Nm)	575 780				
Worm Shaft M (N)	aximum Radial I	_oad	1000				
Maximum Inpi	ut Speed (rpm)		1800				
Gear Case Ma	terial		Stainles	s Steel			
\\\a:=h+(₁ =) =	.t.a.l.a. 1E0		EMT	24.3			
Weight (kg) - s		EMR	28.8				
\\\a\:\a\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	t 2F		EMT	0.58			
vveignt (kg) - p	er extra 25mm s	ыоке	EMR	0.36			

Note: All dimension in millimetres unless otherwise stated.


Designs subject to change without notice


Rod End Fork End Clevis End Top Plate Threaded End

Closed Height

Upright EMR0100-V00

Inverted EMR0100-J00






Closed Height & Bellows Boots


Column Strength	^
-----------------	---

Closed	Threaded End		Top I	Plate	Clevi	s End	Fork	End	Rod	Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EMT0100	200	80	200	80	245	125	302	182	283	163	
Stroke (mm)		EMT0100 with Bellows Boots									
1-300	200	105	200	105	245	150	302	207	298	203	
301-600	200	130	200	130	245	175	302	232	298	228	
601-1050	225	130	225	130	270	175	327	232	323	228	
1051-1500	250	155	250	155	295	200	352	257	348	253	

Model	Α	В	D	Е	G
EMT0100	65	136	15	31	150

Stroke	1-300	301-600	601-1050	1051-1500
EMT0100	20	30	50	70






Note


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.





POWERJACKS

Upright EMT0200-V00




13

85. 84.

4 x M10 x 1.5 x 14 DEEP

STROKE -1

Inverted EMT0200-J00



Performance


Model	Model					
Capacity (kN)					00	
Sustaining	Standard 316	Т	ension	13	32	
Capacity	Lifting Screw		Compression	20	00	
(kN)	Duplex Lifting Screw		20	00		
	Standard 316 W	/or	m Shaft	6	6	
Operating	Operating Capacity (kN) Operating Worm Shaft with 316 Screw		Tension	10	32	
			Compression	200		
(KIV)		Duplex or Plated Worm Shaft with Duplex Screw			200	
1.16.1	Diame	Diameter (mm)		6	5	
Lifting Screw	Lead		Option	1	2	
Jerew	Lead		mm	12	24	
	Gear Ratio			8	:1	
Gear Ratio Option 1	Screw Jack Sta	tic	Efficiency	0.181	0.279	
Option	Screw Jack Dynamic Efficiency		0.242	0.357		
	Gear Ratio			24	24:1	
Gear Ratio Option 2	Screw Jack Sta	tic	Efficiency	0.116	0.178	
Option 2	Screw Jack Dyn	nan	nic Efficiency	0.169	0.250	

Ø89

Model	Model					
Capacity	kN		200			
Lifting Screw I	Lead (mm)		12	24		
Turn of worm for	Gear Ratio 1	1 Turn	1.5mm	3mm		
travel of lifting screw	Gear Ratio 2	2mm	4mm			
Maximum Thr	396					
Lifting Screw I	Restraining Torq	ue (Nm)	1300	1705		
Worm Shaft M (N)	aximum Radial l	_oad	1600			
Maximum Inpo	ut Speed (rpm)		1800			
Gear Case Ma	terial		Stainles	s Steel		
\\\ai=h+(₁ =) -	.t1/- 1F0		EMT	42.4		
Weight (kg) - s	EMR	49.58				
Wainht (ka)	EMT	0.84				
vveignt (kg) - þ	er extra 25mm s	ыоке	EMR	0.52		

Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice




POWERJACKS

Upright EMR0200-V00

215 66.07 66.00 126 LHS 4 210 300 150 75 105 150 RHS 4 4 HOLES Ø 26 ON 135 P.C.D. 105 KEY 40 x 8 Ø28 h8 275 Ø<u>6</u>5 65 <u>Ø9</u>0 STROKE + 100 25

Inverted EMR0200-J00



Closed Height & Bellows Boots

20 24

Ø 185

Closed	Thread	led End	Top I	Plate	Clevi	s End	Fork	End	Rod	End
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0200	265	95	265	95	310	140	400	230	367	197
Stroke (mm)			EMT0200 with Bellows Boots							
1-300	265	120	265	120	310	165	400	255	387	242
301-600	265	145	265	145	310	190	400	280	387	267
601-1050	290	145	290	145	335	190	425	280	412	267

360

215

Ø88 PCD

13

88.8

4 x M10 x 1.5 x 14 DEEP


195

Model	А	В	D	Е	G	
EMT0200	75	165	20	20	165	

315

170

Stroke	1-300	301-600	601-1050	1051-1500
EMT0200	20	30	50	70



305

450

437

292

Note

1051-1500

315

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

170


- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

Column Strength


2.2 x 10 2 x 10⁴ 1.8 x 10⁴ 1.4 x 10 1.2 x 10 1 x 10⁴ 8000

> 6000 4000




COLUMN LENGTH (mm)

Upright EMT0300-V00



Inverted EMT0300-J00




Performance

Model	Model					
Capacity (kN)					00	
Sustaining	Standard 316	Т	ension	20	00	
Capacity	Lifting Screw		Compression	30	00	
(kN)	Duplex Lifting Screw		30	00		
	Standard 316 W	/or	m Shaft	10	00	
Operating	Operating Capacity (kN) Duplex or Plated Worm Shaft with 316 Screw		Tension	20	00	
			Compression	300		
(KIV)		Duplex or Plated Worm Shaft with Duplex Screw			300	
1.16.1	Diame	Diameter (mm)		9	5	
Lifting Screw	Lead		Option	1	2	
Jerew	Lead		mm	16	32	
	Gear Ratio			10 2	2/3:1	
Gear Ratio Option 1	Screw Jack Sta	tic	Efficiency	0.149	0.232	
Option	Screw Jack Dynamic Efficiency		nic Efficiency	0.205	0.308	
	Gear Ratio			32	32:1	
Gear Ratio Option 2	Screw Jack Sta	tic	Efficiency	0.084	0.131	
Option 2	Screw Jack Dyn	an	nic Efficiency	0.128	0.192	

Model	EMT0300 EMR0300			
Capacity	kN		30	00
Lifting Screw I	Lead (mm)		16	32
Turn of worm for	Gear Ratio 1	1 Turn	1.5mm	3mm
travel of lifting screw	Gear Ratio 2	4 Turn	2mm	4mm
Maximum Thr	1440			
Lifting Screw I	Restraining Torq	ue (Nm)	2805 3610	
Worm Shaft M (N)	aximum Radial I	Load	2170	
Maximum Inpi	ut Speed (rpm)		18	00
Gear Case Ma	terial		Stainles	s Steel
\\\a\:\=\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	.t.a.l.a. 150-a-a-		EMT	92.4
Weight (kg) - s	EMR	113.78		
\\\a\:\a\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	EMT	1.55		
vveigiit (kg) - þ	er extra 25mm :	stroke	EMR	1.13


Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice




Closed Height

Upright EMR0300-V00



Inverted EMR0300-J00




Closed Height & Bellows Boots

Closed	Thread	led End	Top I	Plate	Clevi	s End	Fork	End	Rod	End
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0300	325	115	325	115	365	155	on request on request			quest
Stroke (mm)		EMT0300 with Bellows Boots								
1-300	325	140	325	140	365	180	-	-	-	-
301-600	325	165	325	165	365	205	-	-	-	-
601-1050	350	165	350	165	390	205	-	-	-	-
1051-1500	375	190	375	190	415	230	-	-	-	-

Model	А	В	D	E	G
EMT0300	110	220	20	20	191

Stroke	1-300	301-600	601-1050	1051-1500
EMT0300	20	30	50	70



Note

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply


- † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

300kN MACHINE SCREW JACK 3 x 2 x 10


Column Strength


FIXED/GUIDED PINNED/PINNED FIXED/FREE 500 1000 1500 2000 2500 3000 3500 4000 4500 5000 5500 250 500 750 1000 1250 1500 1750 2000 2250 2500





Upright EMT0500-V00

Inverted EMT0500-J00









Performance


Closed Height

Model	EMT0500 EMR0500				
Capacity (kN)				500	
Sustaining Capacity (kN)	Standard 316 Lifting Screw	T	ension	333	
		Compression		500	
	Duplex Lifting Screw			500	
Operating Capacity (kN)	Standard 316 Worm Shaft		167		
	Duplex or Plated Worm Shaft with 316 Screw		Tension	333	
			Compression	500	
	Duplex or Plated Worm Shaft with Duplex Screw			500	
Lifting Screw	Diameter (mm)			120	
	Lead		Option	1	2
	Lead		mm	16	32
Gear Ratio Option 1	Gear Ratio			10 2/3:1	
	Screw Jack Static Efficiency			0.132	0.215
	Screw Jack Dynamic Efficiency			0.181	0.284
Gear Ratio Option 2	Gear Ratio			32:1	
	Screw Jack Static Efficiency			0.079	0.129
	Screw Jack Dynamic Efficiency			0.120	0.188

Model	EMT0500 EMR0500			
Capacity	kN	500		
Lifting Screw I	16	32		
Turn of worm for travel of lifting screw	Gear Ratio 1	1 Turn	1.5mm	3mm
	Gear Ratio 2	4 Turn	2mm	4mm
Maximum Thr	2712			
Lifting Screw I	5645	6975		
Worm Shaft M (N)	2190			
Maximum Inpu	1800			
Gear Case Ma	Stainless Steel			
\\/a:=h±(,=) =	EMT	183.7		
Weight (kg) - s	EMR	224		
\\/\(\lambda_1 = \lambda_1	EMT	2.48		
Weight (kg) - p	EMR	1.94		

Note: All dimension in millimetres unless otherwise stated.


Designs subject to change without notice



Upright EMR0500-V00

435 135.07 135.00 175) LHS 99 460 200 100 150 \oplus 230 RHS 99 6 HOLES Ø33 ON 220 P.C.D. 225 KEY 60 x 12 x 8 535 100 Ø 120 STROKE + 200 Ø 160 20 20 Ø280 Ø135 PCD 120.13 119.87 4 x M16 x 2 x 25 DEEP Ø141

Inverted EMR0500-J00



Column Strength


FIXED/FREE


Closed Height & Bellows Boots

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End		
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EMT0500	390	150	390	150	440	200	on re	quest	on request		
Stroke (mm)		EMT0500 with Bellows Boots									
1-300	390	175	390	175	440	225	-	-	-	-	
301-600	415	200	415	200	465	250	-	-	-	-	
601-1050	440	225	440	225	490	275	-	-	-	-	
1051-1500	465	250	465	250	515	300	-	-	-	-	

Closed	Tilleaded Lild		Top I tate		Clevis Liiu		TOTALIIU		IXOU LIIU	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EMT0500	390	150	390	150	440	200	on re	quest	on re	quest
Stroke (mm)		EMT0500 with Bellows Boots								
1-300	390	175	390	175	440	225	-	-	-	-
301-600	415	200	415	200	465	250	-	-	-	-
601-1050	440	225	440	225	490	275	-	-	-	-
1051-1500	465	250	465	250	515	300	-	-	-	-

EMT0500	150	285	20		45		210
Stroke ₁₋₃₀₀		301-6	00	601	-1050		051-1500
EMT0500	20	30			50		70





Note

Model

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).


 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.

- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

5.10 4.5.10 4,10 3.10 2.5.10 2,10 1,5,10 FIXED/GUIDED 2000 3000 4000 5000

1500

500kN MACHINE SCREW JACK




2500

1000kN Translating


1000kN

POWERJACKS

Upright EMT1000-V00



Inverted EMT1000-J00




Ρ	е	r	t	0	r	r	Υ)	a	r	1	C	е
								Т					

Model			EMT1000 EMR1000
Capacity (k)	1)		1000
Sustaining	Standard 316	Tension	666
Capacity	Lifting Screw	Compression	1000
(kN)	Duplex Lifting S	1000	
	Standard 316 W	orm Shaft	333
Operating	Duplex or Plate Worm Shaft wit		666
Capacity (kN)	316 Screw	Compression	1000
(KIN)	Duplex or Plate Shaft with Duple	1000	
1.0.	Diamet	160	
Lifting Screw	l ead	Option	1
Sciew	Lead	mm	20
	Gear Ratio		12:1
Gear Ratio Option 1	Screw Jack Stat	tic Efficiency	0.131
Spilon 1	Screw Jack Dyn	amic Efficiency	0.178
0 0 0	Gear Ratio		36:1
Gear Ratio Option 2	Screw Jack Stat	0.079	
Option 2	Screw Jack Dyn	amic Efficiency	0.123


Model			EMT EMR				
Capacity	kN		1000				
Lifting Screw I	Lead (mm)		2	0			
Turn of worm for	Gear Ratio 1	1 Turn	1.67mm				
travel of lifting screw	4 Turn	6.67	mm				
Maximum Thr	ough Torque (Nn	n)	6075				
Lifting Screw I	Restraining Torq	ue (Nm)	14890				
Worm Shaft M (N)	aximum Radial	Load	2220				
Maximum Inpu	ut Speed (rpm)		18	00			
Gear Case Ma	terial		Stainles	ss Steel			
\\/a:=h+()			EMT	459.1			
vveignt (kg) - s	Weight (kg) - stroke = 150mm						
NA : 1 : (1 -)		EMT	4.11				
Weight (kg) - p	stroke	EMR	3.38				


Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice



Inverted EMR1000-J00






Closed Height & Bellows Boots

Closed	Threaded End		Top Plate		Clevis End		Fork End		Rod End		
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EMT1000	560	260	560	260	625	325	on re	quest	on request		
Stroke (mm)		EMT1000 with Bellows Boots									
1-300	560	260	560	260	625	325	-	-	-	-	
301-600	560	260	560	260	625	325	-	-	-	-	
601-1050	585	285	585	285	650	350	-	-	-	-	
1051-1500	610	310	610	310	675	375	-	-	-	-	

Model	А	В	D	Е	G
EMT1000	200	220	20	20	244

Stroke	1-300	301-600	601-1050	1051-1500
EMT1000	20	30	50	70







- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x (E +5mm) thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply

- † Control tapes fitted (increase outer diameter by 20mm approximately).


 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.
- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.





E-Series Stainless Steel Screw Jacks

PERFORMANCE ENHANCED VARIANTS TO SOLVE SPECIFIC APPLICATION REQUIREMENTS



Minimise Axial Backlash for Reversing Loads

The Anti-Backlash feature provides a reliable method to regulate the axial backlash in a screw jack for applications where there is a reversal of loading from tension to compression. The amount of backlash between the screw and worm gear nut can be adjusted (adjust shell cap) to a desired amount or a practical minimum. To avoid binding and excessive wear do not adjust backlash to less than 0.025mm.

The Anti-Backlash feature also acts as a safety device, providing dual nut load carrying unit, when the worm gear becomes worn.

A visual wear indicator is available on request for all models and a "feeler" gauge can be used to measure the wear. This can be upgraded to use a sensor for wear monitoring. Consult Power Jacks for either option.



Dimensions

Upright Inverted Tension Compression Load Load A C How it works - refer p193

The dimensions for these screw jacks are the same as the standard units except those detailed below.

Model	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	ЕМТ0300	EMT0500	EMT1000
А	125	145	185	200	265	340	415	585
В	24	30	35	40	55	65	90	125
С	86	103.5	138	146.5	195	250	295	415
D	Stroke + 35	Stroke + 30	Stroke + 20	Stroke + 3	Stroke + 24	Stroke +38	Stroke + 28	Stroke + 3

E-Series - Stainless Steel Screw Jacks - Anti-Backlash - Performance

		Model			110-V0A 110-J0A		25-V0A 25-J0A		50-V0A 50-J0A	EMT0100-V0A EMT0100-J0A	
Сара	acity		kN	10		25		50		100	
Susta	ining		Tension	6.6		16.5		33		6	6
Capacit	ty (kN)	С	ompression	1	0	2	25	5	0	11	00
		Stainless Steel Worm Shaft		3	.3	8.	25	16	5.5	3	3
	Operating Capacity (kN)		Tension	6	.6	10	5.5	3	3	6	6
Capacit	ty (kN)	Worm Shaft	Compression	1	0	2	25	5	0	10	00
			mm	2	20	3	10	4	0	5	5
Lifting S	Screw ¹	Lead	Option	1	2	1	2	1	2	1	2
		Leau	mm	5	10	6	12	9	18	12	24
Gear R	Onting	Option 1		5:1		6:1		6:1		8	:1
Geal N	tatios	Option 2		20:1		24:1		24:1		24	i:1
Max. I	Input	Gea	r Ratio Option 1	0.3	375	1	.5	3	.0	3.	75
Power	- (kW)	Gear Ratio Option 2		0.19		0.0	375	0.	55	1.1	25
Start up		Gear Ratio Option 1		7.8	10.9	23.5	31.3	62.3	84.9	129.2	147.8
load (I		Gea	Gear Ratio Option 2		5.1	9.8	13.0	28.5	38.8	66.8	90.4
Weight (kg) - stro	ke = 150mi	m	2.72		8.62		16.78		26	.12
Weight (kg) per e	xtra 25mm		0.	13	0.21		0.32		0.	57
Gear		Gea	r Ratio	5	:1	6	:1	6	:1	8	:1
Ratio Option	Sc	rew Jack S	Static Efficiency	0.203	0.291	0.169	0.254	0.192	0.281	0.185	0.273
1	Scn	ew Jack Dy	namic Efficiency	0.263	0.365	0.222	0.322	0.251	0.356	0.243	0.325
Gear		Gea	r Ratio	20	D:1	24	4:1	24	i:1	24	i:1
Ratio	Sc	rew Jack S	Static Efficiency	0.109	0.157	0.102	0.153	0.105	0.154	0.119	0.176
Option 2	Option 2 Scre		rew Jack Dynamic Efficiency		0.220	0.150	0.217	0.154	0.218	0.172	0.245

		Mode	l			00-V0A 00-J0A		00-V0A 00-J0A		00-V0A 600-J0A	EMT1000-V0A EMT1000-J0A
Сарас	city		ŀ	κN	21	00	300		500		1000
Sustair	ning		Ter	sion	132		200		333		666
Capacity	y (kN)	(Compression		21	00	31	00	5	00	1000
0	.:	Stainless Steel Worm Shaft		3	.3	11	00	1	67	333	
Operat Capacity	5	Plate	d	Tension	6	.6	2	00	3	33	666
Capacity	y (IXIV)	Worm Shaft		Compression	10		31	00	5	00	1000
			n	nm	6	5	9	5	1	20	160
Lifting So	crew ¹	Lead		Option	1	2	1	2	1	2	1
		Leau		mm	12	24	16	32	16	32	20
Gear Ra		Option 1		8:1		10 2/3:1		10 2/3:1		12:1	
Gear Ra	atios	Option 2		ion 2	24	i:1	32	2:1	32	2:1	36:1
Max. In	nput	Gea	ar Rat	io Option 1	3.	75	6	.0	11	.25	18.5
Power ((kW)	Ge	Gear Ratio Option 2		1.1	25	1	.9	4	.5	8.25
Start up t		Ge	Gear Ratio Option 1		281.2	368.5	534	687	1000	1236	2243
load (N		Gea	ar Rat	io Option 2	153.7	201.4	315	405	568	702	1244
Weight (kg	g) - stro	ke = 150m	ım		4	.9	91		2	09	610
Weight (kg	g) per ex	ktra 25mm	1		0.	86	1.	58	2.	49	4.31
Gear		Ge	ar Rat	io	8	:1	10 2	2/3:1	10 2	2/3:1	12:1
Ratio Option	So	crew Jack	Static	Efficiency	0.170	0.259	0.134	0.209	0.119	0.193	0.118
1)ynam	ic Efficiency	0.226	0.332	0.184	0.277	0.163	0.256	0.160
Gear		Ge	ar Rat	io	24	i:1	32	2:1	32	2:1	36:1
Ratio	So	crew Jack	Static	Efficiency	0.104	0.158	0.076	0.118	0.070	0.113	0.071
2	Option)ynam	ic Efficiency	0.151	0.222	0.115	0.173	0.105	0.165	0.106

Note


- 1. All metric machine screws have a trapezoidal thread form.
- 2. For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- ${\it 3. Efficiency \, values \, for \, standard \, grease \, lubricated \, worm \, gear \, box \, and \, lifting \, screw.}$
- ${\it 4. All E-Series screw\ jacks\ have\ grease\ lubricated\ gearbox\ and\ lead\ screw\ as\ standard.}$

Linear Movement for Rotationally Unconstrained Loads


The Anti-Rotation feature for translating screw jacks stops the lifting screw from rotating without the need for end fixing. This is done by keying the lifting screw.

Benefits:

- · Compact unit integrates anti-rotation into gearbox
- Dimensions are the same as the standard translating screw jack
- Standard round cover pipe for easy installation
- · Proven industrial anti-rotation design



Dimensions



Dimensions for Upright Models with Anti-Rotation (Keyed)

The Dimensions for upright E-Series machine screw jacks with anti-rotation (keyed) mechanism are the same as the standard screw jacks without the feature.

Dimensions for Inverted Models with Anti-Rotation (Keyed)

The dimensions for these screw jacks are the same as the standard units except those detailed below.

Model	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000
А	78	125.5	159	167.5	210	267	307	445
В	Stroke + 35	Stroke + 30	Stroke + 20	Stroke + 3	Stroke -1	Stroke + 15	Stroke + 13	Stroke + 3
øC	N/A	60	75	90	102	141.5	180	236

E-Series - Stainless Steel Screw Jacks - Anti-Rotation (Keyed) - Performance


		Model			110-VK0 110-JK0		25-VK0 25-JK0	EMT00 EMT00			00-7K0 00-AK0		
Сара	acity		kN		10	2	25	5	0	1	00		
Susta	ining		Tension	6	6	16	5.5	3	3	6	6		
Capacit	ty (kN)	С	ompression	•	10	2	25	5	0	1	00		
		Stainles	s Steel Worm Shaft	3.3		8.	25	16	.5	3	3		
Opera Capacit	9	Plated Worm	Tension	6.6		16	3.5	3	3	6	6		
'	Shaft Compression		Compression		10	2	25	5	0	1	00		
		mm		2	20	3	80	4	0	5	5		
Lifting 9	Screw ¹			1	2	1	2	1	2	1	2		
	Lead mm		mm	5 10		6	12	9	18	12 24			
Gear R	Option 1		Option 1	5	:1	6	:1	6	:1	8	:1		
Geark	Ratios		Option 2	2	D:1	24:1		24:1		24	¥:1		
Max. I	Input	Gea	r Ratio Option 1	0.375		1	.5	3	.0	3.	75		
Power	- (kW)	Gea	Gear Ratio Option 2		0.19		0.375		0.55		125		
Start up		Gea	r Ratio Option 1	7.1	9.9	20.8	27.7	58.7	80	121.7	164.7		
load (I		Gea	r Ratio Option 2	3.1	4.4	9.2	12.2	26.8	36.6	63.6	86.1		
Weight (k	kg) - stro	ke = 150mi	m	2	.27	8.	17	15	.88	24	.72		
Weight (k	kg) per ex	xtra 25mm		0.	.13	0.	21	0.	32	0.	57		
Gear		Gea	Gear Ratio		Gear Ratio		:1	6	:1	6	:1	8	:1
Ratio Option	Screw Jack Static Efficiency		0.224	0.322	0.191	0.287	0.203	0.299	0.196	0.290			
1	Scr	ew Jack Dy	namic Efficiency	0.291	0.403	0.251	0.364	0.267	0.378	0.258	0.368		
Gear			2	D:1	24	¥:1	24:1		24:1				
Ratio Option	Sc	rew Jack S	Static Efficiency	0.127	0.182	0.108	0.162	0.111	0.163	0.125	0.185		
2	Screw Jack Dynamic Efficiency		namic Efficiency	0.184	0.255	0.159	0.230	0.164	0.232	0.180	0.257		

		Model			200-JK0 200-JK0		800-7K0 800-AK0		00-7K0 00-AK0	EMT1000-VK0 EMT1000-JK0
Сара	icity		kN	2	00	3	00	5	00	1000
Sustai	ining		Tension	2	00	3	00	5	00	1000
Capacit	ty (kN)	Co	mpression	1	32	2	00	3:	33	666
		Stainless Steel Worm Shaft		2	00	3	00	5	00	1000
Opera		Plated Tension Worm		3	3.3	1	00	1	67	333
Capacit	ty (kN)	Shaft Compression		6	5.6	2	00	3:	33	666
		mm		•	10	3	00	5	00	1000
Lifting S	Screw ¹	Lead Option		(55	9	25	1:	20	160
		Lead mm		12	24	16	32	16	32	20
Gear R)ation		Option 1	8	3:1	10 2	2/3:1	10 2	2/3:1	12:1
Geal K	เสเเบร		Option 2	2	4:1	32	2:1	32	36:1	
Max. Ii	nput	Gear	Ratio Option 1	3.	.75	6	.0	11	.25	18.5
Power	(kW)	Gear	Ratio Option 2	1.125		1.9		4.5		8.25
Start up		Gear	Ratio Option 1	275.3	360.7	506	651	947	1170	2125
load (N		Gear	Ratio Option 2	144	188.7	298	384	526	650	1126
Weight (k	kg) - stro	ke = 150mr	n	4	45	8	36	1'	95	553
Weight (k	kg) per e	xtra 25mm		0.	.86	1.	58	2.	49	4.31
Gear		Gear	Ratio	8	B:1	10 2	2/3:1	10 2	2/3:1	12:1
Ratio Option	Sc	crew Jack Static Efficiency		0.173	0.265	0.142	0.220	0.126	0.204	0.125
1	Scr	crew Jack Dynamic Efficiency		0.230	0.34	0.195	0.292	0.172	0.270	0.169
Gear			2.	4:1	32	2:1	32	2:1	36:1	
Ratio Option	Sc	rew Jack S	tatic Efficiency	0.111	0.169	0.080	0.124	0.076	0.122	0.079
2	Scr	Screw Jack Dynamic Efficiency		0.161	0.237	0.121	0.182	0.144	0.178	0.117

Note

- 1. All metric machine screws have a trapezoidal thread form.
- $2. For loads of 25\% \ to \ 100\% \ of \ screw \ jack \ capacity, \ torque \ requirements \ are \ approximately \ proportional \ to \ the \ load.$
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw.
- 4. All E-Series screw jacks have grease lubricated gearbox and lead screw as standard.

Combine Anti-Backlash & Anti-Rotation in One Screw Jack



Dimensions for E-Series Stainless Steel Screw Jacks with Anti-Backlash & Anti-Rotation

Model	EMT0010-VKA EMT0010-JKA	EMT0025-VKA EMT0025-JKA	EMT0050-VKA EMT0050-JKA	EMT0100-VKA EMT0100-JKA	EMT0200-VKA EMT0200-JKA	EMT0300-VKA EMT0300-JKA	EMT0500-VKA EMT0500-JKA	EMT1000-VKA EMT1000-JKA
ØE	38	60	75	90	102	138	206	264
F	Stroke + 9	Stroke + 30	Stroke + 20	Stroke + 3	Stroke + 24	Stroke + 15	Stroke + 13	Stroke + 28
G	30	37	40	37	58	73	58	180
Н	24	30	35	30	55	65	55	125
I	45	55	65	55	110	115	110	405
J	16	19.5	24	19.5	39	43	39	145

The dimensions for these screw jacks are the same as the Anti-Backlash units except those detailed above.

E-Series - Stainless Steel Screw Jacks - Anti-Backlash & Anti-Rotation (Keyed) - Performance

		Model)10-VKA)10-JKA		25-VKA 25-JKA		50-VKA 50-JKA	2	00-VKA 00-JKA
Сара	acity		kN		10	2	25	5	50	10	00
Susta	ining		Tension	(5.6	10	6.5	3	13	6	6
Capacit	ty (kN)	(Compression		10	2	25	5	i0	10	00
		Stainless Steel Worm Shaft		3	3.3	8.	.25	16	5.5	3	3
Opera				(5.6	10	6.5	3	13	6	6
Capacit	Shaft Compression		Communication	10		2	25	5	50	10	00
	mm			20	3	30	4	0	5	5	
Lifting 9	Screw ¹	v ¹		1	2	1	2	1	2	1	2
	Lead mm		5 10		6	12	9	18	12	24	
Gear F	2-1:		Option 1	į	5:1	6	:1	6	:1	8	:1
Gear R	Ratios		Option 2	2	0:1	24:1		24:1		24	i:1
Max. I	Input	Gea	r Ratio Option 1	0.375		1	.5	3	.0	3.	75
Power	- (kW)	Gea	Gear Ratio Option 2		0.19		0.375		0.55		25
Start up		Gea	r Ratio Option 1	8.3	11.5	24.8	33	65.6	89.3	136	184
load (I		Gea	r Ratio Option 2	3.8	5.3	10.3	13.7	30	40.9	70.3	958.2
Weight (I	kg) - stro	ke = 150m	m	2	.72	8.	.62	16	.78	26	.12
Weight (I	kg) per e	xtra 25mm	ı	0	.13	0.	.21	0.	32	0.	57
Gear		Gea	ır Ratio	į	5:1	6	:1	6	:1	8	:1
Ratio Option	So	Screw Jack Static Efficiency		0.193	0.277	0.161	0.241	0.182	0.267	0.176	0.259
1	Screw Jack Dynamic Efficiency		0.250	0.346	0.211	0.306	0.239	0.338	0.231	0.330	
Gear	0001.110110		2	0:1	24	4:1	24	4:1	24	i:1	
Ratio Option	Sc	crew Jack	Static Efficiency	0.104	0.149	0.097	0.145	0.100	0.146	0.113	0.167
2	tion		0.151	0.209	0.142	0.206	0.146	0.208	0.163	0.233	

		Model				:00-VKA :00-JKA		00-VKA 00-JKA		00-VKA 00-JKA	EMT1000-VKA EMT1000-JKA
Сара	city			kN	2	00	30	00	50	00	1000
Sustai			Te	nsion	1	32	20	00	33	33	666
Capacit	y (kN)	С	Comp	oression	2	00	300		50	00	1000
0		Stainless Steel Worm Shaft			6	56	10	00	10	67	333
Opera Capacit		Plate		Tension	1	32	20	00	33	33	666
	acity (KIN) Worm		Compression	2	00	30	00	50	00	333	
		mm		ć	55	9	5	1:	20	160	
Lifting S	Screw ¹	Lead		Option	1	2	1	2	1	2	1
		Lead mm		12	24	16	32	16	32	20	
Gear R	ation		Ор	tion 1	8	:1	10 2/3:1		10 2/3:1		12:1
Geal K	atios		Option 2		24:1		32	2:1	32	2:1	36:1
Max. Ii		Gea	Gear Ratio Option 1		3.	.75	6	.0	11	.25	18.5
Power	(kW)	Gea	r Ra	tio Option 2	1.125		1	.9	4	.5	8.25
Start up		Gea	r Ra	tio Option 1	296	387.9	562	723	1052	1301	2361
load (N		Gea	ır Ra	tio Option 2	161.8	387.9	331	426	598	739	1309
Weight (k	kg) - stro	ke = 150m	nm			19	9	1	20	09	610
Weight (k	kg) per e	xtra 25mn	n		0.	.86	1.	58	2.	49	4.31
Gear		Gea	ır Ra	tio	8	:1	10 2	2/3:1	10 2	2/3:1	12:1
Ratio Option	Sc	Screw Jack Static Efficiency		0.161	0.246	0.128	0.198	0.113	0.184	0.112	
1	Screw Jack Dynamic Efficiency		nic Efficiency	0.214	0.316	0.175	0.263	0.155	0.243	0.152	
Gear		Gea	ır Ra	tio	24	4:1	32	2:1	32	2:1	36:1
Ratio Option	Sc	rew Jack	Stati	c Efficiency	0.098	0.150	0.072	0.112	0.067	0.108	0.068
2	Scre	ew Jack D	ynam	nic Efficiency	0.143	0.211	0.109	0.164	0.100	0.157	0.100

Note


- 1. All metric machine screws have a trapezoidal thread form.
- 2. For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.
- ${\it 3. Efficiency \, values \, for \, standard \, grease \, lubricated \, worm \, gear \, box \, and \, lifting \, screw.}$
- ${\it 4. All E-Series screw\ jacks\ have\ grease\ lubricated\ gearbox\ and\ lead\ screw\ as\ standard.}$

Extra Safety for Critical Applications

Power Jacks metric machine screw jacks can be fitted with a safety nut, which provides 2 safety roles:

- In the event of excessive wear on the nut thread the load will be transferred from the standard nut to the safety nut. This will also provide visual wear indication as the gap between the safety nut decreases to zero as the standard lifting nut wears.
- 2. In the unlikely event of catastrophic nut thread failure the safety nut will sustain the load. The safety of industrial and human cargo is therefore improved.

There are several configurations for each safety nut device as they only work in one load direction. For this reason when ordering please supply a sketch of your application showing load directions.




All Safety Nuts are BS EN 1570 Compliant


Translating Screw Jacks with Safety Nuts

Tension Safety Nut

A C Load Load Load V E

Compression Safety Nut






Dimensions - Translating Screw

Model	Rating (kN)	А	В	С	D	ØE	F	G	Н	1	J
EMT0010	10	125	24	86	Stroke + 35	38	Stroke + 9	30	24	45	16
EMT0025	25	145	30	104	Stroke + 30	60	Stroke +30	37	30	55	20
EMT0050	50	185	35	138	Stroke + 20	75	Stroke + 20	40	35	65	24
EMT0100	100	200	40	146	Stroke +3	90	Stroke + 28	48	40	80	30
EMT0200	200	265	55	195	Stroke +24	102	Stroke + 24	58	55	110	39


Rotating Screw Jacks with Safety Nuts



Dimensions - Rotating Screw

Model	Rating (kN)	А	В	С	D	ØE	ØF	G
EMR0010	10	Stroke + 76	30	66.5	12	80	35	4 x Ø11, Ø57 PCD
EMR0025	25	Stroke + 95	33.5	75	15	90	40	4 x Ø13.5, Ø65 PCD
EMR0050	50	Stroke + 140	58	125	20	115	55	4 x Ø18, Ø85 PCD
EMR0100	100	Stroke + 170	67	145	25	160	80	4 x Ø22, Ø120 PCD
EMR0200	200	Stroke + 170	67	145	25	185	90	4 x Ø26, Ø135 PCD
EMR0300	300	Stroke + 310	126	270	35	230	125	6 x Ø26, Ø175 PCD
EMR0500	500	Stroke + 335	130	284	50	280	160	6 x Ø33, Ø220 PCD
EMR1000	1000	Stroke + 410	155	335	60	380	210	6 x Ø45, Ø295 PCD







Model	А	В	С	D	ØE	F	ØG
EMR0010	Stroke + 61	52	35	12	35	4 x Ø11, Ø57 PCD	80
EMR0025	Stroke + 80	60	40	15	40	4 x Ø13.5, Ø65 PCD	90
EMR0050	Stroke + 100	85	65	20	55	4 x Ø18, Ø85 PCD	115
EMR0100	Stroke + 120	95	75	25	80	4 x Ø22, Ø120 PCD	160
EMR0200	Stroke + 120	95	75	25	90	4 x Ø26, Ø135 PCD	185
EMR0300	Stroke + 200	160	140	35	125	6 x Ø26, Ø175 PCD	230
EMR0500	Stroke + 225	175	150	50	160	6 x Ø33, Ø220 PCD	280
EMR1000	Stroke + 275	200	175	60	210	6 x Ø45, Ø295 PCD	380

Secondary Guide - Greater Lateral Rigidity for Lifting Screw


Secondary Guiding for the screw for greater lateral rigidity aiding screw guidance and improved side load resilience.






Dimensions for Screw Jacks with Secondary Guides

Mode	ι	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000
	ØΑ	38	60	70	90	100	138	155	225
Upright	В	Stroke + 34	Stroke + 30	Stroke + 20	Stroke + 29	Stroke + 24	Stroke + 40	Stroke + 38	Stroke + 50
	С	20	20	18	20	20	38	38	65
	ØD	N/A	60	70	90	100	138	155	
Inverted	Е	Stroke + 34	Stroke + 30	Stroke + 20	Stroke + 29	Stroke + 24	Stroke + 40	Stroke + 38	On Request
	F	N/A	20	18	20	20	38	38	





Model	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000
Capacity (kN)	10	25	50	100	200	300	500	1000
Style	1	2	2	2	2	2	2	
A	180	213	260	352	428	492	570	
В	145	170	210	247	313	367	440	
С	35	43	50	105	115	125	130	
D	20	23	30	33	40	60	75	On Request
E	33.4	48.3	60.3	73	102	133	168] '
F	20	30	35	40	50	80	110	
ØG	12	16	20	22	30	45	60	
Max Stroke at Rated Load (Compression)	175	352	420	593	592	1338	1920	


Note: All dimensions in millimetres unless otherwise stated.

E-Series Ball Screw Jack

HIGH EFFICIENCY BALL SCREW JACK IN A COMPACT DESIGN WITH INTEGRATED SAFETY DEVICE.

Overall operating efficiency is as high as 70% in some models, depending on the worm gear ratio.





Translating Screw





Upright Inverted

Rotating Screw





Inverted

Typical Applications

Ball Screw Jacks are generally used when the application has a relatively high duty cycle or the input power for a given screw jack is to be minimised. The high efficiency of the ball screw & nut significantly increase the efficiency of a screw jack in comparison to a Machine Screw Jack. Due to their high efficiency they nearly always require a brake to hold position. They are used in a wide variety of applications including Automotive, Steel, Glass, Defence, Nuclear and Solar industries.

Standard Designs

The standard E-Series ball screw jack is available in translating and rotating screw designs in capacity sizes from 10kN to 500kN. The design is optimised for performance and a compact form, which includes an added safety device as standard for most models. There is a large selection of options and accessories (section-7) that allows you to configure a standard design that is just right for your application. These options include Zero-Backlash and Anti-Rotation designs.

Special Designs

We can fully customise our screw jacks so that your application can be the best.

Customisation can be anything from a small modification such as an extra bolt hole on an end fitting to a completely new design of screw jack based on our class leading technology.

For more details please see the Special Screw Jack information in Section-8 or contact us today with your requirements. Our team are looking forward to working with you.

Selecting the Right Screw Jack

Consider all application constraints then choose a product that looks suitable for the intended application. Calculate the power and torque requirements. This is a 5 step process:

- Screw Jack Input Speed (RPM)
- Operating Input Power (kW)
- Operating Input Torque (Nm)
- Screw Jack Start-up Torque (Nm)
- Mechanical Power and Torque Check

Systems

The screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearbox, drive shafts, couplings, plummer blocks and motion control devices.

The use of bevel gearboxes allows the distribution of drive throughout a jacking system. The gearboxes come in 2,3 and 4 way drive types. See the Bevel Gearbox Section-10 for more details.

Bevel gearboxes and other system components can also be supplied in stainless steel or other corrosion resistant designs.

Two of the most popular system configurations are the 'H' and 'U' configured jacking systems. Remember that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.



If multiple ball screw jacks are connected in a mechanically linked system then the complete system in some designs may be considered self-locking. If you would like this checked consult Power Jacks. Alternatively, to be sure, include a brake on the system either as a stand alone device or as a brake motor.

Application Focus

POWERJACKS









CAVENDISH LABORATORY ANTENNA DISH

Position adjustment of Arcminute Microkelvin Imager (AMI) to achieve a pointing accuracy of better than half a minute of arc (1/120 of a degree). 10 x antenna dishes all in close proximity of each other. Measuring the weight of the universe by analysing "dark matter".

10 x off 50kN E-Series special metric ball screw jacks based on EBT0050 in translating screw configuration with a stroke of 1050mm. These ball screw jacks operate in normal UK outdoor conditions and allow the antenna to operate at wind speeds of up to 50mph.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.



Screw Jack Standard Performance

	Model		EBT0010 EBR0010		0025 0025		0050 0050		0100 0100		0200 0200	EBT0300 EBR0300	EBT0500 EBR0500
	Capacity (kN)	10	2	:5	5	50	10	00	20	00	300	500
1.16.1	Diar	neter (mm)	20	2	5	4	0	5	0	6	3	80	
Lifting Screw	Lead	Option	1	1	2	1	2	1	2	1	2	1	
	Leau	Lead (mm)	5	5	10	10	20	10	20	10	20	20	
Gear Ratios		Option 1	5:1	6	:1	6	:1	8	:1	8	:1	10 2/3:1	
Ocui Nutios	Option 2		20:1	24	::1	24	4:1	24	::1	24	4:1	32:1	
Turn of worm for travel	Option 1 6 Turn		6mm	5mm	10mm	10mm	20mm	7.5mm	15mm	7.5mm	15mm	11.25mm	
of Lifting Screw	Option	2 24 Turn	6mm	5mm	0mm	10mm	20mm	10mm	20mm	10mm	20mm	7.5mm	
Maximum	Gear I	Ratio Option 1	0.375	1	.5	;	3	3.	75	3.	75	6.0	
Input Power (kW)			0.19	0.3	375	0.	55	1.1	125	1.1	125	1.9	
Start-up Torque at	Gear I	Ratio Option 1	2.7	5.9	11.1	23.4	44.6	36.4	68.5	75.2	139.4	182	lest
full load (Nm) †	Gear I	Ratio Option 2	1.2	2.6	4.9	10.7	20.4	19.1	35.8	39.4	72.9	107.3	On Request
Maximum Th	rough Tor	que (Nm)	20	59		10	68	34	47	39	96	1440	ō
Lead Screw F	Restraining	Torque (Nm)	9	23	43	88	167	181	340	370	690	1030	
Worm Shaft I	Maximum	Radial Load (N)	325	38	30	7.	40	10	00	16	00	2170	
Maximum Inp	out Speed	(rpm)	1800	18	00	18	300	18	00	18	100	1800	
Gear Case M	aterial		Aluminium	SG	Iron	SG	Iron	SG	Iron	Sto	eel	Seel	
Weight (kg) -	stroke	EMT	2.36	8.	45	14	4.9	24	1.3	42	2.4	92.4	
= 150mi	= 150mm EMR		2.6	8.	85	16	.54	28	3.8	49	.58	113.78	
	Weight (kg) - per EMT		0.11	0.	21	0.	32	0.	58	0.	84	1.55	
extra 25n	extra 25mm EMR		0.05	0.	11	0.	0.19		0.36		52	1.13	
Ball	Nut Safet	/ Device	On Request	Stan	dard	Stan	ndard	Stan	dard	Stan	dard	On Request	

[†] For loads of 25% to 100% of screw jack capacity, torque requirements are approximately proportional to the load.

Efficiency - Option 1 Gear Ratio

Model	EBT0010 EBR0010		0025 0025		0050 0050		0100 0100		0200 0200	EBT0300 EBR0300	EBT0500 EBR0500
Gear Ratio	5:1	6	:1	6	:1	8	:1	8	:1	10 2/3:1	st
Lifting Screw Lead (mm)	5	5	10	10	20	10	20	10	20	20	enb
Static Efficiency	0.603	0.565	0.600	0.567	0.595	0.546	0.581	0.529	0.571	0.492	Re
Dynamic Efficiency	0.681	0.662	0.692	0.663	0.687	0.645	0.674	0.631	0.665	0.595	o o

Efficiency - Option 2 Gear Ratio

Model	EBT0010 EBR0010	EBT0025 EBR0025			0050 0050		0100 0100	EBT0200 EBR0200		EBT0300 EBR0300	EBT0500 EBR0500
Gear Ratio	20:1	24	::1	24	::1	24	::1	24	:1	32:1	st
Lifting Screw Lead (mm)	5	5	10	10	20	10	20	10	20	20	dne
Static Efficiency	0.341	0.320	0.340	0.310	0.325	0.348	0.370	0.337	0.364	0.278	Re
Dynamic Efficiency	0.429	0.419	0.438	0.407	0.422	0.450	0.470	0.440	0.465	0.371	o_

Note

1. Efficiency values for standard grease lubricated worm gear box and lifting screw.


POWERJACKS

Power Jacks ball nut employs the internal ball transfer system for recirculating the balls. This design provides for:

- · Robust design
- Small ball nut body outer diameter
- Smooth movement
- Less turns per circuit
- Absence of parts liable to wear.

Solid formed nylon wiper seals on the ball nut prevents ingress of foreign matter and retain lubrication within the nut.





Standard

Ball Screw Life

Theoretical service life can be expressed in either L_{10} 10^6 revolutions or L_h 10^3 hours or L_d kilometres. As the life of a ball screw is determined by metal fatigue it is not possible to accurately predict life. However, it is practical to suppose that 90% of a sufficiently large number of equally sized ball screws running under equal working conditions will reach L_{10} or L_h without evidence of material fatigue. The L_{10} ball screw life is rated using the Dynamic Capacity, which is the maximum constant axial load that can be applied in running conditions for a life of 1.10^6 revolutions of the ball screw. This can be expressed in linear travel $\{L_d\}$.

Where **L**10= Service Life (millions of revolutions)

 $\mathbf{L}_{d} = \mathbf{L}_{10} * \mathsf{P}$ $\mathbf{L}_{d} = \mathsf{Service Life (km)}$

P = Pitch of Ball Screw (mm)

Li	near Travel L _d ir	ı km					Woı	orking Load (kN)					
Model	Capacity (kN)	Pitch (mm)	5	10	25	30	50	75	100	150	200	250	300
E28501	10	5	20.5	2.5	-	-	-	-	-	-	-	-	-
E3802	25	5	381	48	3	-	-	-	-	-	-	-	-
E38021	25	10	1 775	222	14	-	-	-	-	-	-	-	-
E3805	50	10	11 978	1 497	96	55	12	-	-	-	-	1	-
E38051	50	20	17 039	2 130	136	79	17	-	-	-	-	-	-
E3810	100	10	32 287	4 036	258	149	32	10	4	-	-	-	-
E38101	100	20	38 503	4 813	308	178	39	11	5	-	-	-	-
E3820	200	10	162 327	20 291	1 299	752	162	48	20	6	3	-	-
E38201	200	20	320 060	40 008	2 560	1 482	320	95	40	12	5	-	-
E3830	300	20	903 882	112 985	7 231	4 185	904	268	113	33	14	7	4


Use the following formulae to calculate the service life in terms of hours running:

n_m= Mean Screw Jack Input Speed (rpm)

Gr = Gear Ratio

Note: 1. Ball screw life based on dynamic load calculated according to DIN69051 Part 4.

Extra Safety As Standard with Integral Safety Device



25kN TO 200kN Power Jacks Metric Ball Screw Jacks have an integral safety device as standard. This provides two important safety roles:

- 1. In the unlikely event of an excessive wear in the ball screw drive, the safety device will contact the screw shaft and act as an "ACME" Thread. This will provide early warning of any possible ball screw failure and is capable of providing drive in the event of any such failure. This can allow a control system to alert an operator to wear of this kind by monitoring the increase in motor current required to drive the system due to the increased friction generated by the device.
- 2. It allows the ball nut on the screw jack to sustain a load in the event of catastrophic ball failure. The safety of industrial and human cargo is therefore improved. Ball screw systems without this device could collapse under load or drop the carried load.

Note: Model 10kN & 300kN ball screw jack does not have safety device as standard, if required consult Power Jacks Ltd.


Optimal Ball Nut Alignment & Load Capability

Better by Design Power Jacks Ball Screw Jacks mount the upper load bearing directly on top of the gear the same as all other screw jacks in our range.

Advantages:

- A. Compact Design
- B. Optimum Gear Holding & Accuracy







132

10kN Translating

Upright EBT0010-U00



Inverted EBT0010-I00



Performance

Model			EBR0010 EBT0010	
Capacity		kN	10	
	Diame	ter (mm)	20	
Lifting Screw	Lead	Option	1	
	Leau	mm	5	
	Gear Ratio	1	5:1	
Gear Ratio Option 1	Static Effic	ciency	0.603	
	Dynamic E	fficiency	0.681	
	Gear Ratio)	20:1	
Gear Ratio Option 2	Static Effic	iciency 0.341		
	Dynamic E	fficiency	0.429	
Max. Input	Gear Ratio	Option 1	0.375	
power (kW)	Gear Ratio	Option 2	0.18	
Start up torque	Gear Ratio	Option 1	2.7	
(Nm)	Gear Ratio	Option 2	1.2	

Model		EBR0010 EBT0010			
Capacity	kN		1	0	
Lifting Screw l	5				
Turn of worm for travel of lifting screw	Gear Ratio 1	6 Turn	6mm		
	Gear Ratio 2 24 Turn		6mm		
Maximum Thr	20				
Lifting Screw F	Restraining Torq	ue (Nm)	9		
Worm Shaft M (N)	aximum Radial l	_oad	325		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Alum	inium	
Waight (kg)	traka - 150mm		EMT	2.36	
Weight (kg) - s		EMR	2.6		
Waight (kg)	troko	EMT	0.11		
Weight (kg) - p	stroke	EMR 0.05			
Note: All dimension	on in millimetres un	less otherv	vise stated.		

Note: All dimension in millimetres unless otherwise stated Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	C
	Fork End	
	Rod End	

Upright EBR0010-U00

6 HOLES Ø7 ON 45 P.C.D.


31.83 31.75 KEY 25 x 5 x 5 Ø14 h8 , LHS 130 150 8 50 65 RHS 36

102



35

Inverted EBR0010-I00




Closed Height & Bellows Boots


Column Strength

Closed	Thread	ed End	Top I	Plate	Clevis End Fork End		End	Rod End		
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted
EBT0010	125	45	125	45	145	65	148	98	150	70
Stroke (mm)	EBT0010 with Bellows Boots									
1-300	166	61	166	61	186	81	189	84	209	104
301-600	182	77	182	77	202	97	205	100	225	120
601-1050	206	101	206	101	226	121	229	124	249	144
1051-1500	230	125	230	125	250	145	253	148	273	168

Model	А	В	D	Е	G
EBT0010	30	70	12	12	114

Stroke	1-300	301-600	601-1050	1051-1500
EBT0010	16	32	56	80






Note:


- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 10mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick.

 Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

 For horizontal installations with than 450 mm of stroke, internal boot guides are recommended.


- Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.







Upright EBT0025-U00

Inverted EBT0025-I00







Model						
Capacity		kN	25			
	Diame	ter (mm)	2	5		
Lifting Screw	Lead	Option	1	2		
	Leau	mm	5	10		
	Gear Ratio		6:	:1		
Gear Ratio Option 1	Static Effic	iency	0.565	0.600		
	Dynamic E	fficiency	0.662	0.692		
	Gear Ratio		24	:1		
Gear Ratio Option 2	Static Effic	iency	0.320	0.340		
	Dynamic E	fficiency	0.419	0.438		
Max. Input	Gear Ratio	Option 1	1.5			
power (kW)	Gear Ratio	Option 2	0.375			
Start up torque	Gear Ratio	Option 1	5.9	11.1		
(Nm)	Gear Ratio	Option 2	2.6	4.9		

Model				0025 0025	
Capacity	kN		2	5	
Lifting Screw l	5	10			
Turn of worm for travel of lifting screw	Gear Ratio 1	6 Turn	5mm	10mm	
	Gear Ratio 2	24 Turn	5mm	10mm	
Maximum Thr	59				
Lifting Screw F	Restraining Torq	ue (Nm)	23	43	
Worm Shaft M (N)	aximum Radial I	_oad	380		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		SG Iron		
Waight (kg)	troko – 150mm		EMT	8.45	
Weight (kg) - s		EMR	8.85		
Woight (kg)	stroko	EMT	0.21		
Weight (kg) - p	stroke	EMR	0.11		
Note: All dimension	n in millimetres un	less other	vice stated		


Note: All dimension in millimetres unless otherwise stated Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EBR0025-U00

POWERJACKS

Inverted EBR0025-I00





Closed Height & Bellows Boots

Column Strength

Fixed

Closed	TI	nreade	d End		Top Pl	ate		Clevis	End		Fork E	End		Rod E	nd	25kN METRIC BALLSCREW JACK									
Height "C"	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	Upr	right	Inverted	Upr	right	Inverted		3000		T	2011111			T T		
EBT0025	1.	45	55	14	¥5	55	1	70	80	194		104	1	90	100	(9 ¥ 250		Ballscre	w - 25n	mm Dia x	5mm	ead			
Stroke (mm)						EE	T0025	with B	ellows Bo	ws Boots						LOAD					$\setminus \mid$				
Lead (mm)	5	10	5 & 10	5	10	5 & 10	5	10	5 & 10	5	5 10 5 & 10		5	10	5 & 10	SSIVE	2000				\forall	_		+	
1-300	180	200	100	180	200	100	205	225	125	229	229 249		240 260		160	2500 2000 COMPRESSIVE LOAD (KG) 1500 1500 1500 1600 1600 1600 1600 1600					\				
301-600	190	210	110	190	210 110		215	235	135	239	259	159	250	270	170	0 E	1300								
601-1050	210	230	130	210	230	130	235	255	155	259	279	179	270	290	190	ISSIBI	1000				+	\rightarrow	+		
1051-1500	230	250	150	230	250	150	255	275	175	279	299	199	290	310	210	PERA	500					`			
Model EBT0025	A B D E 40 66 15 15					G ØA									PINNED/PINNED 200 400 800 600 1000 1200					600	700				
Stroke	1-3	00	301-6	00	601-	-1050	1051-	1500	1				_			· '	Note						ead colu ig Guide		ength
EBT0025	20)	30		5	50	70				ØB ØG						Fre	е		Pin	ned	Gui	ded		
Note: 1																									


Fixed

Pinned


50kN Translating

Upright EBT0050-U00

Inverted EBT0050-I00 170



Ø60.3



Performance

Model			EBT0050 EBR0050				
Capacity		kN	5	0			
	Diame	ter (mm)	4)			
Lifting Screw	Lead	Option	1	2			
	Leau	mm	10	20			
	Gear Ratio		6	:1			
Gear Ratio Option 1	Static Effic	iency	0.567	0.595			
	Dynamic E	fficiency	0.633	0.687			
	Gear Ratio		24	:1			
Gear Ratio Option 2	Static Effic	iency	0.310	0.325			
	Dynamic E	fficiency	0.407	0.422			
Max. Input	Gear Ratio	Option 1	3.0				
power (kW)	Gear Ratio	Option 2	0.	55			
Start up torque at full load (Nm)	Gear Ratio	Option 1	23.4	44.6			
	Gear Ratio	Option 2	10.7	20.4			


Model			EBT EBR						
Capacity	kN		5	0					
Lifting Screw (mm)		10	20					
Turn of worm for	Gear Ratio 1	6 Turn	10mm	20mm					
travel of lifting screw	24 Turn	10mm	20mm						
Maximum Thr	n)	16	58						
Lifting Screw F	Restraining Torq	ue (Nm)	88	167					
Worm Shaft M (N)	aximum Radial l	_oad	740						
Maximum Inpu	ut Speed (rpm)		18	00					
Gear Case Ma	terial		SG	Iron					
Waight (kg)	traka – 150mm		EMT	14.9					
Weight (kg) - s		EMR	16.54						
Waight (kg)	or outro 25mm	stroko	EMT	0.32					
Weight (kg) - per extra 25mm stroke EMR 0.19									
Note: All dimension	on in millimetres un	less otherv	vise stated.						


Designs subject to change without notice

Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EBR0050-U00

Inverted EBR0050-I00






Closed Height & Bellows Boots


Column Strength

Closed	Th	reade	d End		Top Plate			Clevis End			Fork E	nd	Rod End			
Height "C"	Upright		Inverted	Upright		Inverted	Upr	ight	Inverted	Upright		Inverted	Upr	ight	Inverted	
EBT0050	185		65	18	85 65		210		90	248		128	24	42	122	
Stroke (mm)						EB	BT0050 with Bellows Boo			ots						
Lead (mm)	10 20		10 &20	10	20	10 & 20	10	20	10 & 20	10	20	10 &20	10	20	10 &20	
1-300	230	270	105	230	270	105	255	295	130	293	333	168	302	342	177	
301-600	240	280	115	240	280	115	265 305		140	303 343		178	312	352	187	
601-900	255	295	130	255 295		130	280 320		155	318 358		193	327	367	202	
900-1050	260 300		135	260	300	135	285	325	160	323	363	198	332	372	207	
1051-1500	280 320		155	280	320	155	305	345	180	343	383	218	352	392	227	

Model	А	В	D	E	G
EBT0050	50	85	15	15	140

Stroke	1-300	301-600	601-900	901-1050	1050 -1500
EBT0050	20	30	45	50	70







Note:

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 15mm Inverted Screw Jacks Recommended bellows boot mounting plate ØB x [E +5mm] thick. Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

- For horizontal installations with than 450 mm of stroke, internal boot guides are recommended. Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar.
- Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.




Note: For 40mm Dia x 20mm lead column strength chart refer to Engineering Guide




100kN Translating

Upright EBT0100-U00

Inverted EBT0100-I00





Model			EBT0100 EBR0100					
Capacity		kN	10	00				
	Diame	ter (mm)	5	0				
Lifting Screw	Lead	Option	1	2				
	Leau	mm	10	20				
	Gear Ratio		8:1					
Gear Ratio Option 1	Static Effic	iency	0.546	0.581				
	Dynamic E	fficiency	0.645	0.674				
	Gear Ratio		24	i:1				
Gear Ratio Option 2	Static Effic	iency	0.348	0.370				
	Dynamic E	fficiency	0.450	0.470				
Max. Input	Gear Ratio	Option 1	3.75					
power (kW)	Gear Ratio	Option 2	1.1	125				
Start up torque at full load (Nm)	Gear Ratio	Option 1	36.4	68.5				
	Gear Ratio	Option 2	19.1	35.8				

Model			EBT(EBR)							
Capacity	kN		10	00						
Lifting Screw (mm)		10	20						
Turn of worm for	Gear Ratio 1	6 Turn	7.5mm	15mm						
travel of lifting screw	10mm	20mm								
Maximum Thr	n)	347								
Lifting Screw F	Restraining Torq	ue (Nm)	181	340						
Worm Shaft M (N)	aximum Radial l	_oad	1000							
Maximum Inpu	ut Speed (rpm)		1800							
Gear Case Ma	terial		SG Iron							
Waight (kg)	traka - 150mm		EMT	24.3						
Weight (kg) - s		EMR	28.8							
Waight (kg)	troko	EMT	0.58							
Weight (kg) - per extra 25mm stroke EMR 0.36										
Note: All dimension	lote: All dimension in millimetres unless otherwise stated.									


Note: All dimension in millimetres unless otherwise stated Designs subject to change without notice


Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

Upright EBR0100-U00

POWERJACKS

Inverted EBR0100-I00





|--|

Closed	TI	hreade	d End		Top Pl	ate		Clevis	End		Fork E	Ind		Rod E	ind				OUPNI W	ETDIC DAI	LSCREWJ	ACK.	
Height "C"	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	1.2·10 ⁴		Τ	T T T T T T T T T T T T T T T T T T T	ETRIC BA	LOCKEW	T	
EBT0100	2	00	80	2	00	80	24	45	125	30	02	182	2	33	163	COMPRESSIVE LOAD (KG)	Ballscr	ew - 50 n	nm Dia x	10 mm lead			
Stroke (mm)						EB	3T0100 with B		ellows Bo	ots						LOAD			\				
Lead (mm)	10	20	10 &20	10	20	10 & 20	10	20	10 & 20	10	20	10 &20	10	20	10 &20	8000 SSIVE							\Box
1-300	255	285	120	255	285	120	300	330	165	337	367	202 353 383		218	0000 MP.RE								
301-600	265	295	130	265	295	130	130 310 340		175	347	377	212	363	393	228	OS BLE CC							
601-1050			360	195	367	397	232	383	413	248	WS 4000							\vdash					
1051-1500	305	335	170	305 335 170 350 380 215		215	387	417	252	403 433		268	2000										
Model	A B D E G						•					ØA			0			С	OLUMN LEN				
Modet	А	A B D E			E		G		300	_			_		FIXED/GUIDED PINNED/PINNED		500 1 500	000 1 1000	500 2000 1500	2500 3	2500	3000	
EBT0100	65 100 15 15			150				_			_	D FIXED/FREE	-			600 80			1400				
Stroke	1-300 301-600 601-1050 1051					1051-	1500	1							F Note					lead col ing Guid		trength	
EBT0100	20)	30		Ę	50	7	0	ØB								Fr	ee	-	Pinned	Gu	ided	
2 In 3 In 4 † 5 Fc 6 C	verted Screw Jacks - Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 20mm verted Screw Jacks - Recommended bellows boot mounting plate ØB x [E +5mm] thick. verted Screw Jacks - Screw Jack mounting plate & bellows boot mounting plate are customers own supply Control tapes fitted (increase outer diameter by 20mm approximately). or horizontal installations with than 450 mm of stroke, internal boot guides are recommended. ustomers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar. ellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.													n	- F		1	-		-			

Fixed


Pinned


Fixed

200kN Translating

Upright EBT0200-U00

215





Performance	Closed Height

Model		0200 0200			
Capacity		kN	200		
	Diame	ter (mm)	6	3	
Lifting Screw	Lead	Option	1	2	
	Leau	mm	10	20	
	Gear Ratio		8	:1	
Gear Ratio Option 1	Static Effic	iency	0.529	0.571	
	Dynamic E	fficiency	0.631	0.665	
	Gear Ratio		24:1		
Gear Ratio Option 2	Static Effic	iency	0.337	0.364	
	Dynamic E	fficiency	0.440	0.465	
Max. Input	Gear Ratio	Option 1	3.75		
power (kW)	Gear Ratio	Option 2	1.125		
Start up torque	Gear Ratio	Option 1	75.2	139.4	
(Nm)	Gear Ratio	Option 2	39.4	72.9	

Model		0200 0200				
Capacity	kN		20	00		
Lifting Screw (mm)		10	20		
Turn of worm for	Gear Ratio 1	6 Turn	7.5mm	15mm		
travel of lifting screw	Gear Ratio 2	24 Turn	10mm	20mm		
Maximum Thr	Maximum Through Torque (Nm)					
Lifting Screw I	Restraining Torq	ue (Nm)	370	690		
Worm Shaft M (N)	aximum Radial I	_oad	1600			
Maximum Inpu	ut Speed (rpm)		1800			
Gear Case Ma	terial		Ste	eel		
\\/ai=ht(.a)			EMT	42.4		
Weight (kg) - s		EMR	49.58			
Weight (kg) - per extra 25mm stroke						
vveignt (kg) - p	ier extra 25mm s	Stroke	EMR	0.52		
Note: All dimension	on in millimetres un	less otherv	vise stated.			

Designs subject to change without notice


	9	
Upright	Threaded End	Inverted
	Top Plate	
	Clevis End	
	Fork End	
	Rod End	

POWERJACKS

Upright EBR0200-U00

215 66.07 66.00 B , LHS 4 210 300 150 105 150 4 RHS 4 HOLES Ø26 ON 135 PCD KEY 40 x 8 x 7 Ø28 h8 275 Ø63 Ø45 65 10mm Lead = STROKE + 176 20mm Lead = STROKE + 190 UE3821 = Ø85 10mm Lead = 150.5 20mm Lead = 160 UE38211 = Ø95 Ø185 Ø88 PCD 85. 4 x M10 x 1.5 14 DEEP Ø89

Inverted EBR0200-I00





Closed Height & Bellows Boots

Closed	Threaded End Top Plate Clevis End		Threaded End			End	Fork End			Rod End					
Height "C"	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted	Upr	ight	Inverted
EBT0200	20	00	80	20	00	80	245 125 302 18			182	28	33	163		
Stroke (mm)		EBT0200 with Bellows Boots													
Lead (mm)	10	20	10 &20	10	20	10 & 20	10	20	10 & 20	10	20	10 &20	10	20	10 &20
1-300	348	396	140	348	396	140	393	441	185	483	531	275	470	518	262
301-600	358	406	150	358	406	150	403	451	195	493	541	285	480	528	272
601-1050	378	426	170	378	426	170	423	471	215	513	561	305	500	548	292
1051-1500	398	446	190	398	446	190	443	491	235	533	581	325	520	568	312

Model	А	В	D	Е	G
EBT0200	75	105	20	20	165


Stroke	1-300	301-600	601-1050	1051-1500
EBT0200	20	30	50	70





0				COLUMI	N LENG	TH (mm			
GUIDED	5 5	00 10	00 1500	2000	2500	3000	3500 4	4000 45	500 5000
PINNED		500	1000	1500	2000	2500	300	0 350	0 4000
D/FREE	2	0 4	00 600	800	1000	1200	1400	1600	1800
Note			m Dia fer to l					n stre	ength

FIXED/GUIDED




NI	ot.	_	
14	U	C	

- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 20mm Inverted Screw Jacks Recommended bellows boot mounting plate $\emptyset B \times \{E+5mm\}$ thick.
- Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).
- For horizontal installations with than 450 mm of stroke, internal boot guides are recommended. Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar.
- Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.

142 300kN Translating


Inverted EBT0300-I00



Ø115

105.13 104.87

> STROKE + 30




Performance

Model			EBT0300 EBR0300
Capacity		kN	300
	Diame	ter (mm)	80
Lifting Screw	Lead	Option	1
	Leau	mm	20
	Gear Ratio	ı	10 2/3:1
Gear Ratio Option 1	Static Effic	iency	0.492
	Dynamic E	fficiency	0.595
	Gear Ratio		32:1
Gear Ratio Option 2	Static Effic	iency	0.278
	Dynamic E	fficiency	0.371
Max. Input	Gear Ratio	Option 1	6.0
power (kW)	Gear Ratio	Option 2	1.9
Start up torque	Gear Ratio	Option 1	182
(Nm)	Gear Ratio	Option 2	107.3

Model		0300 0300			
Capacity	kN		30	00	
Lifting Screw (mm)		2	0	
Turn of worm for	Gear Ratio 1	6 Turn	11.2	ōmm	
travel of lifting screw	Gear Ratio 2	24 Turn	7.5	mm	
Maximum Thre	ough Torque (Nn	n)	1440		
Lifting Screw F	Restraining Torq	ue (Nm)	1030		
Worm Shaft M (N)	aximum Radial I	_oad	2170		
Maximum Inpu	ut Speed (rpm)		1800		
Gear Case Ma	terial		Ste	eel	
\\\ainht (l.a) a			EMT	92.4	
Weight (kg) - s		EMR	113.78		
Weight (kg) - per extra 25mm stroke					
vveignt (kg) - p	ier extra 25mm s	stroke	EMR	1.13	
Note: All dimension	on in millimetres un	less otherv	vise stated.		

Note: All dimension in millimetres unless otherwise stated.

Designs subject to change without notice




POWERJACKS

Upright EBR0300-U00

295 95.38 95.25 105 , LHS 260 380 190 130 190 99 6 HOLES Ø26 ON 175 P.C.D. 140 KEY 55 x 10 x 8, Ø35 h8 Ø70 85 _Ø80 STROKE + 240 <u>Ø1</u>20 Ø107 PCD 13 30 8.4 4 x M10 x 1.5 x 19 DEEP Ø115

Inverted EBR0300-I00





Closed Height & Bellows Boots

Closed			Top I	Top Plate		Clevis End		Fork End		Rod End	
Height "C"	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	Upright	Inverted	
EBT0300	325	115	325	115	365	155	148	98	150	70	
Stroke (mm)		EBT0300 with Bellows Boots									
1-300	470	135	470	135	510	175	-	-	-	-	
301-600	480	145	480	145	520	185	-	-	-	-	
601-1050	500	165	500	165	540	205	-	-	-	-	
1051-1500	520	185	520	185	560	225	-	-	-	-	

Model	А	В	D	Е	G
EBT0300	110	150	20	20	180


Stroke	1-300	301-600	601-1050	1050-1500
EBT0300	20	30	50	70






- Inverted Screw Jacks Bellows Boot Closed Height assumes screw jack mounted on a structure with thickness = 30mm Inverted Screw Jacks Recommended bellows boot mounting plate \emptyset B x $\{E+5$ mm $\}$ thick.
- Inverted Screw Jacks Screw Jack mounting plate & bellows boot mounting plate are customers own supply † Control tapes fitted (increase outer diameter by 20mm approximately).

- For horizontal installations with than 450 mm of stroke, internal boot guides are recommended. Customers with threaded end screw jacks must provide a fixing for the unattached bellows boot collar.
- Bellows boots for Rotating Screw Jacks, other sizes, stroke and materials please consult Power Jacks.





E-Series Ball Screw Jack


PERFORMANCE ENHANCED VARIANTS TO SOLVE SPECIFIC APPLICATION REQUIREMENTS

Variants



Double Clevis Screw Jack

Double Clevis



Model	EBT0010	EBT	0025	EBT	0050	EBT	0100	EBT	0200	EBT0300	EBT0500
Capacity	10	25	25	50	50	100	100	200	200	300	500
Lead Option	1	1	2	1	2	1	2	1	2	1	1
А		260	287	313	364	427	450	525	573		
В		202	229	245	296	299	322	386	434		
С	Request	58	58	68	68	128	128	139	139	equest	equest
D	Seq	23	23	30	30	33	33	40	40	Req	Req
Е	on F	48.3	48.3	60.3	60.3	73	73	102	102	l lo	on F
F		30	30	35	35	40	40	50	50	ole	ole
G	Available	16	16	20	20	22	22	30	30	ailable	Available
Max Raise at Max Rated Load in Compression	Ava	280	200	600	560	658	588	769	621	Ave	Avš

Note

- 1. For other performance and dimension information refer to translating screw models.
- 2. All dimensions in millimetres unless otherwise stated.

Reduced Backlash Ball Screw Jacks



Metric Ball Screw Jacks can be provided with preloaded ball nuts to give reduced axial backlash as a high efficiency alternative to the metric machine screw anti-backlash option. Preloading on the ball nut is obtained by the "Interference Ball" method. By fitting Interference balls in the ball nut to obtain a diametrical interference fit and using the original track form, a four-point contact results.

The anti-rotation device is available for translating ball screw models only. It is used only when the load to be moved (actuated) may

The anti-rotation device consists of a square steel tube which guides the movement of a square aluminium bronze guide block fitted to the end of the ball screw. The guide block also acts as a stop nut.

Model	EBT0010	EBT0025	EBT0050	EBT0100	EBT0200	EBT0300	EBT0500
Capacity (kN)	10	25	50	100	200	300	500
Α	AOR	50	70	AOR	AOR	AOR	AOR
В	AOR	50	60	AOR	AOR	AOR	AOR
С	AOR	90	115	AOR	AOR	AOR	AOR
D	AOR	16	20	AOR	AOR	AOR	AOR


Note

1. AOR = Application On Request, consult Power Jacks Ltd.

rotate, i.e. the screw is unguided and does not prevent rotation.

2. All dimensions in millimetres unless otherwise stated.






E-Series Roller Screw Jack

HIGH PRECISION
PLANETARY ROLLER SCREW
INTEGRATED WITH OUR
FLEXIBLE E-SERIES DESIGN
FOR A SCREW JACK THAT
MEETS THE NEEDS OF
HIGH DUTY & HIGH LOAD
APPLICATIONS.





Features

- High Performance Power Jack
- Metric Single Face Roller Screw Jacks
- Capacities up to 1000kN as standard
- High precision planetary roller screw
- Translating and Rotating Screw in Upright and Inverted types
- Precision Worm Gear Set
- 2 Gear ratios and 2 screw leads as standard
- Anti-Rotation Option
- 6 mounting options including trunnion and double clevis
- Special custom designs available




An extensive range of axially translating and rotating screw jacks fitted with the patented Spiracon roller screw and designed specifically to customers' application requirements. The Spiracon roller screw is an extremely high performance screw mechanism exhibiting almost no axial backlash and is designed to meet the following demands:


- · High precision and repeatable positioning
- High speed
- High dynamic load capacity
- High duty
- High efficiency
- Long life
- Minimum maintenance requirements

The range covers lifting capacities up to 1000kN, with many design features available to meet the customers' particular requirements. The units' gearbox is based on the standard range of Power Jacks screw jacks, although other gearbox types can be designed for specific applications. The gearboxes are either grease or oil lubricated depending on the application. The roller screw is based around the standard Spiracon planetary roller screw range, with alternative nut housings available to meet the requirements of specific applications.

Principle of Operation

The Spiracon™ system consists of a multi-start screw with an involute thread form and a number of planetary rollers with annular grooves, which engage with the screw. These rollers also engage with a grooved load bearing element, which transmits the load through roller thrust bearings, to the nut housing. The rolling action results in a high efficiency mechanism, while the line contact and hardened and ground construction achieves a high dynamic load carrying capacity, together with almost no axial backlash or wear.





Typical Applications

Roller Screw Jacks are generally used when the application is moving a high load with a high duty cycle. Size for size roller screws offer higher load carrying capabilities than ball screws so for high load applications allow for more compact working envelopes. The high efficiency of the roller screw & nut significantly increase the efficiency of a screw jack in comparison to a Machine Screw Jack. Due to their high efficiency they nearly always require a brake to hold position. They are used in a wide variety of applications including Automotive, Steel, Defence and Nuclear.

Standard Designs

The standard E-Series roller screw jack is available in translating and rotating screw designs in capacity sizes up to 1000kN.

The design is optimised for high load and high performance in a compact form. There is a large selection of options and accessories (section-7) available so you can configure a standard design that is just right for your application.

These options include Low-Backlash and Anti-Rotation designs.

Special Designs

We can fully customise our screw jacks so that your application can be the best.

Customisation can be anything from a small modification such as an extra bolt hole on an end fitting to a completely new design of screw jack based on our class leading technology.

For more details please see the Special Screw Jack information in Section-8 or contact us today with your requirements. Our team are looking forward to working with you.

Selecting the Right Screw Jack

Consider all application constraints then choose a product that looks suitable for the intended application. Calculate the power and torque requirements. This is a 5 step process:

- Screw Jack Input Speed (RPM)
- Operating Input Power (kW)
- Operating Input Torque (Nm)
- Screw Jack Start-up Torque (Nm)
- Mechanical Power and Torque Check

Systems

The screw jacks can be connected together in systems so that multiple units can be operated and controlled together. These jacking system arrangements or configurations can be built in many formats with the use of bevel gearboxes, motors, reduction gearbox, drive shafts, couplings, plummer blocks and motion control devices.

The use of bevel gearboxes allows the distribution of drive throughout a jacking system. The gearboxes come in 2, 3 and 4 way drive types. See the Bevel Gearboxes Section-10 for more details.

Bevel gearboxes and other system components can also be supplied in stainless steel or other corrosion resistant designs.

Two of the most popular system configurations are the 'H' and 'U' configured jacking systems. Remember that multiple screw jacks can be linked together mechanically or electrically. The latter is useful if there is no space for linking drive shafts.

If multiple roller screw jacks are connected in a mechanically linked system then the complete system in some circumstances may be considered self-locking depending on the gear ratios and efficiencies of units in the system. In general, Power Jacks recommend a brake is used on **ALL** Roller Screw Jack systems. If you would like this checked, consult Power Jacks. Alternatively, to be sure, include a brake on the system either as a stand alone device or as a brake motor.



E-Series Screw Jack

ACCESSORIES FOR ALL MACHINE SCREW, STAINLESS STEEL, BALL SCREW AND ROLLER SCREW JACKS



















End Fittings

Top Plate









Clevis End









Fork End









Rod End







	o	(1.51)	-	40	0.5		400	000	000	500	4000	4500	0000
	Capacit		5	10	25	50	100	200	300	500	1000	1500	2000
		ØA	65	80	100	120	150	170	240	280	380	400	470
		ØB	25	30	40	50	65	75	110	150	200	215	265
		С	21	25	31.5	36.5	42	58	67	92	127	162	172
		D	8	10	12	16	20	25	30	35	75	80	100
ate		x QTY	9 x 4	11 x 4	13.5 x 4	18 x 4	22 x 4	26 x 4	33 x 4	33 x 4	51 x 4	51 x 6	52 x 8
Top Plate	ØF	(PCD)	45	55	70	85	110	120	170	215	290	310	370
잍		L	M10 x 1.5	M12 x 1.75	M20 x 2.5	M24 x 3	M36 x 4	M48 x 5	M72 x 4	M100 x 4	M125 x 4	M145 x 6	M180 x 8
	M#1	Upright	95	125	145	185	200	265	325	390	560	620	690
		Inverted	40	45	55	65	80	95	115	150	260	230	280
	N#2	Upright	-	150	175	218	252	338	445	-	-	-	-
		Inverted	-	45	55	65	80	95	115	-	-	-	-
	0	eta e (text)	Г	10	٥٢	Ε0	100	200	200	F00	1000	1500	2000
		city (kN) ØA	5 10	10 12	25 16	50 20	100 22	200 30	300 45	500 60	1000 90	1500 105	2000 125
		ØB	25	30	40	50	65	75	110	150	200	230	270
		С	56	63	79.5	91.5	120	143	167	217	297	404	490
		D	30	36	46		66	80	120	150	210	215	270
e l		E	15	18	23	30	33	40	60	75	105	105	130
Clevis Plate			15	20	30	35	40	50			140	150	175
. SVS		L	M10 x 1.5	M12 x 1.75	M20 x 2.5		M36 x 4	M48 x 5	80 M72 v /	110 M100 v /		M145 x 6	M180 x 8
Cle		Upright	115	145	170	M24 x 3	245	310	M72 x 4 365	M100 x 4	M125 x 4 625	760	880 880
	M#1	Inverted	60	65	80	90	125	140	155	200	325	370	470
		_	-	170	200		297	383	485	-	- 320	-	-
	N#2	Upright				243							
		Inverted	-	65	80	90	125	140	155	-	-	-	-
	Cana	alter (LNI)	г	10	25	ГО	400	222	000	F00	1000	1500	0000
						าเม	100	200	.31111	500	1111111		/111111
		city (kN) ØA	5 10			50 25	100 35	200 50	300	500	1000	1500	2000
		ØA	10	12	20	25	35	50	300	500	1000	1500	2000
		ØA B	10 10	12 12	20 20	25 25	35 35	50 50	300	500	1000	1500	2000
		ØA B C	10 10 20	12 12 24	20 20 40	25 25 50	35 35 70	50 50 96					
		ØA B C D	10 10	12 12	20 20	25 25	35 35	50 50					
q		ØA B C D	10 10 20 40 20	12 12 24 48 24	20 20 40 80 40	25 25 50 100 50	35 35 70 144 72	50 50 96 192 96					
End		ØA B C D E	10 10 20 40 20 15	12 12 24 48 24 18	20 20 40 80 40 30	25 25 50 100 50 36	35 35 70 144 72 54	50 50 96 192 96 73					
ork End		ØA B C D E G	10 10 20 40 20 15	12 12 24 48 24 18 62	20 20 40 80 40 30 105	25 25 50 100 50 36 132	35 35 70 144 72 54 188	50 50 96 192 96 73 265					
Fork End		ØA B C D E F G	10 10 20 40 20 15 52	12 12 24 48 24 18 62 20	20 20 40 80 40 30 105 34	25 25 50 100 50 36 132 42	35 35 70 144 72 54 188	50 50 96 192 96 73 265					
Fork End		ØA B C D E F G ØJ L	10 10 20 40 20 15 52 18 M10 x 1.5	12 12 24 48 24 18 62 20 M12 x 1.75	20 20 40 80 40 30 105 34 M20 x 2.5	25 25 50 100 50 36 132 42 M24 x 3	35 35 70 144 72 54 188 60 M36 x 4	50 50 96 192 96 73 265 82 M48 x 5	Available on Request				
Fork End		ØA B C D E F G ØJ L Upright	10 10 20 40 20 15 52 18 M10 x 1.5	12 24 48 24 18 62 20 M12 x 1.75	20 20 40 80 40 30 105 34 M20 x 2.5	25 25 50 100 50 36 132 42 M24 x 3 248	35 70 144 72 54 188 60 M36 x 4 302	50 50 96 192 96 73 265 82 M48 x 5 400					
Fork End		ØA B C D E F G ØJ L Upright Inverted	10 10 20 40 20 15 52 18 M10 x 1.5 114	12 24 48 24 18 62 20 M12 x 1.75 148	20 20 40 80 40 30 105 34 M20 x 2.5 194	25 25 50 100 50 36 132 42 M24 x 3 248 128	35 35 70 144 72 54 188 60 M36 x 4 302 182	50 50 96 192 96 73 265 82 M48 x 5 400					
Fork End		ØA B C D E F G ØJ L Upright Inverted Upright	10 10 20 40 20 15 52 18 M10 x 1.5 114 59	12 24 48 24 18 62 20 M12 x 1.75 148 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224	25 25 50 100 50 36 132 42 M24 x 3 248 128 281	35 35 70 144 72 54 188 60 M36 x 4 302 182 354	50 50 96 192 96 73 265 82 M48 x 5 400 230 473					
Fork End	M#1	ØA B C D E F G ØJ L Upright Inverted	10 10 20 40 20 15 52 18 M10 x 1.5 114	12 24 48 24 18 62 20 M12 x 1.75 148	20 20 40 80 40 30 105 34 M20 x 2.5 194	25 25 50 100 50 36 132 42 M24 x 3 248 128	35 35 70 144 72 54 188 60 M36 x 4 302 182	50 50 96 192 96 73 265 82 M48 x 5 400					
Fork End	M#1	ØA B C D E F G ØJ L Upright Inverted Upright	10 10 20 40 20 15 52 18 M10 x 1.5 114 59	12 24 48 24 18 62 20 M12 x 1.75 148 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224	25 25 50 100 50 36 132 42 M24 x 3 248 128 281	35 35 70 144 72 54 188 60 M36 x 4 302 182 354	50 50 96 192 96 73 265 82 M48 x 5 400 230 473					
Fork End	M#1	ØA B C D E F G ØJ L Upright Inverted Upright Inverted	10 10 20 40 20 15 52 18 M10 x 1.5 114 59	12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230	Available on Request				
Fork End	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 -	12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230	Available on Request				
Fork End	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C	10 10 20 40 20 15 52 18 M10 x 1.5 114 59	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230	Available on Request				
Fork End	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112	Available on Request				
Fork End	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted Oright Inverted City (kN) A ØB C ØD F	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 -	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53 40	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64 48	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82 60	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C ØD F	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53 40 35	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64 48 42	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82 60 58	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75	Available on Request				
Rod End Fork End	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted Upright Inverted The company of the compa	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19 9 7	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53 40 35 16 13	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64 48 42 20 17	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 354 182 60 58 25 21	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted City (kN) A ØB C ØD F	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 19 9 7 17	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8 19	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 227 53 40 35 16 13 32	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64 48 42 20 17 36	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 354 182 60 58 25 21 50	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35 30 65	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted Upright Inverted City (kN) A ØB C ØD F ØG H J K L	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19 9 7	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 227 53 40 35 16 13 32 M20 x 1.5	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 50 94 25 32 64 48 42 20 17	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 354 182 60 58 25 21	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted OB C ØB C ØB C ØB C ØB C UD F ØB H J K L Upright	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19 9 7 17 M10 x 1.5 117	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8 19 M12 x 1.75 150	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 225 77 20 27 53 40 35 16 13 32 M20 x 1.5 190	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 281 128 50 94 25 32 64 48 42 20 17 36 M24 x 2 242	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82 60 58 25 21 50 M36 x 3 283	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35 30 65 M45 x 3	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright City (kN) A ØB C ØD F ØG H J K L Upright Inverted	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19 9 7 17 M10 x 1.5	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8 19 M12 x 1.75 150 70	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 25 77 20 27 53 40 35 16 13 32 M20 x 1.5 190 100	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 281 128 50 94 25 32 64 48 42 20 17 36 M24 x 2 242 122	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82 60 58 25 21 50 M36 x 3 283 163	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35 30 65 M45 x 3 367 197	Available on Request				
	M#1 N#2 Capa	ØA B C D E F G ØJ L Upright Inverted Upright Inverted OB C ØB C ØB C ØB C ØB C UD F ØB H J K L Upright	10 10 20 40 20 15 52 18 M10 x 1.5 114 59 5 43 10 15 29 - 19 9 7 17 M10 x 1.5 117	12 12 24 48 24 18 62 20 M12 x 1.75 148 68 173 68 10 50 12 18 34 23 22 10 8 19 M12 x 1.75 150	20 20 40 80 40 30 105 34 M20 x 2.5 194 104 224 104 225 77 20 27 53 40 35 16 13 32 M20 x 1.5 190	25 25 50 100 50 36 132 42 M24 x 3 248 128 281 128 281 128 50 94 25 32 64 48 42 20 17 36 M24 x 2 242	35 35 70 144 72 54 188 60 M36 x 4 302 182 354 182 100 125 35 42 82 60 58 25 21 50 M36 x 3 283	50 50 96 192 96 73 265 82 M48 x 5 400 230 473 230 200 160 50 60 112 68 75 35 30 65 M45 x 3 367	Available on Request				

Note

- 1. M = For Machine Screw Jacks
- 2. N = For Ball Screw Jacks, Standard Lead only.

Machine Screw Jack Bellows Boots


Features

- Protects the screw from dust and dirt
- Guards against moisture and corrosive contaminants
- Helps maintain the proper lubrication
- Boots are made of P.V.C. coated nylon with sewn construction. Other materials are available
 for applications involving high temperatures, highly corrosive atmospheres and other special
 conditions.



Boot Dimensions


Model	А	В	С	D	Е
EMT0005	25	60	100	13	13
EMT0010	30	70	110	15	15
EMT0025	40	90	120	15	23
EMT0050	50	115	140	15	31
EMT0100	65	136	150	15	31
EMT0200	75	165	165	20	20
EMT0300	110	220	191	20	20
EMT0500	150	285	210	20	45
EMT1000	200	220	244	20	20
EMT1500	215	410	480	25	25
EMT2000	265	396	470	25	25



	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
	Stroke 0 → 150	10	8	8	8	-	-	-	-	-	-	-
	Stroke 0 → 300	20	20	20	20	20	20	20	20	20	-	-
	Stroke $0 \rightarrow 500$	-	-	-	-	-	-	-	-	-	20	25
	Stroke 301 → 600	30	35	30	30	30	30	30	30	30	-	-
F	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	45	40
	Stroke 601 → 1050	-	-	50	50	50	50	50	50	50	-	-
	Stroke 1051 → 1500	-	-	70	70	70	70	70	70	70	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	80	75†
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	160	145†

 $\mathsf{F} = \mathsf{Bellows}$ boot minimum closed thickness, - = Not applicable

Closed Heights



Notes for all metric machine screw jacks with bellows boots

- 1. Supplied complete with a set of corrosion-resistant 'jubilee' clips (2) suitable for fitting over collar diameters.
- 2. † Control tapes are fitted (approximately 20 mm increase to outer diameter).
- 3. For horizontal installation exceeding 450 mm of travel, internal boot guides are recommended.
- 4. Customers with threaded end screw jacks must provide a fixing for the unattached collar (★).
- 5. Bellows boots for Rotating Screw Jacks consult Power Jacks Ltd.
- 6. For other sizes, strokes and materials please consult Power Jacks Ltd.
- 7. All dimensions in millimetres unless otherwise stated.
- 8. Dimensions subject to change without notice.
- Screw Jack mounting plate and bellows boot mounting plate are usually all part of the customers superstructure (★★).
 For other options consult Power Jacks.

Closed Height for all Upright Machine Screw Jacks and Anti-Rotation (Keyed) Types

	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
	Stroke 0 → 150	95	125	145	185	-	-	-	-	-	-	-
	Stroke 0 → 300	120	130	145	185	200	265	325	390	560	-	-
	Stroke 0 → 500	-	-	-	-	-	-	-	-	-	620	690
	Stroke 301 → 600	120	140	170	210	200	265	325	415	560	-	-
G	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	630	690
	Stroke 601 → 1050	-	-	195	210	225	290	350	440	585	-	-
	Stroke 1051 → 1500	-	-	195	235	250	315	375	465	610	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	665	695†
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	745	795†
Н	Extra Closed Height for Clevis	20	20	25	25	45	45	40	50	65	140	190
I	Extra Closed Height for Fork	19	23	49	63	102	135	Request	Request	Request	Request	Request
J	Extra Closed Height for Rod End	37	40	60	72	98	122	Request	Request	Request	Request	Request


Closed Height for all Upright Machine Screw Jacks with Anti-Backlash

	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
	Stroke 0 → 150	95	125	145	185	-	-	-	-	-	-	-
	Stroke 0 → 300	120	130	145	185	200	265	340	415	585	-	-
	Stroke 0 → 500	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 301 → 600	120	140	170	210	200	265	340	440	585	-	-
G	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 601 → 1050	-	-	195	210	225	290	340	465	610	-	-
	Stroke 1051 → 1500	-	-	195	235	250	315	365	490	635	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	Request	Request
Н	Extra Closed Height for Clevis	20	20	25	25	45	45	40	50	65	Request	Request
I	Extra Closed Height for Fork	19	23	49	63	102	135	Request	Request	Request	Request	Request
J	Extra Closed Height for Rod End	37	40	60	72	98	122	Request	Request	Request	Request	Request

Closed Height for all Upright Machine Screw Jacks with Anti-Backlash & Anti-Rotation (Keyed)

	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
	Stroke 0 → 150	95	125	145	185	-	-	-	-	-	-	-
	Stroke 0 → 300	120	130	145	185	200	265	340	415	585	-	-
	Stroke 0 → 500	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 301 → 600	120	140	170	195	200	265	340	440	585	-	-
G	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 601 → 1050	-	-	195	195	225	290	365	465	610	-	-
	Stroke 1051 → 1500	-	-	195	220	250	315	390	490	635	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	Request	Request
Н	Extra Closed Height for Clevis	20	20	25	25	45	45	40	50	65	Request	Request
I	Extra Closed Height for Fork	19	23	49	63	102	135	Request	Request	Request	Request	Request
J	Extra Closed Height for Rod End	37	40	60	72	98	122	Request	Request	Request	Request	Request

Closed Heights



Closed Height for all Inverted Machine Screw Jacks Standard or Anti-Backlash or Anti-Rotation (Keyed)

	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
М	Mounting Plate	10	10	15	15	20	20	30	30	50	60	70
	Stroke 0 → 150	70	75	80	110	-	-	-	-	-	-	-
	Stroke 0 → 300	90	95	80	120	105	120	140	175	260	-	-
	Stroke 301 → 500	-	-	-	-	-	-	-	-	-	230	280
	Stroke 301 → 500	90	95	105	130	130	145	165	200	260	-	-
K	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	225	280
	Stroke 601 → 1050	-	-	130	150	130	145	165	225	285	-	-
	Stroke 1051 → 1500	-	-	130	170	155	170	190	250	310	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	290	285†
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	370	350†
L	Extra Closed Height for Clevis	20	20	25	25	45	45	40	50	65	140	190
N	Extra Closed Height for Fork	19	23	49	63	102	135	Request	Request	Request	Request	Request
Р	Extra Closed Height for Rod End	37	40	60	72	98	122	Request	Request	Request	Request	Request

Closed Height for all Inverted Machine Screw Jacks with Anti-Backlash and Anti-Rotation (Keyed)

	Model	EMT0005	EMT0010	EMT0025	EMT0050	EMT0100	EMT0200	EMT0300	EMT0500	EMT1000	EMT1500	EMT2000
М	Mounting Plate	10	10	15	15	20	20	30	30	50	60	70
	Stroke $0 \rightarrow 150$	70	75	80	110	-	-	-	-	-	-	-
	Stroke 0 → 300	90	95	80	120	105	135	140	238	405	-	-
	Stroke 301 → 500	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke $301 \rightarrow 500$	90	95	105	130	130	160	165	263	405	-	-
K	Stroke 501 → 1000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 601 → 1050	-	-	130	150	130	160	165	288	430	-	-
	Stroke 1051 → 1500	-	-	130	170	155	185	190	313	455	-	-
	Stroke 1001 → 2000	-	-	-	-	-	-	-	-	-	Request	Request
	Stroke 2001 → 4000	-	-	-	-	-	-	-	-	-	Request	Request
L	Extra Closed Height for Clevis	20	20	25	25	45	45	40	50	65	Request	Request
N	Extra Closed Height for Fork	19	23	49	63	102	135	Request	Request	Request	Request	Request
Р	Extra Closed Height for Rod End	37	40	60	72	98	122	Request	Request	Request	Request	Request

POWERJACKS


Features

- · Protects the screw from dust and dirt
- Guards against moisture and corrosive contaminants
- Helps maintain the proper lubrication
- Boots are made of P.V.C. coated nylon with sewn construction. Other materials are available for applications involving high temperatures, highly corrosive atmospheres and other special conditions.



Boot Dimensions

Model	А	В	С	D	Е
EBT0010	30	75	114	12	12
EBT0025	40	66	120	15	15
EBT0050	50	85	140	15	15
EBT0100	65	100	150	15	15
EBT0200	75	105	165	20	20




Model	Α	В	С	D	Е
EBT0300	110	150	180	20	20
EBT0500		Av	ailable on Reque	est	

	Model	EBT0010	EBT0025	EBT0050	EBT0100	EBT0200	EBT0300
	Stroke 0 → 300	16	20	20	20	20	20
	Stroke 301 → 600	32	30	30	30	30	30
_	Stroke 601 → 900	-	-	45	-	-	-
-	Stroke 601 → 1050	56	50	-	50	50	50
	Stroke 901 → 1050	-	-	50	-	-	-
	Stroke 1051 → 1500	80	70	70	70	70	70

Note

- 1. F = Bellows boot minimum closed thickness
- 2. -= Not applicable consult Power Jacks Ltd
- 3. † = Control tapes fitted (approximately 20 mm increase to outer diameter).
- 4. Supplied complete with a set of corrosion-resistant 'jubilee' clips (2) suitable for fitting over collar diameters.
- 5. For horizontal installation exceeding 450 mm of travel, internal boot guides are recommended.
- 6. Customers with threaded end screw jacks must provide a fixing for the unattached collar (★).
- 7. Bellows boots for rotating screw jacks consult Power Jacks Ltd.
- 8. For other sizes, strokes and materials please contact Power Jacks Ltd.
- 9. All dimensions in millimetres unless otherwise stated.
- 10. Dimensions subject to change without notice.
- 11. Screw Jack mounting plate and bellows boot mounting plate are usually all part of the customers superstructure (★★). For other options consult Power Jacks.


Closed Heights



Closed Height for all Upright Metric Ball Screw Jacks

	Model	EBT0010	EBT	0025	EBT	0050	EBT	0100	EBT	0200	EBT0300
	Lead Option	1	1	2	1	2	1	2	1	1	1
	Stroke 0 → 300	166	180	200	230	270	255	285	348	396	470
	Stroke 301 → 600	182	190	210	240	280	265	295	358	406	480
G	Stroke 601 → 900	-	-	-	255	295	-	-	-	-	-
6	Stroke 601 → 1050	206	210	230	-	-	285	315	378	426	500
	Stroke 901 → 1050	-	-	-	260	300	-	-	-	-	-
	Stroke 1051 → 1500	230	230	250	280	320	305	335	378	446	520
Н	Extra Closed Height for Clevis	20	25	25	25	25	45	45	45	45	40
1	Extra Closed Height for Fork	23	49	49	63	63	82	82	135	135	Request
J	Extra Closed Height for Rod End	43	60	60	72	72	98	98	122	122	Request

Closed Heights




Closed Height for all Inverted Metric Ball Screw Jacks


	Model	EBT0010	EBT	0025	EBT	0050	EBT	0100	EBT	0200	EBT0300
	Lead Option	1	1	2	1	2	1	2	1	2	1
М	Mounting Plate	10	15	15	15	15	20	20	20	20	30
	Stroke 0 → 300	61	100	100	105	105	120	120	140	140	135
	Stroke 301 → 600	77	110	110	115	115	130	130	150	150	145
G	Stroke 601 → 900	-	-	-	130	130	-	-	-	-	-
6	Stroke 601 → 1050	101	130	130	-	-	150	150	170	170	165
	Stroke 901 → 1050	-	-	-	135	135	-	-	-	-	-
	Stroke 1051 → 1500				155	155	170	170	190	190	185
К	Extra Closed Height for Clevis	20	25	25	25	25	45	45	45	45	40
N	Extra Closed Height for Fork	23	49	49	63	63	82	82	135	135	Request
0	Extra Closed Height for Rod End	43	60	60	72	72	98	98	122	122	Request

Stop Nuts & Hand Wheels

Stop Nuts







Machine Screw Jack

Model	Extra	(mm)
iviodei	Upright	Inverted
EMT0005	16	11
EMT0010	15	50
EMT0025	20	20
EMT0050	40	40
EMT0100	42	37
EMT0200	41	31
EMT0300	55	35
EMT0500	47	47
EMT1000	72	92
EMT1500	160	210
EMT2000	9	84


Ball Screw Jack

Model	Extra	(mm)
Model	Upright	Inverted
EBT0010	On Re	equest
EBT0025	30	30
EBT0050	57	57
EBT0100	60	60
EBT0200	56	56
EBT0300	On Re	equest
EBT0500	On Re	equest

Note:

These are full power stop nuts. They should only be used as an emergency stop safety feature.

Hand Wheels




Model	Α	В	С	D	Е	H7 Bore
HW 005	40	14	36	98	24	Ø10
HW 010	50	22	38	157	32	Ø14
HW 025	56	24	43	198	40	Ø16
HW 050	56	24	43	198	40	Ø19
HW 100	66	30	44	247	49	Ø25
HW 200	78	32	56	288	58	Ø28
HW 300	108	40	77	375	58	Ø35
HW 500	108	40	77	375	58	Ø40

Notes:

- 1. Material: Polished aluminium casting and rotating handle
- 2. Bored and keyed to BS4235 Part 1
- 3. All dimensions in millimetres unless otherwise stated
- 4. Other types of hand wheels are available on request.

Rotation Indicators



Model	ØA	ØВ	С	D	Е
RI 010	14	25	20	14	13
RI 025	16	29	26	16	14
RI 050	19	32	27	16	14
RI 100	25	50	40	21	19
RI 200	28	50	45	25	22

Notes:

- 1. Rotation Indicators are suitable for fitment to screw jack worm shafts with the corresponding bore size.
- 2. Material: Composite Plastic
- 3. Bored (H7) and keyed to BS4235 Part 1
- 4. All dimensions in millimetres unless otherwise stated
- 5. Other types of rotation indicators are available on request.

POWERJACKS


Base mounted trunnions are an ideal bolt-on accessory for a screw jack to add a pivot point to the gearbox of the screw jack. These base mounted trunnions can be used for both translating and rotating screw jacks with any lifting screw type.

Available in both male or female designs with the option to add standard trunnion feet. Most designs offer trunnions in 2 mounting positions.


If you need trunnions fitted at another position on a screw jack then please contact us as we can provide customised trunnion mounts to suit your exact applications needs




5kN and 10kN - Type-1 Housing - Trunnion Mounts



Capacity	Α	В	B1	С	D	ØE			Н		l1		K	0	Р	Q	ØR (h6)			U
5kN	70	42	21	35	22	11	12	65	20	20	10	159	79.5	74	68	160	15	20	15	2
10kN	70	42	21	35	22	11	12	65	20	25	12.5	181	90.5	103	84	209	20	24	20	2.5



25kN to 500kN Trunnion Mounts




Capacity	А	В	B1	С	D	ØE			Н		11		K	L
10kN	70	42	21	34	21	11	12	65	20	30	15	134	67	177
25kN	100	70	35	40	26	13.5	14	85	30	36	18	171	85.5	226
50kN	140	100	50	55	35.5	18	20	120	42.5	50	25	233	116.5	288
100kN	170	120	60	70	43.5	22	25	130	47.5	60	30	292	146	327
200kN	220	150	75	90	61	33	25	170	59	85	42.5	344	172	409
300kN	280	190	95	120	80	39	35	180	60	100	45	434	217	539
500kN	360	250	125	155	100	51	40	200	70	120	55	514	257	749

Capacity	М	N	0	ØР	ØQ	ØR (f7)	ØS	т	- 11	Ø۷	ØW	Υ	٧	7
' '	141		Ü			1 1 1			Ü	ρv	911	^		_
10kN	78.5	98.5	101	159	214	20	30	20	2.5	20	30	1.5	16.5	19.5
25kN	95.5	130.5	121.5	208	248	25	35	20	2.5	25	35	1.5	16.5	26
50kN	116.5	171.5	163	270	332	35	47	20	2.5	35	47	2	26	39
100kN	126	201	177	312	361	45	58	35	5	45	74	2	32	40
200kN	172	237	238	361	500	60	75	45	5	60	78	2	42	45
300kN	227	312	280	473	578	70	85	70	6	70	90	3	53	58
500kN	332	417	330	643	681	80	95	70	6	80	110	2	62	62

Notes:

- 1. 10kN is for Type-2 Housing screw jacks.
- 2. Trunnion feet for 300kN and 500kN models are available on request.

1000kN to 2000kN Trunnion Mounts



Note: Trunnion feet for 1000kN, 1500kN and 2000kN models are available on request.


Capacity	А	В	B1	С	D	ØE	F	G	Н	I	I1	J	K	L
1000kN	550	450	225	210	60	95	45	50	240	92.5	212.5	120	772	386
1500kN	550	450	225	210	60	95	45	65	260	115	235	120	772	386
2000kN	640	530	265	235	65	110	52	70	265	135	275	140	976	488

Capacity	М	N	0	Р	Q	ØR (f7)		T	U	Ø۷	W	Х	Y	Z
1000kN	N/A	N/A	525	725	1074	110	125	115	14	110	185	6	115	145
1500kN	N/A	N/A	560	758	1162	140	155	120	14	140	230	6	120	145
2000kN	N/A	N/A	626	1004	1295	160	180	145	11	160	270	3	145	148

- Standard adaptors for 10 kN 200 kN metric machine screw and ball screw jacks
- Designed for standard IEC frame sizes
- Allows direct motor coupling on either side of the screw jack input shaft
- Complete with drive coupling and mounting hardware

Note

• When direct coupling a motor to a screw jack, it is necessary to match motor power to screw jack load so the motor does not exceed the maximum power for the screw jack gear set.



Motor Adaptors		Capacity (kN)															
Motor	Adaptors		2				5				10	00			21	00	
Frame Size	Motor Mounting	А	В	ØC	ØD	А	В	ØC	ØD	А	В	ØC	ØD	А	В	ØC	ØD
71	B14 C105	142.5	10	71	105	-	-	-	-	-	-	-	-	-	-	-	-
80	B14 C120	146.5	12	81	120	171	12	86	120	-	-	-	-	-	-	-	-
90	B14 C140	157.5	12	81	140	183	12	88	140	208	12	98	140	218	12	125	140
100	B14 C160	168	12	81	160	193	12	88	160	218	12	98	160	228	12	125	160
112	B14 C190	168	12	81	160	193	12	88	160	218	12	98	160	228	12	125	160
132	B14 C200	-	-	-	-	218	14	95	200	240	14	98	200	250	14	125	200


Notes:

- 1. Motor Adaptors for IEC Frames with B5 Flange mounts available on request.
- 2. Motor Adaptors for screw jacks of capacities 300kN and above are available on request.
- 3. Adaptors for geared motors are available on request for all types of geared motor or gear head.
- 4. Motor Adaptors for Servo Motors available on request.
- 5. Motor Adaptors for NEMA Frame motors are available on request.
- 6. All dimensions in millimetres unless otherwise stated.
- 7. Dimensions subject to change without notice.

Limit Switches on Cover Pipe

End of Travel Proximity Sensors Sensor Kit

- Inductive Proximity Sensors as standard, others available on request.
- No contact so no wearing parts.
- 2 wire sensor for either Normally Closed (NC) or Normally Open (NO) switching.
- Sensor has rugged one-piece metal housing.
- Optical setting aid with 2 LED colour settings:- Red LED indicates just in sensing range. Yellow LED only indicates within 80% safe sensing range.
- M12 plug in connection for fast change-ability.
- M12 sockets available straight or angled with 5-m cable (other cable lengths available on request).
- Full 360° visibility for switching with 4 yellow LED's at 90° offset.
- Sensor kit includes sensor, mounting ring, target ring and modification to screw jacks cover pipe.



		Upr	ight & Inve	rted Machi	ne Screw .	Jacks		
Capacity Rating (kN)	Switch Dia (mm)	A1 (mm)	A2 (mm)	B (mm)	C (mm)	D (Ømm)	F (mm)	Switch Adjustment (mm)
5	8	40	40	Stroke + 12	38	33.4	10	±5
10	8	40	40	Stroke + 20	40	33.4	10	±5
25	12	35	60	Stroke + 15	60	48	15	±5
50	12	40	70	Stroke + 25	65	60	15	±5
100	12	55	85	Stroke + 25	77	73	20	±10
200	12	65	80	Stroke +25	77	89	20	±10
300	18	65	80	Stroke +40	96	141	30	±10
500	18	95	95	Stroke +40	108	168	30	±15
1000	18	155	105	Stroke +50	135	245	50	±15
1500				On	Request			
2000				On	Request			



Note

1. All dimensions in mm unless otherwise stated.


End of Travel Electro-Mechanical Switches

The screw jacks can be fitted with electro-mechanical limit switches in a similar design. For dimensions please consult Power Jacks Ltd.





169





- Use when cover pipe mounted limit switches are not possible e.g. rotating screw jacks.
- Switches fully enclosed.
- 1 cable for all limit switches



Each Limit Switch is Fully Adjustable over full stroke of screw jack.

Rotary limit switches can be used as end of travel limit switches, with the option of intermediate switches as well. These units are mounted onto a screw jacks free worm shaft. **Up to 8 limit switches** can be accommodated in one enclosure (IP66). Operating temperature -40°C to +80°C. More RLS-51 rotary limit switch details in System Components section.

	Screw Jack Capacity (kN)										
		10kN									
Adapter Mounting	Std. Part	А	В	øс							
B5	×	-	-	-							
B14	✓	106.5	10	86							

	Screw Jack Capacity (kN)													
		2	5		50									
Adaptor Mounting	Std. Part	А	В	øс	Std. Part	А	В	øс						
B5	×	-	-	-	×	-	-	-						
B14	✓	117	10	70	✓	133	10	89						

	Screw Jack Capacity (kN)													
		10	00		200									
Adaptor Mounting	Std. Part	А	В	øс	Std. Part	А	В	ØС						
B5	✓	150	13	98	✓	174	13	125						
B14	×	-	-	-	×	-	-	-						

		Usable revs.		1 rev. of the	Change - over		Min drive shaft L1 (mr		mm)		
Gear Size	Usable revs. selected	theoretical with 15° cam	Gear Ratio	drive shaft - corresp. to an	contact reset rev. at driving	Max drive speed	speed (only for change - over		Limit S	witches	
		discs		ang. motion of cam disc =°	shaft	(RPM)	contact)	2		mm) witches 6 157 157 157 182 182 182	8
	4.1	4.16	4.285	84	0.00714	1000	0.67				
1	6.5	6.88	7.083	50.8	0.0118	1200	1.1	132	132	157	157
	11	11.23	11.56	31.14	0.0193	1500	1.8				
	17.5	17.84	18.361	19.6	0.0306	1800	2.9			157	
2	29	29.5	30.35	11.86	0.0505	1800	4.7	132	132		182
	48	48.13	49.538	7.27	0.0825	1800	7.7				
	75	76.45	78.678	4.57	0.131	1800	12.2				
3	125	126.39	130.054	2.77	0.2166	1800	20.2	132	132	157	182
	205	206.26	212.272	1.69	0.3536	1800	33				
	323	327.6	337.135	1.06	0.5616	1800	52				
4	540	541.5	557.284	0.65	0.9284	1800	87	132	157	182	207
	880	883.8	909.59	0.4	1.515	1800	141				
	1384	1403.7	1444.62	0.25	2.406	1800	224				
5	2288	2320.2	2387.96	0.15	3.978	1800	371	132	157	182	207
	3735	3787.1	3897.58 0.09		6.493	1800	606				
	5900	6014.77	6190.204	0.06	10.313	1800	*				
6	9800	9942.2	10232.407	0.04	17.047	1800	*	157	157	182	207
	16000	16227.6	16701.17	0.02	27.824	1800	*				

Notes:

- 1. The mounting kit includes the flexible coupling and drive adapter.
- 2. More than 8 contacts on request.
- 3. Dimensions with more than 8 contacts and with special executions, eg. potentiometer, on request.
- 4. RLS-51 B5 Flange thickness = 4mm.
- 5. Options include anti-condensation heaters, potentiometer, pulse transmitter, encoder, aluminium housing and VBG-70 STAGE technology.
- 6. Mounting kits available for all screw jacks. For those not listed, consult Power Jacks.

Special Designs

OUR SCREW JACK
DESIGNS ARE FULLY
CUSTOMISABLE BY OUR
ENGINEERING TEAM SO
YOUR APPLICATION CAN
BE THE BEST.

Customised Products

For Power Jacks, every order is different.

We're ready every time to assess the precise requirements of the customer and formulate the right solution.

Off-the-shelf solutions are the norm for many engineering companies. And while they're certainly options for our customers, that's only the case if they're precisely the right options.

We pride ourselves on our adaptability – on our readiness to customise basic models, or even to start from scratch, so that we're providing products that offer optimum performance.

It's a customising service across our entire range of products that means customers get exactly what they need.

2 Special Design Examples

Special screw jack design are divided into 4 categories:

- 1. E-Class simple customisation
- 2. SE-Class enhanced design for specific performance.
- 3. HSE-Class highly enhanced design for specialised performance.
- 4. XSD extreme special designs for highly specialised performance.

E Class Special Design

Enhances screw jack design by making simple customisation and feature additions. Examples include (but not limited to): Non-Standard Paint, Non-Standard Plating, Non-Standard Lubrication, Non-Standard Seals, Non-Standard Motor Adapter, Plating of Screw Jack Gearbox Housing, 3-Start Thread on Lifting Screw for increased lead, Special Closed Height for Screw Jack, Extended Worm Shaft, etc...

25kN based on CMT0025 with special closed height




SE Class Special Design

Special Enhancements to screw jack designs where new parts and/or accessories are used to deliver the best performance for the application. Examples include (but not limited to): Integration of Brake to Screw Jack Body, Bespoke End Fitting on Lifting Screw, Lifting Nut with Square Flange, Non-Standard Worm Shaft Design, Cover Pipes on Rotating Screw Jack, etc.



HSE Class Special Design

High Specification Enhancements to screw jack design where significant changes are made to main screw jack design and/or new and/or specialised accessories are integrated. Examples include (but not limited to): Bespoke Clutch on Worm Shaft, Coil Spring Load Limiter, Centre of Gravity Balanced Designs, Bespoke Trunnion Mounts, Telescopic Lifting Screw, Lifting Screw with Left & Right Threaded Sections, Increased Base Thickness for Screw Jack Gearbox Housing etc..



XSD Class Special Design

eXtreme Special Design for screw jacks where a modification of our existing range is not practical for engineering and/or commercial goals. The way to get the best performance for the application is to design and manufacture a unique product using our state of the art screw jack technology. Examples include (but not limited to): Seismic Rated 3500kN Nuclear Screw Jacks, Large Valve Control Mechanisms, 200degC rated Screw Jacks, Ultra Light Weight Screw Jacks for mobile applications, Solar Tracking Screw Jacks



3500kN Seismic rated Nuclear Screw Jacks complete special design for translating and rotating machine screw jacks.

U-Series Underwater / Subsea Screw Jack Overview

The U-Series subsea screw jacks are a proven and reliable technology for subsea lifting, positioning and actuation solutions down to a depth of 3000m. They are used in a wide variety of underwater applications in the oil & gas sector. Each submersible variant is tailored exactly to the customer application.



- Proven depth ratings up to 3000m subsea as standard (deeper on request)
- Pressure compensated or flooded designs available
- Capacities up to 2000 kN (200Te) as standard
- Capacities up to 35000 kN (3500Te) on request
- Machine Screw Jacks
- Translating and rotating screw configurations
- Full stainless steel Screw Jacks
- Self-locking (the products only use power when moving)
- Anti-rotation mechanism for unconstrained loads
- · Anti-backlash mechanism for axial positioning
- Option for reinforced shaft design for up to 300% higher torque transmission

- Reinforced sealing
- Dual nut (safety nut) fail safe load-holding option
- Shock load rated units
- Full range of anti-corrosion options
- ROV drive interfaces
- Low (-65°C) to High (+250°C) temperature solutions available
- Vibration resistant designs
- Full range of feedback devices for speed, position, rotation, wear and load monitoring control
- Special custom designs available to meet your exact requiren



For more details request the U-Series brochure from Power Jacks or download a copy from www.powerjacks.com



U-Series Subsea Screw Jack Performance

Full Stainless Steel Construction

Model		UM-0025	UM-0050	UM-0100	UM-0200	UM-0300	UM-0500	UM-1000	UM-1500	UM-2000	
Capacity (kN)		25	50	100	200	300	500	1000	1500	2000	
Lifting Screw note1	Diameter X Pitch (mm)	30 x 6	40 x 9	55 x 12	65 x 12	95 x 16	120 x 16	160 x 20			
Gear Ratios	Option 1	6:1	6:1	8:1	8:1	102/3:1	102/3:1	12:1			
Geal Ratios	Option 2	24:1	24:1	24:1	24:1	32:1	32:1	36:1			
Turn of worm for raise of	Option 1	1 for 1mm	1 for 1.5mm	1 for 1.5mm	1 for 1.5mm	1 for 1.5mm	1 for 1.5mm	3 for 5mm			
lifting screw	Option 2	4 for 1mm	4 for 1.5mm	2 for 1mm	2 for 1mm	2 for 1mm	2 for 1mm	9 for 5mm	1500 VANILIAN ON Regulact		
Maximum Input Power	Option 1	1.5	3	3.75	3.75	6	11.25	18.5			
(kW)	Option 2	0.375	0.55	1.125	1.125	1.9	4.5	8.25			
Start up Torque at full load	Option 1	19.8	56	115.9	263.8	480	900	2025			
(Nm) note2	Option 2	8.7	25.5	60.5	137	284	504	1119	1500		
Weight (kg) – stroke = 150mm	UMT	8.45	14.9	24.3	42.4	92.4	183.7	459.1	1	รล	
Weight (kg) – Stroke = 130mm	UMR	8.85	16.54	28.8	49.58	113.78	224	560.4	1500 to ald all all all all all all all all all	b b	
Weight (kg) per extra 25mm	UMT	0.21	0.32	0.58	0.84	1.55	2.48	4.11		r R	
weight (kg) per extra 25mm	UMR	0.11	0.19	0.36	0.52	1.13	1.94	3.38] -	916	
	Gear Ratio	6:1	6:1	8:1	8:1	102/3:1	102/3:1	12:1] -	<u> </u>	
Option 1	Screw jack Static Efficiency	0.201	19.8 56 115.9 263.8 480 900 2025 8.7 25.5 60.5 137 284 504 1119 8.45 14.9 24.3 42.4 92.4 183.7 459.1 8.85 16.54 28.8 49.58 113.78 224 560.4 0.21 0.32 0.58 0.84 1.55 2.48 4.11 0.11 0.19 0.36 0.52 1.13 1.94 3.38 6:1 6:1 8:1 8:1 10²/3:1 10²/3:1 12:1 0.201 0.213 0.206 0.181 0.149 0.132 0.131 0.264 0.281 0.272 0.242 0.205 0.181 0.178	A							
o	Screw jack Dynamic Efficiency	0.264	0.281	0.272	0.242	0.205	0.181	0.178	1500		
	Gear Ratio	24:1	24:1	24:1	24:1	32:1	32:1	36:1			
9 So	Screw jack Static Efficiency	0.115	0.117	0.132	0.116	0.084	0.079	0.079			
o o	Screw jack Dynamic Efficiency	0.167	0.172	0.190	0.169	0.128	0.120	0.123			
Standard Depth Rating	m	3000	3000	3000	3000	3000	3000	3000	30	00	
Flooded Design Ava	ilable	Υ	Y	Y	Y	Y	Y	Y	`	1	
Pressure Compensated Des	sign Available	Υ	Υ	Υ	Y	Υ	Υ	Υ	,	1	

Notes:

- 1. All metric machine screws have a trapezoidal thread form, single start as standard (diameter x pitch)
- 2. For loads of 25% to 100% of Screw Jack capacity, torque requirements are approximately proportional to the load
- 3. Efficiency values for standard grease lubricated worm gear box and lifting screw
- 4. For performance of anti-backlash and anti-rotation (keyed) models, consult our Power Jacks experts

Standard construction:

- 5. Stainless steel Screw Jack rated for rated capacity in tension or compression for static or dynamic movement
- 6. Lubrication = EP2 Grease
- 7. Paint finish = Power Jacks Standard Subsea Yellow (other colours available on request)
- 8. Other materials, plating and paint specifications are available to suit all applications and budgets

Please supply depth rating required with enquiry

POWERJACKS







GRAPHITE HANDLING MACHINE


The Graphite Handling system was developed to retrieve graphite components, capping pieces and thermocouples from inside nuclear reactors, crush them for size reduction and deposit them into shielded flasks. The machine houses 4 types of flask.

The Crusher Jaws are driven by three 50 kN E-Series Ball Screw Jacks, complete with Bevel gearbox, brake and motor, to size reduce the component. The selected Flask is raised into the docking position by two more 50kN screw jacks, driven by a single electric motor via bevel gearboxes. The size reduced component is deposited into the flask and the flask is returned to its storage position.

For more application examples see the 'Power at Work' brochure or www.powerjacks.com.









COIL SPRING LOAD LIMITER

When an industrial machine needs to move a cover or lid onto a dead stop or sealing face it must do so precisely and positively, with contact on all dead stops or over the complete sealing face.


To push the cover into position precisely Power Jacks designed a special coil spring load limiter for the end of the jacks lifting screw.


For more application examples see the 'Power at Work' brochure or www.powerjacks.com.




ENGINEERING GUIDE

USEFUL PERFORMANCE & OPERATIONAL DETAIL FOR SCREW JACKS









L

9


Important Notes


1. All charts are rated for industrial cargo with a safety factor of 3.5.


Machine Screw Jack Column Strength Charts


2. For human cargo a safety factor of 5 is recommended. To alter the permissible compressive load (WP) for human cargo multiply the load selected from the chart by 0.7 e.g. $W_{p_{HC}} = W_{p} * 0.7$.


Column Length Correction Factors, F_{cb}



















Note


- 1. Column end constraints based on A.I.S.C. recommended values
- 2. All screw jack column strength charts show a Euler buckling curve and three scales for the appropriator end condition for the application under analysis.


9


Machine Screw Jack Column Strength Charts















Note


- 1. Column end constraints based on A.I.S.C. recommended values
- 2. All screw jack column strength charts show a Euler buckling curve and three scales for the appropriator end condition for the application under analysis.
















Ball Screw Jack Column Strength Charts
















Machine Screw Critical Screw Speed (Shaft Whirling)



Based on both ends fixed and 80% of the critical speed.

Ball Screw Critical Screw Speed (Shaft Whirling)



Based on both ends fixed and 80% of the critical speed.

The key torque (restraining torque) is caused by the tendency of the lifting screw to rotate. It is a function of the screw lead, screw efficiency and the load. It is not affected by the screw jack unit gear ratio.

Note

The values below are given at rated load. For a smaller load reduce the key torque in direct proportion.

Machine Screw Jacks

Capacity (kN)	Screw Diam (mm)	Lead (mm)	Key Torque (Nm)
5	16	0.003	8
5	16	0.006	11
10	20	0.005	22
10	20	0.010	30
25	30	0.006	76
25	30	0.012	102
50	40	0.009	210
50	40	0.018	290
100	55	0.012	575
100	55	0.024	780
200	65	0.012	1300
200	65	0.024	1705
300	95	0.016	2805
300	95	0.032	3610
500	120	0.016	5645
500	120	0.032	6975
1000	160	0.020	14890
1000	160	0.040	18220
1500	180	0.020	24610
2000	220	0.024	39995

Ball Screw Jacks

Capacity (kN)	Screw Diam (mm)	Lead (mm)	Key Torque (Nm)			
10	20	0.005	9			
10	-	-	-			
25	25	0.005	23			
25	25	0.01	43			
50	40	0.01	88			
50	40	0.02	167			
100	50	0.01	181			
100	50	0.02	340			
200	63	0.01	370			
200	63	0.02	690			
300	80	0.02	1030			
500	On Request					

187

Maximum Jack Side Load Ratings with Full Jack Rated Load in Tension


Machine Screw Jacks

Metric Machine Screw Jack									
Capacity (kN)	5	10	25	50	100	200	300	500	1000
Max. Side Load 300mm Offset (N)	100	150	540	1130	2900	3350	17500	37800	83400


Ball Screw Jacks

Ball Screw Jack											
Capacity (kN)	10	25	25	50	50	100	100	200	200	300	500
Ball Screw Lead (mm)	5	5	10	10	20	10	20	10	20	20	*
Max. Side Load 300mm Offset (N)	105	195	195	980	980	1570	1570	2060	2060	4340	*

^{*}Consult Power Jacks.



To calculate maximum side load for different raises for screw jacks in tension under full rated load use the following formula to modify the above tabulated values.



Note

The correct units must be used

Important Notes

- 1. These figures are for Screw Jacks in tension only.
- 2. The figures given above are permissible side load ratings, however, we recommend that all side loads be carried by guides in your arrangement and not by the screw and nut.
- 3. Life of the lifting screw and nut will be adversely affected the more side load they see.
- 4. These figures are based on acceptable stresses in the lifting screw and not on lifting screw deflection.
- 5. For maximum side load ratings for screw jacks in compression consult Power Jacks Ltd.
- 6. For precise calculations for your application consult Power Jacks Ltd.

Radial Loads on Screw Jack Worm Shaft

For applications where a screw jack is belt/chain driven, a calculation must be made to determine the radial force (Fo) and compared to the allowable radial load exerted on the worm shaft, that must not exceed those tabulated below. The values below are maximum values for the screw jacks at rated load regardless of worm speed or load direction and the radial load applied midway along the key of the worm shaft. For all applications the sprocket, gear etc. Should be positioned as close as possible to the screw jack housing in order to reduce bearing loads and shaft stresses and to prolong life.

Radial Force,
$$F_R = \frac{2000 \times T \times K}{D}$$


Where


= Radial Load (N)

= Torque applied to the screw jacks input shaft (Nm)

= Factor from table below **D** = PCD in mm of gear, sprocket

Transmission Element	Factor K			
Chain sprocket	1			
Gears (spur or helical pinion)	1.25			
V-Belt pulley	1.5			
Flatbelt pulley	2.0			





Capacity (kN) 25 50		
Capacity (KIN) 25 30	100	200
Radial Load (N) 440 1100	1200	1600

Machine Screw Jack									
Capacity (kN)	5	10	25	50	100	200	300	500	1000
Radial Load (N)	180	325	380	740	1000	1600	2170	2190	2220

189

Machine Screw Jacks

Component	Normal Backlash
Lifting Screw and Nut	$0.12 \text{mm} \rightarrow 0.2 \text{mm} (0.005" \rightarrow 0.008")$
Load Bearings	$0.00 \text{mm} \rightarrow 0.03 \text{mm} (0.000" \rightarrow 0.001")$
Total	$0.12 \text{mm} \rightarrow 0.23 \text{mm} (0.005" \rightarrow 0.009")$

Note

- 1. The lifting screw backlash will increase during operation due to wear of threads in the nut
- 2. Axial play can be reduced by altering the load bearings preload to eliminate bearing play or by specifying a screw jack with the Anti-Backlash feature
- 3. For exact backlash ratings for an individual unit consult Power Jacks.

Anti-Backlash Option

Machine screw jacks fitted with the anti-backlash feature can be adjusted for screw thread and bearing clearances to a minimum of 0.025 mm (0.001"). Some clearances must be maintained to keep torque requirements within reason and to provide adequate space for a lubrication film to form.

Ball Screw Jacks

Component	Normal Backlash
Ball Track and Nut	$0.05 \text{mm} \rightarrow 0.15 \text{mm} (0.002" \rightarrow 0.006")$
Load Bearings	$0.00 \text{mm} \rightarrow 0.03 \text{mm} (0.000" \rightarrow 0.003")$
Total	$0.05 \text{mm} \rightarrow 0.18 \text{mm} (0.0002" \rightarrow 0.007")$

Note

- 1. For exact backlash ratings for an individual unit consult Power Jacks.
- 2. Ball nuts can be supplied with zero backlash or with adjustable backlash via a special twin nut assembly (twin nut assembly for rotating screw units only). Consult Power Jacks for details.
- 3. Altering the load bearings preload to eliminate bearing play can reduce axial play.
- 4. There is no Anti-Backlash nut feature for the gear sets of these screw jacks.

Pitch Deviation of Lifting Screw

Lifting Screw	Pitch Deviation
Machine Screw	0.05mm → 0.25mm per 300mm
Ball Screw	0.025mm → 0.050mm per 300mm (DIN Class 5.7)

Note

- 1. Pitch deviation is cumulative and **NOT** detrimental to the operation of the Screw Jack
- 2. The Lifting screws are manufactured from material with a straightness tolerance of 0.2 mm per metre
- 3. Pitch deviation is related to the cutting machines tolerance and the material used.

Lateral Movement Ratings


Machine Screw Jacks

Stroke (mm)	5kN	10kN	25kN	50kN	100kN	200kN	300kN	500kN	1000kN
100	0.7	0.6	0.8	1.0	1.0	0.4	0.4	0.7	0.7
200	1.3	1.1	1.4	1.7	1.7	0.7	0.6	1.0	1.0
300	1.9	1.5	1.9	2.3	2.3	0.9	0.8	1.3	1.3
400	2.5	2.0	2.5	2.9	2.9	1.2	1.0	1.7	1.6
500	3.1	2.4	3.1	3.6	3.6	1.4	1.2	2.0	1.9
600	3.7	2.8	3.6	4.2	4.2	1.6	1.4	2.3	2.2
700	4.3	3.3	4.2	4.8	4.8	1.9	1.6	2.6	2.4
800	4.8	3.7	4.8	5.5	5.5	2.1	1.8	2.9	2.7
900	5.4	4.2	5.3	6.1	6.1	2.4	1.9	3.2	3.0
1000	6.0	4.6	5.9	6.7	6.7	2.6	2.1	3.6	3.3

Notes


- 1. Values quoted above are the maximum expected lateral movement for the given raise and screw jack model.
- 2. Does not allow for possible deflection due to side loads.
- 3. Lateral movements are for information only. For best results we recommend guides where possible.
- 4. Lateral movements will be reduced if the screw jack is fitted with secondary guides.
- 5. The above movements apply to machine screw jack only and not ball screw jacks. Permitting lateral movement on the ball screw jack under load will exert side thrust on the ball screw and ball nut and will be detrimental to the ball screw and nut life. Ball screw applications should be guided to ensure a minimum of lateral movement.
- 6. Where lateral movement is critical consult Power Jacks for exact values for the application.

191




How a Rotating Screw Jack Works

The rotation of the worm shaft causes the worm gear to rotate. For rotating screw jacks the lead screw is fixed to the worm gear and they rotate at the same speed. The lifting nut moves along the lead screw. As the worm gear turns, the friction forces on the screw thread act to turn the nut also. The greater the load on the screw jack unit, the greater the tendency of the nut to turn. If the nut turns with the screw, it will not raise the load. Therefore the nut needs to be fixed to a structure to prevent rotation. The restraining torque required for the structure, also known as the "lead screw key torque" can be found on the product performance tables in this catalogue or requested from Power Jacks.



How a Translating Screw Jack Works

The rotation of the worm shaft causes the worm gear to rotate. For translating screw jacks the worm gear is threaded to accommodate the lead screw thread. The lead screw translates through the gear. As the worm gear turns, the friction forces on the screw thread act to turn the screw also. The greater the load on the screw jack unit, the greater the tendency of the screw to turn. If the screw turns with the nut (worm gear), it will not raise the load. In those cases where a single unit is used, and where the load cannot be restrained from turning, it is necessary to use a screw jack with an anti-rotation mechanism (keyed screw jack). Lead screw key torque (refer to the product performance tables in this catalogue or request from Power Jacks) must be checked as excessively heavy unguided loads could break the Anti-rotation mechanism (key).



Anti-Backlash Screw Jack - When To Use

For reduced axial backlash of the lead screw in the screw jack select a model with the "Anti-Backlash" mechanism. This is typically used when the load direction changes from tension to compression and minimal axial backlash is required. This design is only available for translating screw jacks. It can be combined with Anti-Rotation mechanism as well.

Input Torque Required for a Screw Jack

The input torque for a single screw jack depends on the load, the worm gear ratio, type of screw (machine screw, ball screw or roller screw) and the pitch of the lead screw. Torque values are listed in the individual product specification charts based on capacity loads. For loads from 25% to 100% of screw jack model capacity, torque requirements are approximately proportional to the load.

Note

The input torque, as well as the efficiency and side load ratings, is the same for both translating screw and rotating screw jacks.

Maximum Input Power & Speed for a Screw Jack

The input power to the screw jacks should not exceed the power rating shown in the specifications table. Maximum input speed in rpm (revolutions per minute) to a screw jacks worm shaft should not exceed 1800 rpm for C & E-Series screw jacks.

Efficiency of a Screw Jack

Screw Jack model efficiencies are listed in the individual product specification charts.

Expected Life of a Screw Jack

The life expectancy of a screw jacks lead screw, bearings, nut and worm gear set varies considerably due to the extent of lubrication, abrasive or chemical action, overloading, excessive heat, improper maintenance, etc. For detailed life calculations, consult Power Jacks.

Screw Jack with Anti-Rotation (Keyed) Mechanism

This design is only available for translating screw jacks. If the structure/object connected to the lead screw is not prevented from rotating or the lead screw is not always in contact with the structure then a screw jack with an "Anti-Rotation" mechanism (keyed) should be used.

Standard Screw Jacks - How To Prevent The Load from Rotating

For multiple screw jack systems, fix the lead screw end fittings (e.g. top plate or clevis) to the common member being lifted by all the units. For single screw jack applications, bolt the lead screw end fitting (e.g. top plate or clevis) to the load and ensure the load is guided to prevent rotation.

A guided load is always recommended to ensure that the screw jack does not receive any side load and so guidance can be scaled suitably for the load without altering the screw jack design unnecessarily. Note that an external guidance system can provide a higher restraining "key" torque than compared to an anti-rotation mechanism in a screw jack.

Self-Locking of Screw Jacks

Screw Jacks with 24:1 or higher gear ratios are considered self-locking in most cases. Consult Power Jacks for a recommendation specific to your application.

All screw jacks with multi-start lifting screws are considered not to be self-locking.

All ball screw and roller screw jacks are considered <u>not</u> to be self-locking.

Screw Jacks considered not self-locking will require a brake or other holding device.

Shock Loads on a Screw Jack

Shock loads should be eliminated or reduced to a minimum, if they cannot be avoided, the screw jack model selected should be rated at twice the required static load.

For severe shock load applications, the load bearings can be replaced with heat-treated steel thrust rings which is an option available from Power Jacks. Note this will increase the input torque by approximately 100%.

Axial Backlash in a Screw Jack

Backlash in Standard Machine Screw Jacks

Machine screw jacks have backlash due not only to normal manufacturing tolerances, but to the fact that there must be some clearances to prevent binding and galling when the screw jack unit is under load. Usually, the axial backlash is not a problem unless the load on the screw jack unit changes between compression and tension. If a problem does exist, a unit with the anti-backlash feature should be considered.

Screw Jacks with the Anti-Backlash Device

The anti-backlash device reduces the axial backlash between the lead screw and nut assembly to a regulated minimum. As the backlash will increase as the lead screw thread on the gear wears the anti-backlash device can be adjusted to remove this normal condition.


How the Anti-Backlash Device Works

When the screw (1) is under a compression load, the bottom of its thread surfaces are supported by the top thread surfaces of the worm gear (2) at point (A). The antibacklash nut (3), being pinned to the worm gear and floating on these pins and being adjusted downward by the shell cap, forces its bottom thread surfaces against the upper thread surfaces of the lifting screw at point (B). Thus, backlash between worm gear threads is reduced to a regulated minimum.

When wear occurs in the worm gear threads and on the load carrying surfaces of the lifting screw thread, the load carrying thickness of the worm gear thread will be reduced. This wear will create a gap at point (B) and provide backlash equal to the wear on the threads

Under compression load, the lifting screw will no longer be in contact with the lower thread surface of the anti-backlash nut. Under this condition, backlash will be present when a tension load is applied. The anti-backlash feature can be maintained simply by adjusting the shell cap until the desired amount of backlash is achieved.

To avoid binding and excessive wear do not adjust lifting screw backlash to less than 0.025mm (0.001"). This will reduce the calculated separation (C) between the antibacklash nut and worm gear and will reduce the backlash between the worm gear threads and the lifting screw to the desired minimum value.



When separation (C) has been reduced to zero, wear has taken place. Replace the worm gear (2) at this point. This feature acts as a built in safety device which can be used to provide wear indication for critical applications.

Column Strength of the Screw Jack

Column strength of a screw is determined by the relationship between the screw length and its diameter. For column strength charts consult product literature or Power Jacks.

Side Loads on a Screw Jack

Screw jacks are designed primarily to move and position loads and any side loads (loads not acting axially on lead screw) should be avoided. The units will withstand some side loads, depending on the diameter of the lifting screw and the extended length of the lifting screw. Where side loads are present, the loads should be guided and the guides, rather than the screw jacks, should take the side loads - particularly when long raises are involved. Even a small side load can exert great force on the housings and bearings and increase the operating torque and reduce the life expectancy.

Allowable Duty Cycle of Screw Jack

Because of the efficiency of conventional worm gear screw jacks, the duty cycle is intermittent at rated load. At reduced loading, the duty cycle may be increased. Ball screw jacks are more efficient than machine screw jacks and so can provide a higher duty cycle. In addition Power Jacks have special designs for high duty cycle screw jacks. For detailed analysis consult Power Jacks Ltd.

Operation

POWERJACKS

Maximum Operating Temperatures For E-Series Screw Jack

Normal operation at ambient temperatures of up to 90°C. Operations above 90°C will require special lubricants. For temperatures above 90°C, the life of even special lubricants is limited. Therefore consult Power Jacks on your application. For temperatures above 90°C, advise Power Jacks of full particulars of the duration of such temperatures. Power Jacks suggest that a lubricant manufacturer be consulted for type of grease and lubrication schedule. As a general rule, the screw jack unit should be shielded to keep ambient temperatures to 90°C or less.

Minimum Temperature For E-Series Screw Jacks

With the standard lubricant and materials of construction, the screw jacks are suitable for use at sustained temperatures of -20°C. Below -20°C, low temperature lubricant should be used and no shock loads are present. Power Jacks application engineers must be consulted in these instances for a recommendation. Screw Jacks with standard material of construction and lubrication may be safely stored at temperatures as low as -55°C.

Thermal / Heat Build-Up in a Screw Jack as it is operated

The duty cycle, the length of the screw, the magnitude of the load, and the efficiency of the screw jack all have a direct influence on the amount of heat generated within the screw jack. Long lifts can cause serious overheating. Note that Power Jacks have special designs with higher thermal capacities than conventional worm gear screw jacks (consult Power Jacks for more details).

Screw Jacks to Pivot a Load

A screw jack can be built to pivot a load by two methods:

1. Double Clevis Screw Jack

The screw jack can be furnished with a clevis at both ends (commonly referred to as a double clevis screw jack). The bottom clevis is welded to the bottom end of an extra strong cover pipe, which is fitted to the base of the screw jack. This cover pipe still performs its primary function of encasing the lifting screw in its retracted portion. The clevis ends can be replaced with other pivot options such as Fork End or Rod End.

2. Clevis - Trunnion Mounting

The screw jack is fitted with the pivot end fitting (e.g. Clevis, Fork or Rod End) on the lead screw and a trunnion mount adapter is bolted to the screw jacks base plate.

The design of the structure in which these types of screw jacks are to be used must be constructed so that screw jack can pivot at both ends. Use only direct compression or tension loads, thereby eliminating side load conditions.

Corrosion Resistant Properties

Screw Jacks can be supplied with alternative materials and/or paint specifications for high corrosive areas. These options include stainless steel, chrome plating, electro-nickel plating, epoxy paint, etc. Check the unit specification is suitable before installation.

Using Screw Jacks within a Rigid Structure or Press

Power Jacks recommend that the screw jack selected has a greater capacity than the rated capacity of the press or of the load capacity of the structure. We also recommend that a torque clutch or similar device be used to prevent overloading of the screw jack unit. Unless these precautions are taken, it is possible to overload the screw jack without realising it.

Screw Jack Drift after Drive Motor is Switched Off

The screw jack will drift after the motor drive is switched off unless a brake of sufficient capacity is used to prevent it. The amount of drift will depend upon the load on the screw jack and the inertia of the rotor in the motor.

For machine screw jacks with no load, the amount of drift will depend upon the size and speed of the motor. For example, a 1500 RPM input directly connected to a screw jack without a load will give on average 35mm to 60mm of drift; a 1000 RPM input will give about 1/2 as much drift. Note that the drift varies as the square of the velocity (RPM). The drift of the screw jacks screw can be controlled by using a magnetic brake on the motor. Variations of drift will also be seen if the motor drives the screw jack via a reduction gearbox.

195

Screw Jacks Operation where Vibration is Present

Screw Jacks will operate in areas with vibration, however the vibration may cause the lead screw to "creep" or "inch" under load. For applications involving slight vibration, select the higher of the worm gear ratios. If considerable vibration is present, use a motor equipped with a magnetic brake, which will prevent the screw jack from creep and/or back-driving.

Use of Screw Jacks Fitted With Emergency Stop Disc

To prevent over travel of the lead screw, a stop disc or nut can be fitted to a screw jack that is hand operated. It should not be used as a full power stop.

Use of Screw Jacks Fitted With Emergency Stop Nut

For motor driven units, it is possible for the full capacity of the screw jack or even a greater force (depending on the power of the motor) to be applied against the stop. These stops are called "full power stop nuts". They must only be used as an emergency device and if such a condition occurs, an assessment made to discover why it happened in order to carry out preventative action. If the full power stop nut is used at full load in an emergency it might be driven into the unit jamming so tightly that it must be disassembled in order to free it.

It is recommended that external stops are fitted where possible, however they must only be used as a last resort (Note - limit switches are one possible solution to constrain screw jack movement safely - consult Power Jacks for system advice). Under ideal conditions where a slip clutch or torque limiting device is used, a stop pin or stop nut may be used - but Power Jacks should be consulted.

Screw Jack System Arrangements

Perhaps the greatest single advantage of Power Jacks screw jacks is that they can be linked together mechanically, to lift, lower, move or position in unison. Typical mechanical system arrangements link 2, 4, 6 or 8 screw jacks together and are driven by one motor. As an alternative, screw jacks can be individually driven by electric motors and with suitable feedback devices, such as encoders, be synchronised electronically by a control system.

Connecting Screw Jacks in Series

The number of screw jacks that can be connected in series is limited by input torque requirements on the first worm shaft in the line. For the C & E-Series the torque on the worm shaft of the first screw jack should not exceed 300% of its rated full load torque (this does not include the 200kN screw jacks which are rated at 150%).

Efficiency of a Multiple Screw Jack System

In addition to individual device efficiencies, the efficiency of the screw jack arrangement must be taken into consideration. The arrangement efficiency allows for misalignment due to slight deformation of the structure under load, for the losses in couplings, bearings, and for a normal amount of misalignment in positioning the screw jacks and gearboxes. For efficiency values consult Power Jacks product literature or engineers.

Number of Screw Jacks in System	2	3	4	6-8
Jacking System Efficiency	0.95	0.90	0.85	0.80

Screw Jack Fitted with 3rd Party Accessories

If your screw jack is fitted with a device not manufactured by Power Jacks then please consult the provided manual for this device.

Installation and Maintenance Tips

The following installation and maintenance tips are for the C & E-Series, Metric machine screw and ball screw jacks models. General care should be taken to ensure that equipment is sufficient to handle the load.

- 1. The structure on which the screw jack unit is mounted should have ample strength to carry the maximum load, and be rigid enough to prevent undue deflection or distortion of the screw jack unit supporting members.
- 2. It is essential that the screw jack be carefully aligned during installation so that the lifting screws are vertically true and the connecting shafts are exactly in line with the worm shafts. After the screw jack, shafting, and gear boxes are coupled together, it should be possible to turn the main drive shaft by hand. If there are no signs of binding or misalignment, the jacking system is then ready for normal operation.
- 3. The screw jack should have a greater stroke than is needed in the screw jack installation. If it is necessary to operate the screw jack at the extreme limits of travel, it should be done with caution.

CAUTION: Do not allow screw travel below catalogue closed height of the screw jack or serious damage to internal mechanism may result. Refer to table specifications for closed height of respective units.

- 4. The input power should not exceed the power rating shown in the specification table. Maximum RPM should not exceed 1800.
- 5. The lifting screw should not be permitted to accumulate dust and grit on the threads. If possible, lifting screws should be returned to closed position when not in use.
- 6. The ball screws in the ball screw jacks should be checked periodically for excessive backlash and spalling of raceways. A periodic check of backlash of the lifting screw thread is recommended to check wear of the worm gear internal threads on the machine screw jack models. Backlash in excess of 50% of the thread thickness indicates the need to replace the worm gear.
- 7. Unless otherwise specified, screw jacks are shipped packed with grease which should be sufficient for one month of normal operation. For normal operation, the screw jacks should be lubricated about once a month, using one of the following extreme pressure greases or their equivalent:

Shell Gadus S2V220AC2 (Alvania WR2)

BP Energrease LC2
Castrol Spheerol EPL2
Mobil Mobilux EP2

For severe conditions, the screw jacks should be lubricated more frequently, using one of the above greases (daily to weekly depending on conditions). If duty is heavy, an automatic lubrication system is strongly recommended. If ambient temperatures exceed 90°C (194°F) consult Power Jacks.

8. On ball screw jack applications, periodically lubricate the exposed ball screw grooves with a cloth dampened with a good grade 10W30 oil for most applications. An instrument grade oil should be used in dirty and heavy duty environments, and bearing grease for environments at extremely high temperatures. Extreme temperature and other environmental conditions should be referred to Power Jacks for recommended lubricating procedures.

CAUTION: Where ball screws are not protected from airborne dirt, dust, etc., bellows boots should be used. Inspect frequently at regular intervals to be certain a lubricating film is present. Ball screws should never be run dry.

9. Due to the high efficiency of the ball screw jack design, a brake must be used in conjunction with motor selected to position the screw jack.

Useful Formulae for Screw Jack Calculations

Lifting Screw Lead

Lifting Screw lead (mm) = Screw Pitch (mm) *Number of Starts on Lifting Screw

Calculation of the Linear Speed

When the worm shaft speed is known, the linear speed can be determined with this formula:

Calculation of Screw Jack Input Torque

Calculation of Screw Jack Input Power

Input Power (kW) =
$$\frac{\text{Load (kN) x Lifting Screw Lead (mm) x Input Speed (rpm)}}{60000 \text{ x Efficiency x Gear Ratio}}$$
or alternatively
$$\frac{\text{Load (kN) x Linear Speed (mm/min)}}{60000 \text{ x Efficiency}}$$

Useful Formulae for Screw Jack Calculations

Power	Metric	Imperial
Lifting Motion	$P = \frac{m \times g \times v}{\eta \times 1000}$	P=
Linear Motion	$P = \frac{F_R \times v}{1000}$	$P = \frac{F_R \times V}{33000}$
	$F_R = \mu \times m \times g$	F _R = µxw
Rotary Motion	P = T x n 9550	P= Txn 63000

Torque

$$T = F_R x r$$
 $T = T x r$

Linear Motion
$$T = \frac{P \times 9550}{n}$$

$$T = \frac{P \times 6300}{n}$$

Symbol	Quantity	Metric Units	Imperial Units
Р	Power	kW	HP
T	Torque	Nm	lbf.in
F _R	Resistance due to Friction	N	lbf
m	Mass	kg	-
W	Weight	-	lb
g	Gravitational Acceleration	9.81 ms ⁻²	32.185 ft ⁻²
V	Velocity	ms ⁻¹	ft/min
η	Efficiency	decimals	decimals
μ	Coefficient of Friction	decimals	decimals
n	Rotational Speed	rpm	rpm
r	Radius	m	in

Useful Formulae for Screw Jack Calculations

Moment of Inertia	Metric	Imperial
Solid Cylinder	$J = \frac{1}{2} \times m \times r_{od}^2$	$WK^2 = \frac{1}{2} \times W \times r_{od}^2$
Hollow Cylinder	$J = \frac{1}{32} \times \varpi \times \rho \times d_{od} 4$	$WK^2 = \frac{\varpi}{32} r \times l \times d_{od}^4$
	$J = 0.098 \times \rho \times I \times d_{od}^{4}$	$WK^2 = 0.1 \times \rho \times I \times d_{od}^4$
Hollow Cylinder	$J = \frac{1}{2} \times m \times (r_{od}^2 - r_{id}^2)$	$WK^2 = \frac{1}{2} \times W \times (r_{od}^2 - r_{id}^2)$
Hottow Cyunder		34 .4
	$J = \frac{1}{32} \times \varpi \times \rho \times I \times (d_{od}^{4} - d_{id}^{4})$ $J = 0.098 \times \rho \times I \times (d_{od}^{4} - d_{id}^{4})$	$WK^{2} = \frac{\varpi}{32} \times \varpi \times \rho \times I \times (d_{od}^{4} - d_{id}^{4})$ $WK^{2} = 0.1 \times \rho \times I \times (d_{od}^{4} - d_{id}^{4})$
		55 10

Acceleration or Braking Time

$$T_{acc} = \frac{J \times n}{9.55 \times T_{acc}} \qquad T_{acc} = \frac{WK^2 \times n}{308 \times T_{acc}}$$

Symbol	Quantity	Metric Units	Imperial Units
J	Moment of Inertia (metric)	kgm ²	-
WK ²	Moment of Inertia (imperial)	-	lb.ft ²
T _{acc}	Torque due to Acceleration or Braking	Nm	lbf.ft
m	Mass	kg	-
W	Weight	m	lb
g	Outer Radius	m	ft
V	Internal Radius	m	ft
η	Outer Diameter	m	ft
μ	Internal Diameter	m	ft
n	Density	kg/m ³	kg/m ³
r	Time for Acceleration or Braking	S	5
r	Rotational Speed	rpm	rpm

Range-C Bevel Gearboxes

ULTRA COMPACT & VERSATILE SPIRAL BEVEL GEARBOXES

Features

201





Introducing the Range-C bevel gearbox range from Power Jacks, a compact and versatile design in a cubic housing.

Created by a team of experienced design engineers, the focus was to provide our customers with a compact bevel gearbox in a "cubic" housing that offers versatility in design. In addition to this, we wanted to design a bevel gearbox that had the perfect combination of excellent performance, a long lasting service life, durability and the flexibility to be engineered for the most demanding applications.

Perfect for industrial applications or the extreme such as subsea, defence or nuclear.

Standard Gearbox

- 6 Gearbox Sizes
 35, 37, 38, 39, 40, 42* Series
 *42-Series in Range-N design only
- 16 Gearbox Configurations
- Gear Ratios:
 1:1, 1.5:1, 2:1, 3:1 and 4:1*
 *No 4:1 on 35-Series
- Special gear ratios available on request e.g. 1.25:1
- Power Ratings: 0.1 226 kW
- Torque Ratings: 15 Nm 7000Nm
- Mounting Points on Every Gearbox Side (35 40 Series)

Reliable Spiral Bevel Gear

With a proven design already used in millions of gearboxes, the Precision Spiral Bevel Gears with accurate gear mesh delivers high torque with smooth and quiet transmission.

Superior Gear and Shaft Support

For gear ratios 1:1 and 1.5:1 where each gear has a bearing support on both sides. This gives optimum gear support and minimises bearing hub sizes for non-through shaft configurations.

Shaft Configurations

- 2, 3 or 4-way
- Solid or hollow shaft
- Special configurations available
- Motor Adapter to bolt an IEC motor directly to the gearbox input
- Service life of 10,000 hours for all gearbox sizes
- Input Speed up to 3000 rpm maximum
- Breather / vents available for high speed designs



Gearbox Housing

A rugged Cubic Compact design made from a highly durable SG Iron. This provides a strong housing that firmly and accurately holds the gear set in a reservoir of quality lubricant suited to the most industrial demands.





Corrosion Protection

To suit all economic needs.

- Standard Industrial Paint Finish
- Arduous Environment Paint Finish
- Customer Specified Paint
- Plated Finish
- Stainless Steel







Based on Ratio 1:1, 3way solid shaft, Gear Unit Size *42 Series is Range-N design

Example

C380S30-10M06-0000-00000 C-Range, 38 Series, Standard, Solid Shaft, 4-Way, Standard Gear Configuration, 1:1 Gear Ratio, Metric Shaft (mm) - Spiral Bevel, Standard Material Shafts lubrication and paint.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30
С	3	8	0	S	3	0	-	1	0	М	0	6	-	0	0	1	0	-	0	0	0	0	-	0	0	0	0	0	0

1 GROUP-1 - Bevel Gearbox Definition

2 GROUP-2 - Bevel Gearbox Features

3 GROUP-3 - Accessories

1 GROUP-1 - Bevel Gearbox Definition

1-Bevel Gearbox Range					
С	Compact Cubic, Versatile Design with mounting bolt holes on every gearbox side				
N	Ultra Compact, Versatile Design				

2-3 - Gearbox Series	35	37	38	39	40	42

4-Gearbox	4-Gearbox Type				
0	Standard				
٧	Vertical Shaft				

5-Shaft Type					
S	Solid Shaft				
Н	Hollow Shaft				

6-Shaft Number						
2	2-Way					
3	3-Way					
4	4-Way					

7-Shaft Configuration				
0	Standard Gear Configuration			
R	Reverse Gear Configuration			

8 - Character Space

9-10 - Sha	9-10 - Shaft Number					
10	:1 Gear Ratio					
15	1.5:1 Gear Ratio					
20	2:1 Gear Ratio					
30	3:1 Gear Ratio					
40	4: 1 Gear Ratio					

11-Gear & Shaft Design		
М	Metric Shaft (mm) - Spiral Bevel	

12-13 - Design Revision XX Internal Numbering System Only #1

14 - Character Space

2 GROUP-2 - Bevel Gearbox Features

	15-Gearbox Housing Material	
	0	Standard Material (SG Iron)
ı	А	Aluminium
ı	N	Nickel Plated SG Iron Housing
	S	Stainless Steel Housing

17-Mounting	
0	Standard Range-N - 4 Tapped Holes - Side 5 & 6
1	Standard Range-C - ALL Sides Tapped Holes
5	4 Tapped Holes Side 5 Only
6	4 Tapped Holes Side 6 Only
Α	Base Flange - Bolt-On - Side 5
В	Base Flange - Bolt-On - Side 6

16-Drive Shaft Design	
0	Standard Material
1	Reinforced Through Shaft for Higher Torque Transmission #10
С	Chrome Plated Drive Shafts
D	Chrome Plated & Reinforced for Through Shaft #10
N	Nickel Plated Drive Shafts
М	Nickel Plated & Reinforced for Through Shaft #10
S	Stainless Steel Drive Shafts
Т	Stainless Steel & Reinforced for Through Shaft #10

18-Enviro	18-Environment & Temperature Rating #8	
0	Standard	
1	High Temperature	
2	Low Temperature	
N	Radiation Resistant	
М	Radiation Resistant & Low Temperature	
Р	Radiation Resistant & High Temperature	
R	Chemical Resistant	
S	Chemical Resistant & Low Temperature	
Т	Chemical Resistant & High Temperature	

19 - Character Space

20-Drive Shaft Keys - Side-1 (input)		Shaft Keys - Side-1 (input)
	0	Standard (Closed Keyway) - also select if motor adapter
	1	Open Keyway
	2	Keyless #4

22-Drive S	22-Drive Shaft Keys - Side-3	
0	Standard (Closed Keyway) - also select if hollow shaft #3	
1	Open Keyway #2	
2	Keyless #4	

21-Drive Shaft Keys - Side-2		Shaft Keys - Side-2
	0	Standard (Closed Keyway)
	1	Open Keyway #2
	2	Keyless #4

23-Drive Shaft Keys - Side-4	
0	Standard (Closed Keyway) - also select if hollow shaft #3
1	Open Keyway #2
2	Keyless #4

24 - Character Space

3 GROUP-3 - Accessories

25-Drive T	25-Drive Type	
0	Standard (normal shafts, no extra features)	
А	Motor Adapter, Input, B14	
В	Motor Adapter, Input, B5	
Н	Hand Wheel - Side 1 (Input)	
J	Hand Wheel - Side 2	
К	Hand Wheel - Side 3	
L	Hand Wheel - Side 4	

26-Motor Frame Size	
0	Not Applicable
A	63
В	71
С	80
D	90
E	100
F	112
G	132
Н	160
I	180
J	200

27-Drive Shaft Protective Cover		
0	None - Standard	
1	Cover- Side 1 (Input)	
2	Cover - Side 2	
3	Cover - Side 3	
4	Cover - Side 4	
Α	Cover - Side 2 & 3	
В	Cover - Side 2 & 4	
С	Cover - Side 3 & 4	
R	Rotation Indicator (Visual) - Side 1	
S	Rotation Indicator (Visual) - Side 2	
Т	Rotation Indicator (Visual) - Side 3	
U	Rotation Indicator (Visual) - Side 4	

28-Breath	er (Vent)					
0	None (Standard) #5					
1	Breather fitted Side-1 (Input)					
2	Breather fitted Side-2					
3	Breather fitted Side-3					
4	Breather fitted Side-4					
5	Breather fitted Side-5					
6	Breather fitted Side-6 #6					
А	Breather 90deg Type fitted Side-1 (Input)					
В	Breather 90deg Type fitted Side-2 #7					
С	Breather 90deg Type fitted Side-3					
D	Breather 90deg Type fitted Side-4					
Е	Breather 90deg Type fitted Side-5					
F	Breather 90deg Type fitted Side-6					

29-Lubr	29-Lubricant #9						
0	0 Standard Oil (input speed >250 rpm)						
1	Standard Grease (input speed < 250rpm)						
2	No Lubricant						
Α	Food Grade Oil						
В	Food Grade Grease						
С	Nuclear Grade Oil						
D	Nuclear Grade Grease						
Е	Biodegradable Oil						
F	Biodegradable Grease						

30-Paint	
0	Standard Paint (Red)
1	Standard Primer (Grey) Only
2	Standard Epoxy Paint (Red)
3	Subsea Paint (Yellow)
4	No Paint

Notes:

#1 Internal design revision number leave as XX and Power Jacks will update at time of order.

#2 Not applicable to hollow shaft gearboxes.

#3 Select if hollow shaft gearboxes with standard shaft designs on hollow shaft.

#4 Keyless shaft design, typically for servo couplings.

#5 Suitable for horizontal gearbox mounting, running within allowable speed limits for lubrication.

#6 Common side for breather on horizontally mounted gearbox (on side 5) with oil lubrication

#7 Common side for 90deg breather on 2-way or 3-way horizontally mounted gearbox (on side 5) with oil lubrication

#8 The environment and temperature range specified here dictates the seal type and temperature rating of the gearbox, hence temperature rating / type of lubricant as well.

#9 Type / Grade of lubricant defined by character 29 and 18

#10 The gearboxes "Through Shaft" is reinforced to transmit higher torque. It does not increase the torque transmitted through the gear set.

How to Select a Bevel Gearbox

When selecting a gearbox, there are a number of factors which can influence the final size of unit selected. The information contained in the selections gearbox characteristics and Technical data provide details of these factors for use in the selection process.

The following Selection Procedure provides a step-by-step guide to gearbox selection for those not fully familiar with the procedures. An example has been used in the selection procedure to assist in following through the procedure.

Specified information	Example Information
1. Gearbox Input Speed (rpm)	1000
2. Gearbox Output Speed (rpm)	500
3. Gearbox Configuration (page 213)	2 Way
4. Required Output Torque (Nm)	150
5. Operating Hours per Day (HRS)	10
6. Input Power Source (page 210)	Electric Motor
7. Gearbox Application (page 210)	Stacking Machine
8. Number of Starts per Hour (page 210)	8
9. Transmission Methods (page 210)	Clutch
10. Duty Cycle per Hour (% Running time)	45/60 = 75%
11 Operating Ambient Temperature °C (page 211)	20

Selection of Design Factors	Example Design Factors
Step 1 - Shock Load Factor (f,) Using the Specified Information in Points 5, 6 and 7 above, select the Shock Load Factor from the Page 210.	1.25
Step 2 - Starting Frequency Factor (f ₂) Using the Specified Information in Point 8 above, select the Starting Frequency Factor from the page 210.	1.00
Step 3 - Transmission Load Factor [f ₃] Using the Specified Information in Point 9 above, select the Transmission Load Factor from the Page 210.	1.00
Step 4 - Thermal Limit - Duty Cycle - Factor (f,) Using the Specified Information in Point 10 above, select the Thermal Limit - Duty Cycle - Factor from the Page 210.	1.25
Step 5 - Thermal Limit- Ambient Temperature - Factor [f _s] Using the Specified Information in Point 11 above, select the Thermal Limit - Ambient Temperature -Factor from the Page 211.	1.00



A gearbox is required for an Input Speed of 1000 rpm, an Output Speed of 500 rpm, an Output Torque of 150Nm and one Output Shaft. The Drive is by electric motor through a clutch mechanism and the gearbox is on the main drive of a heavy duty stacking machine. The machine operates for 10 hours per day, starts 8 times per hour and operates for 45 minutes in every hour, the other 15 minutes being taken up in loading the machine. The ambient temperature of the premises is 20°C.

Calculated data

Step 6 - Calculate the Gear Ratio Input Speed ÷ Output Speed

Note: If the gear ratio does not correspond to one of

the STANDARD ratios contained in this technical manual, one of the speeds, normally the output speed, must be changed to bring the ratio to standard. Non-standard ratios can be supplied, if required, but such special selections must be referred to Power Jacks.

Example Data

1000/500 = 2 Therefore 2:1 Reduction

Step 7 - Calculate the Corrected Output Torque Required Output Torque $x f_1 x f_2 x f_3$

Note: Where there is more than one output shaft, the Required Output Torque for the gearbox is the summation of the individual Output Torques from the output shafts.

150 x 1.25 x 1.00 x 1.00 x = 187.5 Nm

Step 8 - Calculate the Corrected Output Power Required Output Torque x Output Speed / 9550

Step 9 - Calculate the Required Input Power = Output Power /
Efficiency (Gearbox efficiency is between 95% and 98% after initial

9.82 / 0.98 = 10.02 kW

Calculate the gearbox,

 $(187.5 \times 500) / 9550 = 9.82 \text{ kW}$

Gearbox Selection

running in).

Example Gearbox Selection

Step 10 - From the GEARBOX TORQUE x POWER RATING TABLE (page 209), select the gearbox with the closest adequate rated power.

From the Selection Table on page 209, for Input Power 10.02 kW, gear ratio 2:1 and Input Speed 1000 rpm, select Series 39.

Step 11 - When selecting a gearbox, the Thermal Capacity of the gearbox chosen must be considered. For the Limiting Thermal Capacity (page 211), expressed as a Power Rating. For the selected gearbox, calculate the Thermal Capacity = Limiting Thermal Capacity x f_{α} x f_{α} .

From the table in page 211, Limiting Thermal Capacity for Series 39 is $49 \, \text{kW}.$

The Calculated Input Power must not exceed this Calculated Thermal Capacity. A larger gearbox must be selected if the Calculated Input Power is higher and a check run on the other parameters.

Thermal Capacity = $49 \times 1.25 \times 1.00 = 61.25 \text{ kW}$

The Input Power is within this limit. Selected gearbox is OK.

Step 12 - As a final check on the capacity of the chosen gearbox, the effect of the connected drive systems must be considered. The section headed Permissible Shaft Loading (page 212) describes the calculation to be undertaken where the transmission mechanism can give rise to radial and/or axial forces on the gear shafts. This occurs, particularly, where chain and belt drives are employed.

Power transmission is by clutch. From the Transmission Load Factor table (page 210 $[f_3]$), there are no additional loads to be considered and the selection of gearbox is acceptable.

Series		35	37	38	39	40	42 ^{#3}			
	Nominal ^{#1}	46	115	328	481	1353	6195			
Torque (Nm)	Max Running#2	93	187	505	935	3088	7000			
	Max Start-Up	140	281	758	1403	4632	10500			
Input Speed	Max (rpm)	3000	3000	3000	3000	3000	3000			
Thermal Limit	Power (kW)	3.3	9	20.5	49	90	190			
Backlash	arcmin	9 to 16	9 to 16	9 to 16	7 to 10	7 to 10	7 to 10			
Effici	Efficiency (%)		95% - 98%							
Service Life	(hours)	>10000	>10000	>10000	>10000	>10000	>10000			
Housin	g Material	SG Iron	SG Iron	SG Iron	SG Iron	SG Iron	SG Iron			
Oil Ougatitu	Litres	0.14	0.29	0.75	1.71	3.27	7			
Oil Quantity	Pints	0.24	0.5	1.32	3	5.75	12.3			
	2 Way - 1:1 & 1.5:1	5.25	11	21.75	53.25	125	190			
	2 Way - 2:1 +	5.5	11	22	54.5	125	215			
\\\-:= =+ ()	3 Way - 1:1 & 1.5:1	5.5	11.5	22	54.5	128	197			
Weight (kg)	3 Way - 2:1 +	6	11.5	22.5	55.75	128	223			
	4 Way - 1:1 & 1.5:1	6	13	25	64	150	204			
	4 Way - 2:1 +	7	14	27	69.5	153	231			

The above tables and other torque & power tables are on the basis of the following nominal values:

- 1 Shock-free operation
- 2 Operating time per day = 8 hours
- 3 Maximum 20 starts per hour (torque x 1.5 permissible)
- 4 Duty cycle 100%
- 5 When selecting gearboxes take the thermal capacity into consideration
- 6 Ambient temperature for operation -10° to +50°C permissible

Notes:

- #1 Nominal torque values at running speeds of 1500 rpm
- #2 Maximum running torque value at speed of 10 rpm
- #3 42-Series is Range-N design.

Lubrication

The oil levels stated in the table above assumes that the gearbox is positioned with all shafts in a horizontal plane. To get the correct lubrication recommendation please supply shaft orientation and operating speeds required as part of the application details provided to Power Jacks with an enquiry.

! All Range-C gearboxes are shipped without lubrication, except for grease filled units.

Input Speeds: 250 rpm < n < 1500 rpm

For input speeds up to 1500 rpm the oil level in the gearbox should be maintained just below the centre line of the shafts.

Input Speeds: n > 1500 rpm

For input speeds above 1500 rpm a change in oil level may be required in combination with a breather (vent). Consult Power Jacks for specific application advice.

Input Speeds: 250 rpm < n

For input speeds below 250 rpm then a grease filled gearbox is recommended.


Oil Specification

Ambient Temperature	Gear Oil
Below +5C	ISO 150
+5C to +40C	ISO 220
Above +40C	ISO 320

Grease Specification

Use an EP1 rated grease.

		Gear					ı	nput Speed	S				
Gear U	Init Size	Ratio	10	50	100	250	500	750	1000	1500	2000	2500	3000
		1:1	0.1	0.4	0.8	1.7	3.1	4.3	5.4	7.4	8.9	10.3	11.6
	Power	1.5:1	0.04	0.2	0.4	0.7	1.4	2.1	2.6	3.7	4.7	5.8	6.8
	(kW)	2:1	0.03	0.12	0.2	0.5	0.9	1.2	1.6	2.2	2.9	3.6	4.3
Series 35		3:1	0.01	0.03	0.06	0.15	0.31	0.5	0.6	0.9	1.2	1.4	1.7
Series 33	Output	1:1	93	74	74	63	58	53	50	46	41	38	36
	Torque	1.5:1	56	56	56	39	39	39	36	34	32	32	31
	M2 (Nm)	2:1	56	44	37	37	33	29	29	27	27	26	26
	IVIZ (INIII)	3:1	28	16	16	16	17	18	16	16	16	15	15
		1:1	0.2	1	2	4.3	7.7	10.8	13.6	18.5	22.6	26.3	30.6
	Power	1.5:1	0.1	0.5	0.8	1.9	3.5	5	6.4	9	11.5	14.3	17
	(kW)	2:1	0.1	0.3	0.6	1.3	2.5	3.5	4.5	6.4	8.1	10.1	12
	(KVV)	3:1	0.03	0.11	0.2	0.5	0.8	1.2	1.5	2.1	2.8	3.5	4.2
Series 37		4:1	0.01	0.06	0.1	0.2	0.4	0.6	0.8	1.2	1.5	1.9	2.3
30110307		1:1	187	187	187	160	144	134	127	115	105	98	95
	Output	1.5:1	140	140	112	106	98	93	89	84	80	80	79
	Torque	2:1	187	112	112	97	93	87	84	79	75	75	74
	M2 (Nm)	3:1	84	61	56	56	44	44	42	39	39	39	39
		4:1	37	44	37	29	29	29	29	29	28	28	28
		1:1	0.54	2.7	5.3	11.7	21.2	29.9	38	52.6	65.1	76.6	-
	Power	1.5:1	0.2	0.9	1.6	3.4	6.1	8.7	11.1	15.5	19.4	23.6	27.6
	(kW)	2:1	0.27	0.6	1.2	2.6	4.8	6.9	9	12.8	16.6	20.8	25
	(KVV)	3:1	0.1	0.3	0.5	1.2	2.2	3.1	4	5.7	7.5	9.4	11.1
Series 38		4:1	0.03	0.13	0.23	0.7	0.9	1.3	1.7	2.4	3.2	4	4.8
00000		1:1	505	505	495	437	396	373	355	328	304	286	-
	Output	1.5:1	280	252	224	190	171	162	155	145	136	132	129
	Torque	2:1	505	224	224	194	179	172	168	159	155	155	155
	M2 (Nm)	3:1	280	168	140	134	123	116	112	106	105	105	103
		4:1	112	97	86	104	67	64	63	59	59	59	59
		1:1	1	5	9.8	22.2	38.6	52	62.9	77.2	-	-	-
	Power	1.5:1	0.4	1.8	3.6	9	16.3	23.2	29.7	41.8	52.5	63.6	-
	(kW)	2:1	0.5	2	3.6	7.9	14.5	20.7	26.6	38	49.5	60.7	71.4
		3:1	0.2	0.8	1.4	3.2	5.9	8.4	10.9	15.6	20.5	25.1	29.4
Series 39		4:1	0.1	0.4	0.7	1.6	2.9	4.2	5.4	7.7	10.2	12.5	14.7
	0.11	1:1	935	935	917	831	722	648	588	481	-	-	-
	Output	1.5:1	505	505	505	505	457	434	416	391	368	357	-
	Torque	2:1	935	748	673	591	542	516	497	474	463	454	445
	M2 (Nm)	3:1	561	449	393	359	331	314	306	291	287	281	275
		4:1	374	299	262	239	217	209	202	192	190	187	183
		1:1	3.3	16.2	31.8	74.3	126	166	194	1/5	-	-	-
	Power	1.5:1 2:1	1.9	8.9 6.8	16.3 12.5	36.4 28	65.6 52	90.8 74.8	96.7	145 139	181	221.5	-
	(kW)	3:1	0.7	2.6	4.5	10.3	19.2	27.8	36.1	52	68.3	83.6	98.3
		4:1	0.7	1.5	2.8	7	11.7	16.9	21.9	31.6	42.1	51.5	60.5
Series 40		1:1	3088	3032	2975	2781	2358	2071	1815	-	- 42.1	-	-
	Output	1.5:1	2667	2498	2288	2043	1841	1699	1572	1356	_	-	-
	Torque	2:1	2807	2545	2339	2096	1946	1866	1809	1734	1693	1658	_
	M2 (N	3:1	1965	1459	1263	1156	1078	1040	1013	973	958	938	919
	m)	4:1	1497	1122	1048	1048	875	843	819	788	787	771	754
		1:1	7.5	37.4	74.8	187	374	558	-	-	-	-	-
		1.5:1	3.5	17.3	34.5	86.1	172	245	310	-	_	-	_
	Power	2:1	3.7	17.6	32.6	73.8	138	198	255	361	-	-	-
	(kW)	3:1	0.72	3.6	7.2	18	37.1	53.4	68.3	98.4	128.5	157.3	-
		4:1	1	3.7	6.7	14.9	28	40.6	52.8	76.3	97.7	119.7	140.8
Series 42		1:1	7000	7000	7000	7000	7000	6962	-	-	-	-	-
	Output	1.5:1	4913	4856	4842	4834	4828	4585	4351	-	-	-	-
	Torque	2:1	6925	6588	6101	5525	5165	4941	4772	4504	_	-	_
	M2 (N	3:1	2021	2021	2021	2021	2083	1998	1917	1841	1803	1766	-
	m)	4:1	3743	2770	2508	2231	2096	2026	1976	1904	1828	1972	1756



Check Thermal Limit - Torque

Power Ratings (kW) @ given INPUT speeds (rpm)
Output Torque M2 (Nm) @ given INPUT speeds (rpm)

Load Factors

Shock Load Factor (f,)

Shock Load Category							
1	II	III					
Conveyor Belts	Heavy Duty Lifts	Punching Machine					
Generators	Hoists	Shears					
Ventilators	Mixers	Forging Presses					
Light Textile Machinery	Cranes	Vibrators					
Rotating Machine Tools	Heavy Duty Textile Machinery	Rolling Mills					
	Woodworking Machinery	Extremely Heavy Lifts					
	Paper Machinery	Heavy Duty Roller Conveyors					

	Input Power Source									
Shock Load Category	Electric Motor			Piston Machine Hydro Motor			Single Cylinder Piston Machine			
	Operati	Operating Time per Day (hrs)			Operating Time per Day (hrs)			ng Time per D	lay (hrs)	
	≤2	10	>10	≤2	10	>10	≤2	10	>10	
I	0.9	1	1.25	1	1.25	1.5	1.25	1.5	1.75	
II	1	1.25	1.5	1.25	1.5	1.75	1.5	1.75	2	
III	1.5	1.5	1.75	1.75	2	2.25	2	2.25	2.5	

Starting Frequency Factor (f,)

up to 20 starts per hour $f_2 = 1.0$

up to 60 starts per hour $f_2 = 1.1$

up to 200 starts per hour $f_2 = 1.3$

up to 600 starts per hour $f_2 = 1.5$

more than 600 starts per hour (on request)

Transmission Load Factor (f₃)

The total load on the drive shafts and their bearing is the result of:

- a. The loads arising from the gear teeth
- b. The axial and radial loads arising from the transmission mechanisms attached to the drive shafts. It is this load which must be considered when selecting the gearbox and shaft sizes.

Depending upon the type of transmission mechanism used in connecting the gear shafts to the driving and driven loads, axial and / or radial loads can be applied to the gearbox shafts and their bearings.

These loads can arise from:

either preload, due for example, to tension loading in belts or dynamic forces, due for example, to out-of-balance in the transmission element or shock load, due for example, to snatching in a chain drive.

The following table gives the factors which should be used to correct the Output Torque when sizing the gearbox.

	Transmission Load Factor (f ₃)							
Transmission Mechanism	Preload	Dynamic						
Clutches	-	1						
Gears of all Types	-	1.00 to 1.25						
Chains	1.00 to 1.25	1.25 to 1.50						
Flat Belts	2.00 to 2.50	1.00 to 1.25						
V-Belts, Toothed Belts	1.50 to 2.00	1.00 to 1.25						

Due to the compact design of this range of spiral bevel gear units the ratings are controlled by the thermal capacity at some speeds. A maximum case temperature of 80°C is specified and temperatures in excess of this figure normally indicate either incorrect oil levels or too much power being handled by the unit. If this temperature is exceeded Power Jacks should be consulted.

Thermal Limit - Duty Cycle - Factor (f,)

Duty cycle per hour is the percentage of the time per hour during which the gearbox will be on-load.

Duty Cycle per Hour (%)	100	80	60	40	20
Thermal Limit Factor, f ₄	1	1.25	1.5	1.75	2

Thermal Limit - Ambient Temperature - Factor (f ,

Ambient Temperature °C	10	20	30	40	50
Thermal Limit Factor, f ₅	1.2	1	0.87	0.75	0.62

Limiting Thermal Capacity

The capacity of some gears is limited by the maximum permissible temperature of the oil bath. The charts below show the limiting thermal capacities, which can be transferred without cooling at an ambient temperature of 20°C and duty cycle of 100% per hour.

Series	35	37	38	39	40	42
Power (kW)	3.3	9	20.5	49	90	190

WARNING: The case temperature must not exceed 80°C, (see thermal limits).

Power Jacks should be consulted if a gear unit is to be installed with a shaft positioned vertically.

After selecting the gearbox for the required duty it is necessary to check that the axial and radial loading arising from the transmission mechanism is acceptable for the gear shaft diameters on the selected gearbox (gear shaft diameters are given on the Dimensions page for the chosen design).

The bearing configuration on the shafting, the shaft diameter and the shaft speed determine the permissible external loading which can be carried by the shaft without bearing or shaft failure. The graph showing permissible radial forces on shafts has been drawn for a typical Output Shaft. In this arrangement the bearing centres are mounted at either end of the through shaft and there is a significant span which allows higher radial loads to be accepted, see sketch below. For typical Input Shafts and Output Shafts, which are overhung from the gearbox face, the bearing centres are closer together and the radial load carrying capacity is reduced, see sketch below.

- 1. Read off the Permissible radial Force for the nearest diameter shafts from the graph below.
- 2. Use the Correction Factors, below, to calculate the Permissible Radial and Axial Loads for each of the gearbox shafts.


To calculate the Permissible Loading on the gearbox shafts, use the gearbox output and input speeds and diameters respectively.

Correction Factors

	Output Shaft (Bearings on through shaft)	Input Shaft (Bearings on overhung shaft)	Output Shaft (Bearings on overhung shaft)	Gearboxes with Centre bearing
Permissible Radial Forces	1.00	0.66	0.66	0.40
Permissible Axial Forces	0.50	0.50	0.50	0.50


The calculated loads should be checked against the radial and axial loads provided by the manufacturer of the transmission mechanism. If the loading created by the transmission mechanism exceeds the permissible level, a gearbox with a larger diameter shaft is required. At this point Power Jacks should be consulted as it is often possible to fit a special shaft arrangement into a standard gearbox.

Permissible Shaft Loading Curves




Example: Series 39, Ratio 2:1, 1440 rpm Input

Ød1	=	48	permissible radial force 7500 N x 0.66 = 4950 N permissible axial force 4950 N x 0.50 = 2475 N
Ød2	=	48	permissible radial force 9000 N x 1.00 = 9000 N permissible axial force 9000 N x 0.50 = 4500 N



Ratios 1:1 & 1.5:1


Ratios 2:1 & above



Ratio 1:1 & 1.5:1



Ratio 2:1 & Above



Hollow Shaft - All Ratios




Performance

Series 35				
	Nominal#1	46		
Torque (Nm)	Max Running#2	93		
	Max Start-Up	140		
Input Speed	Max (rpm)	3000		
Thermal Limit	Power (kW)	3.3		
Backlash	arcmin	9 to 16		
Efficiency	(%)	95% - 98%		
Service Life	(hours)	>10000		
Housing Material		SG Iron		
Oil Ougatitu	Litres	0.14		
Oil Quantity	Pints	0.24		
	2 Way - 1:1 & 1.5:1	5.25		
Weight (kg)	3 Way - 1:1 & 1.5:1	5.5		
	4 Way - 1:1 & 1.5:1	6		

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C350S20-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep



Notes:


High Temperature

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


Low Temperature

C350S30-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Solid Shaft

C350S40-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

	Series 35	
	Nominal#1	46
Torque (Nm)	Max Running#2	93
	Max Start-Up	140
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	3.3
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Ougatitu	Litres	0.14
Oil Quantity	Pints	0.24
	2 Way - 2:1 +	5.5
Weight (kg)	3 Way - 2:1 +	6
	4 Way - 2:1 +	7

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C350S20-20





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C350S30-20





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




Notebotes:

- 1. All. ditheiraicomasion animma measteathearthice existe tatated
- 2. D2m@irraiemsismsbjædbjæcthaangenvojehvoithootinetice


4 Way Solid Shaft

C350S40-20





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C35


Performance

	Series 35	
	Nominal#1	46
Torque (Nm)	Max Running#2	93
	Max Start-Up	140
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	3.3
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
0.1.0	Litres	0.14
Oil Quantity	Pints	0.24
	2 Way - 1:1 & 1.5:1	5.25
	2 Way - 2:1 +	5.5
AA (L.)	3 Way - 1:1 & 1.5:1	5.5
Weight (kg)	3 Way - 2:1 +	6
	4 Way - 1:1 & 1.5:1	6
	4 Way - 2:1 +	7

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

C350H20-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep



Notes:


High Temperature

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


3 Way Hollow Shaft

C350H30-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




Notebotes:

- 1. All. ditheiraismsion snimmardeusslesbeatwerevistatetated
- 2. D2m@irraiemsicsnusbjeactbjeccthaardyarvojehovithaatiaetice


4 Way Hollow Shaft

C350H40-10





Tapped hole in end of each solid drive shaft - M6 x 16mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

	Series 37	
	Nominal#1	115
Torque (Nm)	Max Running#2	187
	Max Start-Up	281
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	9
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Ouantitu	Litres	0.29
Oil Quantity	Pints	0.5
	2 Way - 1:1 & 1.5:1	11
Weight (kg)	3 Way - 1:1 & 1.5:1	11.5
	4 Way - 1:1 & 1.5:1	13

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C370S20-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C370S30-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep




Notebotes:

- 1. All. ditheiraismsion snimmardeusslesbeatwerevistatetated
- 2. D2m@irraiemsismsbjædbjæcthaangenvojehvoithootinetice


4 Way Solid Shaft

C370S40-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice




	Series 37	
	Nominal#1	115
Torque (Nm)	Max Running#2	187
	Max Start-Up	281
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	9
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Ouantitu	Litres	0.29
Oil Quantity	Pints	0.5
	2 Way - 2:1 +	11
Weight (kg)	3 Way - 2:1 +	11.5
	4 Way - 2:1 +	14

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C370S20-20





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C370S30-20





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Solid Shaft

C370S40-20





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

Series 37		
	Nominal#1	115
Torque (Nm)	Max Running#2	187
	Max Start-Up	281
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	9
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Ougatitu	Litres	0.29
Oil Quantity	Pints	0.5
	2 Way - 1:1 & 1.5:1	11
	2 Way - 2:1 +	11
Weight (kg)	3 Way - 1:1 & 1.5:1	11.5
	3 Way - 2:1 +	11.5
	4 Way - 1:1 & 1.5:1	13
	4 Way - 2:1 +	14

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

C370H20-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep



Notes:


High Temperature

- 1. Adddimensions in mm unless otherwise stated
- 2. Dialedinionssionssions in thomshanges without is set is that ed
 - 2. Dimensions subject to change without notice


3 Way Hollow Shaft

C370H30-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep



Notes:


Notes All dimensions in mm unless otherwise stated

- 1. All dimensions is unject the shart per without a tetle
- 2. Dimensions subject to change without notice


4 Way Hollow Shaft

C370H40-10





Tapped hole in end of each solid drive shaft - M8 x 25mm Deep



Notes dimensions in mm unless otherwise stated


- 2. Alimensia sia subject to charge with wise stated
- 2. Dimensions subject to change without notice

	Series 38	
	Nominal#1	328
Torque (Nm)	Max Running#2	505
	Max Start-Up	758
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	20.5
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Quantity	Litres	0.75
Oil Quantity	Pints	1.32
	2 Way - 1:1 & 1.5:1	21.75
Weight (kg)	3 Way - 1:1 & 1.5:1	22
	4 Way - 1:1 & 1.5:1	25

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C380S20-10





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep



Notes:


High Temperature

NoAelsdimensions in mm unless otherwise stated


- 2. Alimenaina a subject to what so with with a stated
- 2. Dimensions subject to change without notice

C380S30-10





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




NoAelsdimensions in mm unless otherwise stated

- 2. Almenaiana as bije at to a heavy oviction wise at itsed
- 2. Dimensions subject to change without notice


4 Way Solid Shaft

C380S40-10





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep



Notes:

NoAelsdimensions in mm unless otherwise stated

- 2. Almenaiasionshipent to whites governments estated
- 2. Dimensions subject to change without notice




	Series 38	
	Nominal#1	328
Torque (Nm)	Max Running#2	505
	Max Start-Up	758
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	20.5
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Quantity	Litres	0.75
Oil Quantity	Pints	1.32
	2 Way - 2:1 +	21
Weight (kg)	3 Way - 2:1 +	22.5
	4 Way - 2:1 +	27

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C380S20-20





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C380S30-20





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




Notebotes:

- 1. All. ditheiraismsion snimmardeusslesbeatwerevistatetated
- 2. D2m@irraiemsicsnusbjeactbjeccthaardyarvojehovithaatiaetice


4 Way Solid Shaft

C380S40-20





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

	Series 38	
	Nominal#1	328
Torque (Nm)	Max Running#2	505
	Max Start-Up	758
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	20.5
Backlash	arcmin	9 to 16
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
0:1.0	Litres	0.75
Oil Quantity	Pints	1.32
	2 Way - 1:1 & 1.5:1	21.75
	2 Way - 2:1 +	22
Weight (kg)	3 Way - 1:1 & 1.5:1	22
	3 Way - 2:1 +	22.5
	4 Way - 1:1 & 1.5:1	25
	4 Way - 2:1 +	27

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

C380H20-10





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep



Notes:


High Temperature

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


3 Way Hollow Shaft

C380H30-10





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Hollow Shaft

C380H40





Tapped hole in end of each solid drive shaft - M10 x 25mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

	Series 39	
	Nominal#1	481
Torque (Nm)	Max Running#2	935
	Max Start-Up	1403
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	49
Backlash	arcmin	7 to 10
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Quantity	Litres	1.71
Oil Quantity	Pints	3
	2 Way - 1:1 & 1.5:1	53.25
Weight (kg)	3 Way - 1:1 & 1.5:1	54.5
	4 Way - 1:1 & 1.5:1	64

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C390S20-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C390S30-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




NoteNotes:

- 1. All .dArth ethirsien siem snirm rombers a leth seorthiese vaiteet esthated
- 2. Dizn Dinsiensienbjeabjeat Handre najth with roution tice


4 Way Solid Shaft

C390S40-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

Ratio 2:1 & above


Performance

	Series 39	
	Nominal#1	481
Torque (Nm)	Max Running#2	935
	Max Start-Up	1403
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	49
Backlash	arcmin	7 to 10
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Ougatitu	Litres	1.71
Oil Quantity	Pints	3
	2 Way - 2:1 +	54.5
Weight (kg)	3 Way - 2:1 +	55.75
	4 Way - 2:1 +	69.5

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C390S20-20






Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C390S30-20





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Solid Shaft

C390S40-20





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C39


Performance

	Series 39	
	Nominal#1	481
Torque (Nm)	Max Running#2	935
	Max Start-Up	1403
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	49
Backlash	arcmin	7 to 10
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
011.0	Litres	1.71
Oil Quantity	Pints	3
	2 Way - 1:1 & 1.5:1	53.25
	2 Way - 2:1 +	54.5
AA (L.)	3 Way - 1:1 & 1.5:1	54.5
Weight (kg)	3 Way - 2:1 +	55.75
	4 Way - 1:1 & 1.5:1	64
	4 Way - 2:1 +	69.5

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

C390H20-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep



Notes:


High Temperature

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


3 Way Hollow Shaft

C390H30-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Hollow Shaft

C390H40-10





Tapped hole in end of each solid drive shaft - M12 x 30mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

	Series 40	
	Nominal#1	1353
Torque (Nm)	Max Running#2	3088
	Max Start-Up	4632
Input Speed	Max (rpm)	3000
Thermal Limit	Power (kW)	90
Backlash	arcmin	7 to 10
Efficiency	(%)	95% - 98%
Service Life	(hours)	>10000
Housing Material		SG Iron
Oil Oventity	Litres	3.27
Oil Quantity	Pints	5.75
	2 Way - 1:1 & 1.5:1	125
Weight (kg)	3 Way - 1:1 & 1.5:1	128
	4 Way - 1:1 & 1.5:1	150

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C400S20-10






Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C400S30-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notebotes:

- 1. All. ditheiraicomasion animma measteathearthice existe tatated
- 2. D2m@irraiemsicsnusbjeactbjeccthaardyarvojehovithaatiaetice


4 Way Solid Shaft

C400S40-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C40 POWERJACKS


Performance

Series 40			
	Nominal#1	1353	
Torque (Nm)	Max Running#2	3088	
	Max Start-Up	4632	
Input Speed	Max (rpm) 3000		
Thermal Limit	Power (kW)	90	
Backlash	arcmin	7 to 10	
Efficiency	(%)	95% - 98%	
Service Life	(hours)	>10000	
Housing Material		SG Iron	
Oil Quantity	Litres	3.27	
	Pints	5.75	
Weight (kg)	2 Way - 2:1 +	125	
	3 Way - 2:1 +	128	
	4 Way - 2:1 +	153	

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

C400S20-20






Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C400S30-20





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notelotes:

- 1. All. dith direiemsion snimm menslesse on twee existentated
- 2. D2m@irraiemsicsnusbjeactbjectbaaabarvojehwithoutinetice


4 Way Solid Shaft

C400S40-20





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

C40


Performance

Series 40			
Torque (Nm)	Nominal#1	1353	
	Max Running#2	3088	
	Max Start-Up	4632	
Input Speed	Max (rpm)	3000	
Thermal Limit	Power (kW)	90	
Backlash	arcmin	7 to 10	
Efficiency	(%)	95% - 98%	
Service Life	(hours)	>10000	
Housing Material		SG Iron	
Oil Quantity	Litres	3.27	
	Pints	5.75	
	2 Way - 1:1 & 1.5:1	125	
Weight (kg)	2 Way - 2:1 +	125	
	3 Way - 1:1 & 1.5:1	128	
	3 Way - 2:1 +	128	
	4 Way - 1:1 & 1.5:1	150	
	4 Way - 2:1 +	153	

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

C400H20-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


3 Way Hollow Shaft

C400H30-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notebotes:

- 1. All. ditheiraicomasion animma measteathearthice existe tatated
- 2. D2m@irraiemsicsnusbjeactbjeccthaardyarvojehovithaatiaetice


4 Way Hollow Shaft

C400H40-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep



Notetes:


- 1. AlAllichiemenisienenisnimmmanlabessetbetrevrisvesetateted
- 2. Di Diemenisian subjejet do to harregreg evit hithutut ortatiece

Series 42			
	Nominal#1	6195	
Torque (Nm)	Max Running#2	7000	
	Max Start-Up	10500	
Input Speed	Max (rpm)	3000	
Thermal Limit	Power (kW)	190	
Backlash	arcmin	7 to 10	
Efficiency	(%)	95% - 98%	
Service Life	(hours)	>10000	
Housing Material	SG Iron		
Oil Quantity	Litres	7	
	Pints	12.3	
Weight (kg)	2 Way - 1:1 & 1.5:1	190	
	3 Way - 1:1 & 1.5:1	197	
	4 Way - 1:1 & 1.5:1	204	

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Solid Shaft

N420S20-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notes:

High Temperature


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

N420S30-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notes:


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

4 Way Solid Shaft

N420S40-10



Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

Series 42			
	Nominal#1	6195	
Torque (Nm)	Max Running#2	7000	
	Max Start-Up	10500	
Input Speed	Max (rpm) 3000		
Thermal Limit	Power (kW)	190	
Backlash	arcmin	7 to 10	
Efficiency	(%)	95% - 98%	
Service Life	(hours)	>10000	
Housing Material		SG Iron	
Oil Quantity	Litres	7	
	Pints	12.3	
Weight (kg)	2 Way - 2:1 +	215	
	3 Way - 2:1 +	223	
	4 Way - 2:1 +	231	

Notes:


#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17

Accessories & Options




2 Way Solid Shaft






Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notes:


- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

4 Way Solid Shaft





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice

N42


Performance

Series 42			
Torque (Nm)	Nominal#1	6195	
	Max Running#2	7000	
	Max Start-Up	10500	
Input Speed	Max (rpm)	3000	
Thermal Limit	Power (kW)	190	
Backlash	arcmin	7 to 10	
Efficiency	(%)	95% - 98%	
Service Life	(hours)	>10000	
Housing Material		SG Iron	
Oil Quantity	Litres	7	
	Pints	12.3	
	2 Way - 1:1 & 1.5:1	190	
Weight (kg)	2 Way - 2:1 +	215	
	3 Way - 1:1 & 1.5:1	197	
	3 Way - 2:1 +	223	
	4 Way - 1:1 & 1.5:1	204	
	4 Way - 2:1 +	231	

Notes:

#1 Nominal torque values at running speeds of 1500 rpm #2 Maximum running torque value at speed of 10 rpm Full detailed performance for each unit refer to page 16 & 17


Accessories & Options




2 Way Hollow Shaft

N420H020-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


3 Way Hollow Shaft

N420H030-10





Tapped hole in end of each solid drive shaft - M16 x 38mm Deep




Notes:

- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice


4 Way Hollow Shaft

N420H040-10






Tapped hole in end of each solid drive shaft - M16 x 38mm Deep



- 1. All dimensions in mm unless otherwise stated
- 2. Dimensions subject to change without notice





Motor frame Size B5 Flange	Gear unit Series	Gear Ratio	Dimension 'A'	Gear Unit Prefix for Product Code
71	35	All	115	Α
80	35	All	115	В
90	37	All	130	С
100	37	1:1 & 1.5:1	130	D
100	37	2:1	140	D
112	37	1:1 & 1.5:1	130	D
112	37	2:1	140	D
112	38	All	190	D
132	38	All	190	E
132	39	All	220	E
160	38	1:1, 1.5:1 & 2:1	190	F
160	38	3:1 & 4:1	210	F
160	39	1:1, 1.5:1 & 2:1	220	F
160	39	3:1 & 4:1	240	F
180	39	1:1, 1.5:1 & 2:1	220	G
180	39	3:1 & 4:1	240	G
180	40	All	280	G
200	40	All	280	Н
225 : 2 Pole	40	All	280	J
225 : 4-8 Pole	40	All	310	К
250 : 2 Pole	40	All	310	L

- 1. All standard motor adapters use a B5 IEC flange.
- 2. All Flange dimensions conform to standard IEC electric motor details.
- 3. NEMA flanges available on request.

Extended Drive Shafts



For each gearbox size the drive shafts (input or output) can be extended in length for solid shaft or hollow shaft designs.

For an application these designs can:

- Eliminate the need for extra drives shafts.
- Reduce the number of couplings.
- Reduce the overall installation cost.
- Reduce the associated maintenance and spare parts inventory and cost.
- Allow the machine design to be fully optimised.

Stainless Steel Bevel Gearboxes



Stainless steel gearboxes are recommended for use in applications which require one or more of the following properties:

- High corrosion resistance.
- Hygienic for food processing.
- Good chemical resistance.
- Resistance to fire & high temperatures.
- Strength at low temperatures.
- Stainless steel has good recycling options.
- Easy to clean surfaces.
- Non-magnetic options available.

All of which makes stainless steel gearboxes ideally suitable for industries such as marine, paper, chemical, food, beverage, nuclear, oil and gas.

Subsea Gearbox

U-Series Underwater / Subsea Gearbox

The U-Series subsea bevel gearboxes are a proven and reliable technology for subsea drive solutions down to a depth of 3000m. They are used in a wide variety of underwater applications in the oil & gas and even the nuclear sector. Each submersible variant is tailored exactly to the customer application.





Subsea Design Features

- Proven depth ratings up to 3000m subsea (deeper on request)
- Pressure compensated or flooded designs available
- Full stainless steel designs available
- Reinforced sealing
- Full range of anti-corrosion options
- ROV drive interfaces
- Low (-65°C) to High (+250°C) temperature solutions available
- Vibration and shock load resistant designs
- Full range of feedback devices for speed, position and rotation
- Special custom designs available to meet your exact requirements

Standard Gearbox

- Six gearbox sizes
- 35, 37, 38, 39, 40, 42 Series
- Nine gearbox configurations
- Gear ratios: 1:1, 1.5:1, 2:1, 3:1, 4:1 as standard
- Special gear ratios available on request, e.g. 1.25:1
- Torque ratings up to 20000 Nm
- Option for reinforced shaft design for up to 300% higher torque transmission

Reliable Spiral Bevel Gear

With a proven design already used in millions of gearboxes, the Precision Spiral Bevel Gears, with accurate gear mesh, deliver high torque with smooth and quiet transmission.



Shaft Configurations

- 2, 3 or 4-way
- Solid or hollow shaft
- Special configurations available
- ROV torque receptacle integrated to gearbox drive
- ROV paddle adapter fitted to input drive shaft
- Motor adapter for direct connection of subsea motor to gearbox input
- Service life of 10,000 hours for all gearbox sizes
- Input speed up to 3,000 rpm maximum

Gearbox Housing

A rugged compact design made from a highly durable SG iron as standard or stainless steel on request.

It provides a strong housing that firmly and accurately holds the gear set in a reservoir of quality lubricant suited to the demands of subsea work.

Corrosion Protection





- To suit all economic needs
- Standard subsea paint finish
- Customer specified paint
- Plated finish
- Stainless steel

For more details request the U-Series brochure from Power Jacks or download a copy from www.powerjacks.com

Design Possibilities / Designed For You

The Range-N bevel gearboxes are provided as a range of standard bevel gearboxes and as a range of engineered gearboxes. Each gearbox design can be altered to suit exact application requirements such as:


- Low weight designs.
- Long or short drive shafts.
- Keyless shafts.
- Shafts with threaded sections.
- Alternative shaft profiles e.g. hexagonal.
- Nuclear rated gearboxes.
- Food & beverage processing grade gearboxes.
- Special shaft sealing.
- Integrated or bolt on base flange.
- Extra mounting holes.
- Motor adapters for servo, hydraulic or air motors.
- Integrated limit switches.
- Protective shaft covers.
- High & low temperature rated designs.
- Alternative housing designs e.g. curved.
- High corrosion & chemical resistant designs.

Use Power Jacks engineering technology to bring your concept to reality.



11

POWER JACKS OFFERS A WIDE RANGE OF REDUCTION GEARBOXES FOR SCREW JACK SYSTEM BUILDING



A-series - Right Angled Helical Bevel Gearbox



Size	Torque [Nm]
A 05	100
A 10	150
A 20	250
A 30	410
A 35	600
A 41	850
A 50	1500
A 55	2000
A 60	2800
A 70	5000
A 80	8000
A 90	14000

Torque Range

100 Nm to 14000 Nm

Power Rating

0.22 kW to 150 kW (at 1400 rpm input)

Gear Ratios

5.4:1 to 1715:1

Output

Foot and shaft mount - two bore options size Keyless shrink disc fitting Metric or Inch series solid output shaft Taper bushing Splined Hollow shaft to DIN 5480

Input

IEC and NEMA motor adaptors Servo motor adapters Metric or inch series solid input shaft

Main gear options

Backstop Reinforced bearings for higher overhung load capacity Reduced backlash Taconite seals

AC Motors

Integral motors and brake motors IEC motors and brake motors Single and dual speed motors

Main brake features

DC and AC supply
Fast brake engage/disengage through
electronically controlled AC/DC rectifiers.

Main motor options

C-series - In-Line Helical Gearbox



Size	Torque [Nm]
C 05	45
C 12	100
C 22	200
C 32	300
C 36	450
C 41	600
C 51	1000
C 61	1600
C 70	2300
C 80	4000
C 90	7200
C 100	12000

Torque Range

45 Nm to 12000 Nm

Power Rating

0.08 kW to 213 kW (at 1400 rpm input)

Gear Ratios

2.6:1 to 1481:1

Output

Foot and Flange mount Metric or inch series solid output shaft

Input

IEC and NEMA motor adaptors Servo motor adapters Metric or inch series solid input shaft

AC Motors

Integral motors and brake motors IEC motors and brake motors Single and dual speed motors

Main brake features

DC and AC supply Fast brake engage/disengage through electronically controlled AC/DC rectifiers.

Main motor options

F-series - Parallel Shaft Helical Gearbox



Size	Torque [Nm]
F 10	140
F 20	250
F 25	400
F 31	600
F 41	1100
F 51	1800
F 60	2900
F 70	5000
F 80	8000
F 90	14000

Torque Range

140 Nm to 14000 Nm

Power Rating

0.17 kW to 125 kW (at 1400 rpm input)

Gear Ratios

6.4:1 to 2099:1

Output

Keyed hollow shaft - two bore options per size Keyless shrink disc fitting Plug-in solid output shaft as an option

Input

IEC and NEMA motor adaptors Servo motor adapters Metric or inch series solid input shaft

AC Motors

Integral motors and brake motors IEC motors and brake motors Single and dual speed motors

Main brake features

DC and AC supply Fast brake engage/disengage through electronically controlled AC/DC rectifiers.

Main motor options

VF & W - Series - Worm Gearbox



Size	Torque [Nm]	
VF 27	13	
VF 30	24	
VF 44	55	
VF 49	88	
VF 63	190	
VF 75	320	
VF 86	440	
VF 110	830	
VF 130	1500	
VF 150	2000	
VF 185		3600
VF 210		5000
VF 250		7100

Torque Range

13 Nm to 71000 Nm

Power Rating

0.04 kW to 75 kW (at 1400 rpm input)

Gear Ratios

7:1 to 10000:1

Output

Keyed hollow shaft Plug-in solid output shaft Torque limiter as an option

Input

IEC motor adaptors Solid input shaft

AC Motors

Integral motors and brake motors IEC motors and brake motors Single and dual speed motors


Main brake features

DC and AC supply Fast brake engage/disengage through electronically controlled AC/DC rectifiers.

Main motor options

11

POWER JACKS CAN SUPPLY ELECTRIC MOTORS FOR ALL APPLICATIONS WHETHER AC OR DC MOTORS ARE REQUIRED.



POWERJACKS

Power Jacks can supply electric motors for all applications whether AC or DC motors are required. Detailed in this section of the Design Guide are some of the most popular motors used in industrial applications.

Ac Induction Motors

Standard Specification

- 3 Phase, 50 Hz / 60Hz.
- · Voltages:

IEC Frame 56 - 132

230 / 400 V - Δ / Y - 50 Hz (standard)

 $400 / 690 \text{ V} - \Delta / \text{ Y} - 50 \text{ Hz (on request)}$

460 V - Y - 60 Hz (standard)

IEC Frame 160 - 200

 $400 / 690 V - \Delta / Y - 50 Hz$ (standard)

460 V - Δ - 60 Hz (standard

- B3 Foot, B5 Flange and B14 Face Mounting. (or a combination).
- 2 Pole (3000 rpm)
- 4 Pole (1500 rpm)
- 6 Pole (1000 rpm)
- 8 Pole (750 rpm)
- IEC Frame Sizes 63 to 200.
- Enclosure IP55, TEFV.
- S1 Continuous rating.

Features

- Standard Efficiency of IE1. Other efficiency ratings of IE2, IE3 and IE4 are available on request.
- Low noise levels.
- High power factors.
- High torque with smooth acceleration and low current.
- Aluminium construction for light weight and corrosion resistance.

Optional

- Brake motors AC or DC units.
- 2 and 8 Pole 3 phase AC motors.
- Single phase AC motors.
- DC motors permanent magnet or servo.
- Cast Iron or Steel construction motors.
- High altitude and high temperature options.
- Integral AC inverter.
- Integral Incremental or Absolute encoder.
- Forced ventilation.
- Enclosures IP56 to IP68.
- Tropicalised motors.
- NEMA and Japanese standard units.
- Marine motors.
- Explosion proof motors, including ATEX motors.
- Anti-Condensation Heaters
- Thermistors
- H-Class Insulation
- Brake hand release
- Plug-in connectors
- · Second output shaft.

Brake Motor

The brake units are a single disc type mounted on the non-drive end-shield of the motor and can be either DC or AC types. They are spring applied electrically released units, which provide fail to safe operating characteristics such that on interruption, or failure of power supply, the brake will engage and arrest the load.

With DC brakes, the brake coil is fed via a rectifier in the motor terminal box and is automatically switched with the AC motor supply. AC brakes are connected directly to the motor terminals. They can however be separately energised form their own AC supply, in the case of inverter drives and/or where very fast brake operation is required.

The enclosure ratings for brake motors are IP54 as standard and IP55 on request. More enclosure ratings are available on request e.g. IP56.

Symbols	Units of Measure	Description
cosф	-	Power Factor
η	-	Efficiency
f _m	-	Power adjusting factor
I	-	Cyclic duration factor
I _N	(A)	Rated current
Is	(A)	Locked rotor current
Jc	(Kgm²)	Load moment of inertia
J _M	(Kgm²)	Moment of inertia
K _c	-	Torque factor
K _d	-	Load factor
K,	-	Inertia factor
M _A	(Nm)	Mean breakaway torque
M _B	(Nm)	Brake torque
M _N	(Nm)	Rated torque
M_L	(Nm)	Counter-torque during acceleration
M _s	(Nm)	Starting torque

Symbols	Units of Measure	Description
n	(min ⁻¹)	Rated Speed
P _B	(W)	Power drawn by the brake at 20°C
P _N	(kW)	Motor rated power
P _r	(kW)	Required power
t ₁	(ms)	Brake response time with one-way rectifier
t _{1S}	(ms)	Brake response time with electronic- controlled rectifier
t ₂	(ms)	Brake reaction time with a.c. disconnect
t _{2C}	(ms)	Brake reaction time with a.c. disconnect
t _a	°C	Ambient temperature
t _f	(min)	Work time constant load
t _r	(min)	Rest Time
W	(1)	Braking work between service interval
W _{MAX}	(J)	Maximum brake work for each braking
Z	(1/h)	Permissible starting frequency, loaded
Z ₀	(1/h)	Max. permissible unloaded starting frequency (I=50%)

Motor Rating - 2 Pole Motors (3000 rpm)

			1М Кg	2.0	5.4	9.9	7.8	9.8	9.7	12.4	13.3	15.1		16.4	18.1	20.7		27	30	40		46	26	29					
20 Hz			J, x 10-4 kgm²	2.6	3.0	3.9	4.6	5.3	6.1	9.4	10.6	13.0 1		\dashv	18.3	21 2		35	43	99	Н	112	154	189					
2(ķe			H		H	_		\dashv				-	+		4		_	_		Н	-	\dashv						
	a.c. brake	¥	Z° 1/h	4800	4800	4500	 4200	4200	3600	3200	3000	2600		2200	2200	2200		1600	1000	950		009	550	430					
			MB	1.75	1.75	3.5	 3.5	2	2	2	10	15	,	15	15	26		26	40	07		20	20	75					
			Туре	FA-02	FA-02	FA-02	FA-03	FA-03	FA-03	FA-04	FA-04	FA-04	i	FA-14	FA-14	FA-05		FA-15	FA-15	FA-06S		FA-06	FA-06	FA-06					
			1M B5	5.2	5.6	8.9	8.1	8.9	10.0	12.5	13.4	15.2	,	16.5	18.2	20		26	29	39		48	55	99					
			J_x 10⁴ kgm²	2.6	3.0	3.9	4.6	5.3	6.1	9.4	13.4	15.2	,	14.1	18.3	21		35	43	99		112	154	189					
	ke		/h SB	7800	4800	4500	4100	4200	3300	3200	3000	2600		2200	2200	2200		1600	006	950		009	550	430					
	d.c. brake	윤	Z _o 1/h	3900	3900	3600	3000	2900	1900	1700	1500	1300		006	006	900		700	450		Н		-						
			M M B	1.75	_	3.5	3.5	2	2	22	10	15		15	15	26		26	40	07		20	20	75					
			Туре	FD-02	FD-02	FD-02	FD-03	FD-03	FD-03	FD-04	FD-04	FD-04	;	FD-14	FD-14	FD-05		FD-15	FD-15	FD-06S		FD-06	FD-06	FD-56					
			1M Rg	3.5	3.9	5.1	5.4	6.2	7.3	9.8	9.5	11.3	-	_	14	14	,	20	23	28 F	Н	35	\dashv	53	92	84	67	109	140
			J, x 10-⁴ kgm²	2.0	2.3	3.3	3.5	4.1	5.0	7.8	0.6	11.4	H	\dashv	16.7	16.7		31	39	57		101	145	178	210	340	420	490	770
			M _n Ma	2.0	2.3	2.6	2.6	2.8	2.8	5.6	2.8	2.8	-	+	2.6	2.7	,	5.6	2.5	2.9		2.2	2.2	2.3	2.5	2.3	2.3	2.4	2.9
			M n	2.1	2.3	2.6	2.8	2.9	3.1	2.6	2.8	2.7		2.7	2.9	2.9		2.6	2.7	3.0		5.6	2.6	2.8	2.9	2.6	2.7	2.6	2.7
			<u>र</u> ु । <u>ए</u>	3.0	3.3	3.9	4.8	5.0	5.1	4.8	4.8	6.4	(5.9	6.2	6.3		9.6	5.8	6.9		5.9	6.4	6.7	6.9	7.1	7.6	7.8	7.8
S1			In 400V A	0.56	0.72	0.99	0.95	1.37	1.86	1.75	2.57	3.4		3.4	4.0	4.8		6.7	6.7	8.2		11.2	14.7	17.7	20.6	28.1	34	40	54
min ⁻¹ - S1			софр	0.77	0.76	0.78	0.76	0.76	0.76	0.81	0.81	0.81		0.80	0.80	0.80		0.79	0.80	0.82		0.84	0.85	0.86	0.88	86.0	86.0	0.88	0.89
3000 г			% (%0 <u>\$)</u> ህ	51.9	8.49	8.99	70.6	74.8	76.2	68.3	75.0	77.2		78.1	75.4	80.8		77.4	77.8	83.0		81.2	84.4	83.6	0.48	88.0	0.68	89.5	87.6
			ղ (75%) %	56.9	8.49	8.99	73.0	75.8	76.2	75.5	76.2	79.5		81.5	82.0	82.1		81.3	83.0	84.5		84.5	86.3	86.5	87.0	89.4	90.1	89.7	90.1
			ղ (100%) %	59.9	0.99	69.1	73.8	76.0	76.6	76.2	76.4	79.1		82.0	82.5	82.7		81.5	83.1	85.5		84.7	86.5	87.0	97.6	9.68	90.4	89.9	7.06
			E	A/N	A/N	A/N	A/N	N/A	A/N	>	>	>	-	>	>	>		>	>	>		>	>	>	>	>	>	>	>
			Σ°E	0.63	0.87	1.26	1.25	1.86	2.6	2.6	3.8	5.1		2.0	6.1	7.3		10.0	13.3	13.2		18.2	25	30	36	67	09	72	86
			n min ⁻¹	2730	_	2800	2820	2820	2810	2810	2800	2800	 -	-	\rightarrow	2880		2860	2870	2900		2890	2900	2930	2920	2930	2930	2930	2930
				2	2	2	2	2	2	2	2	2		2	2	2		2	3 2	2		۷ 2	3 2	2	R 2	В 2	2	2	1 2
2P				BN 63A	BN 63B	BN 63C	BN 71A	BN 71B	BN 71C	BN 80A	BN 80B	BN S0C		BN 90SA	BN 90SB	BN 90L		BN 100L	BN 100LB	BN 112M		BN 1325A	BN 1325B	BN 132M	BN 160MR	BN 160MB	BN 160L	BN 180M	BN 200LA
			۳. X	0.18	0.25	0.37	0.37	0.55	0.75	0.75	1.1	1.5		-	1.85	2.2		က	7	7		5.5	7.5	9.2	11	15	18.5	22	30


Motor Rating - 4 Pole Motors (1500 rpm)

							_							_	_	_	~		g								~				
A.			B5 Kg				5.0	5.4	9.9	7.5	8.3	9.7	12.0	13.7	15.1		16.3	20.3	21.8	25	29	42	28	71	77	88	128		144		
50Hz			J_X 10-4 kgm²				2.6	3.0	3.9	6.9	8.0	10.2	16.6	22	27		23	32	34	77	28	107	223	280	342	382	710		820		
	a.c. brake	FA	Z, 1/h				13000	13000	10000	11000	9400	8700	8000	7800	5300		8000	0009	2900	4700	4400	2100	1200	1000	006	820	750		700		
	rö		M M E				1.75	3.5	3.5	3.5	5.0	7.5	10	15	15		15	26	26	40	07	09	75	100	150	150	200	Ш	250		
			Туре				FD-02	FD-02	FD-02	FD-03	FD-03	FD-03	FD-04	FD-04	FD-04		FD-14	FD-05	FD-05	FD-15	FD-15	FD-06S	FD-06	FD-07	FD-07	FD-07	FD-08		FD-08		
			11M B5				5.2	5.6	8.9	7.8	9.8	10.0	12.1	13.8	15.2		16.4	19.6	21.1	25	28	40	57	99	75	98	129		145	175	197
			J, x 10-4 kgm²				2.6	3.0	3.9	6.9	8.0	10.2	16.6	22	27		23	32	34	77	28	107	223	280	342	382	725		865	1450	1850
	ke		n as				13000	13000	10000	11000	9400	8700	8000	7800	5300		8000	0009	2900	4700	4400	1400	1050	950	006	800	750		700	400	300
	d.c. brake	윤	Z _o 1/h				10000	10000	7800	7700	0009	4300	4100	4100	2600		4800	3400	3200	2600	2400	-		1		-	1		-	-	
			A K				1.75	3.5	3.5	3.5	2	7.5	10	15	15		15	26	26	40	07	09	75	100	150	150	200		250	300	400
			Туре				FD-02	FD-02	FD-02	FD-03	FD-03	FD-53	FD-04	FD-04	FD-04		FD-14	FD-05	FD-05	FD-15	FD-15	FD-04S	FD-56	FD-06	FD-07	FD-07	FD-08		FD-08	FD-09	FD-09
			Kg B5	3.1	3.1		3.5	3.9	5.1	5.1	5.9	7.3	8.2	6.6	11.3		12.2	13.6	15.1		22	30	777	53	26	70	66		115	135	157
			J _m x 10-4 kgm²	1.5	1.5	Ì	2.0	2.3	3.3	5.8	6.9	9.1	15	20	25	İ	21	28	30	07	24	86	213	270	319	360	920		790	1250	1650
			. M a ' π	2.0	2.4		1.8	2.0	1.9	1.7	1.9	2.3	2.0	2.5	2.5		2.2	2.4	2.6	2.0	2.2	2.5	2.2	2.4	2.5	2.5	2.1		2.5	2.5	2.8
			M. M.	2.3	2.5		1.9	2.2	2.1	1.9	2.0	2.3	2.3	2.7	2.8		2.6	2.8	2.8	2.2	2.3	2.7	2.3	2.5	2.7	2.7	2.3		2.6	2.5	2.7
			<u>s</u> । ⊏	2.6	2.6		2.6	2.6	2.7	3.3	3.7	4.1	4.1	6.4	5.1		4.6	5.3	5.1	4.5	2.0	5.6	5.5	5.7	5.9	6.0	6.0		6.2	6.4	7.1
7.0			In 400V A	0.28	0.42		0.47	0.71	0.80	0.78	1.05	1.55	1.43	1.85	2.7		2.70	3.6	4.3	5.2	8.9	8.4	11.6	15.5	18.8	22.4	30	Ш	37	77	59
1500 min ⁻¹ - S1			софр	0.65	09:0		0.62	0.67	0.69	0.73	92.0	0.74	0.77	0.78	0.78		0.77	0.77	0.79	0.75	0.77	0.81	0.81	0.81	0.81	0.81	0.81		0.81	0.80	0.80
1500 r			ر <mark>(50%)</mark> (<mark>50%)</mark>	41.3	42.9		47.0	52.5	57.9	59.1	63.0	8.89	69.7	69.3	70.4		72.2	74.9	77.2	79.9	83.7	81.6	82.5	85.3	87.5	86.0	88.4	Ш	89.2	0.06	91.0
			ր (75%) %	44.2	47.6		56.2	52.9	65.0	62.2	66.7	68.9	71.3	74.5	76.2		76.2	78.5	78.9	81.4	83.8	84.2	84.8	86.3	9.88	87.8	88.5		89.5	90.0	91.7
			ր (100%) %	8.97	51.7		59.8	54.8	65.3	63.7	8.99	0.69	72.0	75.0	75.5		76.5	78.7	78.6	81.1	82.6	84.4	84.7	86.0	88.4	87.6	88.7		89.3	89.9	91.4
			Ē	N/A	N/A	Ì	N/A	N/A	N/A	N/A	A/N	N/A	N/A	>	>	Ì	>	>	>	>	>	>	>	>	>	>	>		>	>	>
			Σ° E	0.43	0.64	İ	0.85	1.30	1.78	1.73	2.6	3.8	3.8	5.1	7.5	ļ	7.6	10.2	12.7	14.9	20	27	36	20	19	73	86		121	144	196
			n min-1	1340	1350		1350	1320	1340	1380	1370	1380	1390	1400	1400		1390	1410	1390	1410	1410	1430	1440	1440	1440	1440	1460		1460	1460	1460
				7	7		4	7	7	7	7	7	7	7	7		4	4	7	7	7	4	4	7	7	4	4		4	7	7
4b				BN 56A	BN 568		BN 63A	BN 638	BN 63C	BN 71A	BN 71B	BN 71C	BN 80A	BN 80B	BN 80C		BN 90S	BN 90LA	BN 90LB	BN 100LA	BN 100LB	BN 112M	BN 132S	BN 132MA	BN 132MB	BN 160MR	BN 160L		BN 180M	BN 180L	BN 200L
			۳. ۲	0.06 E	0.09 E		0.12 E	0.18 E	0.25 E	0.25 E	0.37 E	0.55 E	0.55 E	0.75 E	1.1 E		1.1 E	1.5 E	1.85 E	2.2 E	е	4	5.5 E	7.5 E	9.2 E	11	15 E		18.5 E	22 E	30 E


Motor Rating - 6 Pole Motors (1000 rpm)

			F 10 (B	<u> </u>	\d	6	_	-	7	-	0		7					\neg	_			е е	е С			
N			11M B5	6.1	6.4	7.9	9.1	10.1	13.7	15.1	16.0		16.7	22	29	31	77	ŀ		63	74	113	133			_
50 Hz			J _{,,} x 10 ⁻⁴ kgm²	4.0	4.3	9.5	12	14	23	27	30		28	37	98	66	177		226	318	709	815	1045			
	a.c. brake	FA	Z _o 1/h	14000	14000	13500	13000	9500	8200	7200	9400		9200	7800	4100	3600	2100		1400	1200	1050	006	800			
	rö		M W W	3.5	3.5	5.0	5.0	7.5	10	15	15		15	26	40	40	09		75	100	150	170	200			
			Туре	FD-02	FD-02	FD-03	FD-03	FD-03	FD-04	FD-04	FD-04		FD-14	FD-01	FD-15	FD-15	FD-08S		FD-06	FD-07	FD-07	FD-08	FD-08			
			1M B5	6.3	9.9	8.2	7.6	10.4	13.8	15.2	16.1		16.8	21	28	30	42		67	28	72	112	133	170		185
			J _n x 10-4 kgm²	4.0	4.3	9.5	12	14	23	27	30		28	37	98	66	177		226	305	905	815	1045	1750	-	1900
	ıke		e e	14000	14000	13500	13000	9500	8500	7200	9700		9200	2000	4100	3600	2100		1400	1200	1050	006	800	009	_	450
	d.c. brake	윤	Z _o 1/h	0006	0006	8100	7800	5100	5200	4800	3400		3400	2700	1900	1700					,	,	,	,	-	-
			MB EN	3.5	3.5	5	2	7.5	10	15	15		15	26	40	40	09		75	100	150	170	200	300		400
			Туре	FD-02	FD-02	FD-03	FD-03	FD-53	FD-04	FD-04	FD-04		FD-14	FD-05	FD-15	FD-15	FD-06S		FD-56	FD-08	FD-07	FD-08	FD-08	FD-09		FD-09
			1M B5	9.4	6.4	5.5	6.7	7.7	6.6	11.3	12.2		12.6	15	22	24	32		36	45	26	83	103	130	-	145
			J _{,,} x 10-4 kgm²	3.4	3.7	8.4	10.9	12.9	21	25	28		26	33	82	95	168		216	295	383	740	970	1550		1700
			Ma	1.8	1.7	1.7	1.7	2.0	2.0	2.2	2.2		2.2	2.0	2.0	2.0	2.0		1.8	1.8	1.9	2.0	2.3	2.4		2.3
			Mn	2.1	1.9	1.9	1.9	2.4	2.2	26	2.5		2.4	2.3	2.1	2.1	2.2		1.9	2.0	2.1	2.2	2.5	2.0		2.0
			s - c	2.1	2.1	2.6	2.6	3.0	3.2	3.9	3.8		3.8	3.9	4.1	4.6	4.8		5.1	5.5	6.1	5.9	9.9	6.2		5.9
51			ln V002	09.0	0.64	0.68	0.82	1.17	1.15	1.67	2.38		2.27		4.0	8.4	5.5		7.1	9.2	12.2	15.7	22.7	30		37
nin-1 - S1			сοφα	0.53	0.53	69.0	17.0	69.0	89'0	89.0	99.0		89.0	69.0	0.72	0.73	0.81		92.0	0.77	0.78	0.81	0.81	0.82		0.81
1000 m			% (%0 5) Ն	32.9	41.8	51.0	51.4	53.3	63.3	64.3	7.79		64.2	69.1	70.3	62.6	76.5		75.1	79.5	79.1	84.8	85.9	87.3		87.3
			ր (75%) %	41.0	0.44	55.5	58.5	0.09	4.74	8.69	70.0		0.69	72.6	74.2	72.8	79.0		77.0	81.5	80.9	85.0	86.5	88.0		88.0
			ր (100%) %	41.0	45.0	55.0	62.0	0.99	0.89	70.0	70.0		70.0	72.9	75.2	76.6	78.5		79.7	81.4	83.1	85.0	86.4	87.7		9.88
			131	N/A	N/A	N/A	N/A	N/A	N/A	N/A	>		>	>	>	>	>		>	>	>	>	>	>		>
			Σ E	0.98	1.32	1.91	2.70	3.9	3.9	5.7	7.8		7.8	11.4	15.2	19.0	22		30	40	26	75	109	148		184
			n min ⁻¹	880	870	006	006	910	910	920	920		920	920	940	930	940		940	950	945	955	096	970		096
				9	9	9	9	9	9	9	9		9	9	9	9	9		9	9	9	9	9	9		9
49				BN 63A	BN 63B	BN 71A	BN 71B	BN 71C	BN 80A	BN 80B	BN 80C		BN 90S	BN 80B	BN 100LA	BN 100LB	BN 112M		BN 1325	BN 132MA	BN 132MB	BN 160M	BN 160L	BN 180L		BN 200LA
			σ. ¥	0.09	0.12	0.18	0.25	0.37	0.37	0.55	0.75	}	0.75	1.1	1.5	1.85	2.2	ŀ	က	4	5.5	11	15	18.5		30

Motor Rating - 8 Pole Motors (750 rpm)



Motor Dimensions - Standard - B3 Foot Mount




FRAME			SHAFT					нои	SING							М0	TOR				
SIZE	D DA	E EA	DB	GA GC	F FA	В	A	НА	ВВ	АВ	К	С	нс	AC	L	LB	LC	AD	AF	LL	V
BN 63	11	23	M4	12	4	80	100	8	96	120	7	40	63	121	207	184	232	95			30
BN 71	14	30	M5	16	5	90	112	8	112	135	,	45	71	138	249	219	281	108	74	80	37
BN 80	19	40	M6	21.5	6	100	125	8	124	153		50	80	156	273	233	315	119			38
BN 90S	0,4	F0		0.7		100	1/0	0	455	45/	10	F./	00	487	00/	05/	050	100			,,
BN 90L	24	50	М8	27	8	125	140	8	155	174		56	90	176	326	276	378	133			44
BN 100							160			192		63	100	195	366	306	429	142	98	98	50
BN 112	28	60	M10	31	8	140	190	10	175	224	40	70	112	219	385	325	448	157			52
BN 132S			1440		40		04.4	40	040	05/	12		400	0.40		/10		400	440	440	
BN 132M	38	80	M12	41	10	178	216	12	218	254		89	132	260	493	413	576	193	118	118	58
BN 160M	42	110	M16	45	12	210	05/	0.5	264	040	47.5	100	1/0	040	596	486	680	0/5			5.4
BN 160L	38 (1)	80 (1)	M12 (1)	41 (1)	10 (1)	254	254	25	304	319	14.5	108	160	310	640	530	724	245	105	105	51
BN 180L	48 42 (1)	110	M16 M16 (1)	51.5 45 (1)	14 12 (1)	279	279	2/	329	359	14	121	180	2/0	708	598	823	2/1	187	187	52
BN 200L	55 42 (1)	110 (1)	M20 M16 (1)	59 45 (1)	16 12 (1)	305	318	26	355	398	18	133	200	348	722	612	837	261			64

Note

1. These values refer to the rear shaft end.

Motor Dimensions - Standard - B5 Flange Mount




FRAME			SHAFT					FLA	NGE						MO [°]	TOR			
SIZE	D DA	E EA	DB	GA GC	F FA	М	N	Р	s	т	LA	AC	L	LB	LC	AD	AF	LL	٧
BN 56	9	20	М3	10.2	3	100	80	120	7	3	8	110	185	165	207	91			34
BN 63	11	23	M4	12.5	4	115	95	140	0.5	3	40	121	207	184	232	95	, .		26
BN 71	14	30	M5	16	5	130	110	160	9.5		10	138	249	219	281	108	74	80	37
BN 80	19	40	M6	21.5	6	165	130	200	11.5	3.5	11.5	156	274	234	315	119			38
BN 90	24	50	М8	27		165	130	200	11.5		11.5	176	326	276	378	133			44
BN 100			1440	0.1	8	405	100	050			14	63	367	307	429	142	98	98	50
BN 112	28	60	M10	31		125	180	250	14	4	15	219	385	325	448	157			52
BN 132	38	80	M12	41	10	265	230	300			20	050	493	413	576	400	440	440	58
BN 160 MR												258	562	452	645	193	118	118	218
BN 160 M	42 38 (1)	110 80 (1)	M16 M12 (1)	45 41 (1)	12 10 (1)						45		F0.						
BN 160 L						300	250	350	40.5	_	15	310	596	486	680	245			51
BN 180 M	48 38 (1)		M16 M12 (1)	51.5 41 (1)	14 10 (1)				18.5	5		310	640	530	724		187	187	
BN 180 L	48 42 (1)	110 110 (1)	M16 M16 (1)	51.5 45 (1)	14 12 (1)						40	0.40	708	598	823	0/4			52
BN 200 L	55 42 (1)		M20 M16 (1)	59 45 (1)	16 12 (1)	350	300	400			18	348	722	612	837	261			66

Note

1. These values refer to the rear shaft end.


Electric Motors

Motor Dimensions - Standard - B14 Face Mount



FRAME			SHAFT				F	LANG	E					М0	TOR			
SIZE	D DA	E EA	DB	GA GC	F FA	М	N	Р	s	Т	AC	L	LB	LC	AD	AF	LL	٧
BN 56	9	20	М3	10.2	3	65	50	80	МЕ		110	185	165	207	91			34
BN 63	11	23	M4	12.5	4	75	60	90	M5	2.5	121	207	184	232	95			26
BN 71	14	30	M5	16	5	85	70	105			138	249	219	281	108	74	80	37
BN 80	19	40	M6	21.5	6	100	105	120	M6		156	274	234	315	119			38
BN 90	24	50	M8	27		115	120	140		3	176	326	276	378	133			44
BN 100					8				M8		195	367	307	429	142	98	98	50
BN 112	28	60	M10	31		130	110	160		3.5	219	385	325	448	157			52
BN 132	38	80	M12	41	10	165	130	200	M10	4	258	493	413	576	193	118	118	58


Motor Dimensions - Brake Motor - DC Brake - B3 Foot Mount



FRAME			SHAFT					HOU	SING								мото	R					
SIZE	D DA	E EA	DB	GA GC	F FA	В	A	НА	ВВ	АВ	К	С	н	AC	L	LB	LC	AD	AF	LL	v	R	s
BN 63	11	23	M4	12	4	80	100	8	96	120	7	40	63	121	272	249	297	122			14	96	
BN 71	14	30	M5	16	5	90	112	8	112	135	/	45	71	138	310	280	342	135	98	133	25	103	5
BN 80	19	40	M6	21.5	6	100	125	8	124	153		50	80	156	346	306	388	146			41	129	
BN 90S	24	50	M8	27	8	100	140	8	155	174	10	56	90	176	409	359	461	149			15	127	
BN 90L	24	50	IMIO	27	0	125	140	0	100	1/4		36	90	176	409	337	401	147	110	165	39	160	
BN 100	- 28	60	M10	31	8		160	10	175	192		63	100	195	458	398	521	158	110	100	62	100	6
BN 112	20	80	MITO	31	0	140	190	10	175	224	12	70	112	219	484	424	547	173			73	199	
BN 132S	- 38	80	M12	41	10		216	12	218	254	12	89	132	260	603	523	686	210	140	188	46	204	
BN 132M	36	00	IMIZ	41	10	178	210	12	210	254		07	132	200	603	523	000	210	140	100	40	(2)	
BN 160M	42	110	M16	45	12	210	254	25	264	319	14.5	108	160	310	736	626	820	245			51	266	
BN 160L	38 (1)	80 (1)	M12 (1)	41 (1)	10 (1)	254	234	23	304	317	14.3	100	100	310	780	670	884	243	187	187	J1	200	
BN 180L	48 42 (1)	110	M16 M16 (1)	51.5 45 (1)	14 12 (1)	279	279	26	329	359	14	121	180	348	886	756	981	261	10/	10/	52	305	-
BN 200L	55 42 (1)	110 (1)	M20 M16 (1)	59 45 (1)	16 12 (1)	305	318	20	355	398	18	133	200	340	878	768	993	201			64	300	

- 1. These values refer to the rear shaft end.
- 2. For FD07 high torque brake value R=226 (consult Power Jacks for more details).


Motor Dimensions - Brake Motor - DC Brake - B5 Flange Mount



FRAME			SHAFT					FLA	NGE							MO	ГOR				
SIZE	D DA	E EA	DB	GA GC	F FA	М	N	Р	S	Т	LA	AC	L	LB	LC	AD	AF	LL	V	R	ES
BN 63	11	23	M4	12	4	115	95	140	9.5	3	10	121	272	249	297	122			14	96	
BN 71	14	30	M5	16	5	130	110	160	9.5		10	138	310	280	342	135	98	133	25	103	5
BN 80	19	40	M6	21.5	6					3.5		156	346	156	388	146			41	100	
BN 90S	- 24	50	M8	27		165	130	200	11.5	3.5	11.5	176	409	176	461	149		165	39	129	
BN 90L	24	50	IMIO	21								176	409	176	401	146	110	160	39	400	
BN 100	20	/0	M10	21	8	245	245	245			14	195	458	195	521	158	1110	165	62	160	
BN 112	- 28	60	M10	31		215	215	215	14	4	15	219	484	219	547	173		165	73	199	6
BN 132	38	80	M12	41	10	265	230	300			20	250	603	523	686	210	1/0	100	46	204 (2)	
BN 160MR	42	110	M16	45	12							258	672	562	755	210	140	188	161	226	
BN 160M	38 (1)	80 (1)	M12 (1)	M41 (1)	10 (1)						4.5		E0./	/0/	000						
BN 160L	42 38 (1)	110	M16	45 41 (1)	12 10 (1)	300	250	350	18.5	_	15	310	736	626	820	245			51	266	
BN 180M	48 38 (1)	80 (1)	M12 (1)	51.5 41 (1)	14 10 (1)					5			780	670	864		187	187			_
BN 180L	48 42 (1)	110	M16 M16 (1)	51.5 45 (1)	14 12 (1)						10	0.46	866	756	981	0/4			52	005	
BN 200L	55 42 (1)	110 (1)	M20 M16 (1)	59 45 (1)	16 12 (1)	350	300	400	18.5		18	348	878	768	722	261			64	305	

- 1. These values refer to the rear shaft end.
- 2. For FD07 high torque brake value R=226 (consult Power Jacks for more details).

Motor Dimensions - Brake Motor - DC Brake - B14 Face Mount




FRAME			SHAFT				F	LANG	E						M0 ⁻	TOR				
SIZE	D DA	E EA	DB	GA GC	F FA	М	N	Р	S	т	AC	L	LB	LC	AD	AF	LL	v	R	ES
BN 63	11	23	M4	12.5	4	75	60	90	M5	2.5	121	272	249	297	122			14	96	
BN 71	14	30	M5	16	5	85	70	105		2.5	138	310	280	342	135	98	133	25	103	5
BN 80	19	40	M6	21.5	6	100	105	120	M6		156	346	306	388	146			41	129	
BN 90 S	0,1	F0	140	0.5		445	100	1/0		3	45/	/00	050	,,,,	149			00	129	
BN 90 L	24	50	M8	27		115	120	140	MO		176	409	359	461	146	110	1/5	39	1/0	
BN 100				0.4	8	400	440	1/0	M8	0.5	195	458	398	521	158	110	165	62	160	6
BN 112	28	60	M10	31		130	110	160		3.5	219	484	424	547	173			73	199	
BN 132	38	80	M12	41	10	165	130	200	M10	4	258	603	523	686	210	140	188	46	204 (1)	

Note

1. For FD07 high torque brake value R=226 (consult Power Jacks for more details).

11

FULL RANGE OF COUPLINGS AND DRIVE SHAFTS SO YOU CAN BUILD COMPLETE JACKING SYSTEMS.



Flexible Couplings

Selection of Coupling Type



The selection of coupling type depends on the installation and the type of misalignment. The three main types of misalignment encountered are:-

- 1. Angular Misalignment is usually present to some extent on all applications, typical values 1° 2°. Sometimes higher values are necessary.
- 2. Parallel (Radial) Misalignment is also nearly always present. A well aligned installation might have values below 0.25 mm.
- 3. Axial Misalignment (End Float) sometimes caused by thermal expansion or as a result of machine design.

Other considerations include:

- Backlash Free Couplings are either one part couplings or have bolted joints. These are effective for precise positioning and to avoid wear on reversing drives.
- Torsional rigidity of couplings depends on the joining method. Types with rubber or plastic elements can be considered as torsionally soft and will have an amount of twist at rated torque.

Procedure:

- Decide if the coupling should be torsionally soft or rigid.
- 2. Consider whether a small amount of backlash is acceptable.
- 3. Calculate the required coupling torque.
- 4. Make a provisional selection.
- 5. Check that the coupling's maximum speed is sufficient.
- 6. Check that the coupling's dimensions are acceptable.
- 7. Contact Power Jacks with your order or technical enquiry

Selection of Coupling Size:

Coupling Torque, T(Nm) = $\frac{9550 * Power Transmitted (kW) * S}{RPM}$

where S = Service Factor - dependant on drive conditions (refer to each coupling) Select the coupling which is rated above the calculated torque. If a brake is present in the system the coupling should be based on either the brake torque or the transmitted torque whichever is greater.

- 1. Maximum misalignment values are extremes and should not be combined. As operating misalignment approaches the maximum, torque and power ratings should be reduced to maintain life.
- 2. Gear couplings accommodate parallel misalignment by converting it to angular misalignment at the gear meshes in the flexible halves of the coupling.
- 3. The maximum axial misalignment values apply when the coupling is aligned. If axial misalignment greater than the listed maximum is required, consult Power Jacks.
- 4. The inertia values includes shafts through the bores.
- 5. When ordering please quote the coupling size and type, specify the bore and keyway sizes, and advise if puller holes or set-screws are required.
- 6. For maximum performance, the actuators, shafts, Gearboxes and motor should be carefully aligned.
- 7. Imperial couplings on request.

Keyways	Metric	Imperial
Standard Bores	B.S. 4500 1969 H7	B.S. 1916 Part 1 1953 K7
Standard Keyways	B.S. 4235 Part 1 1967 P9	B.S. 46 Part 1 1958

279

Jaw Type Flexible Coupling

- Curved jaw design.
- No need for lubrication.
- Quick and simple to install.
- Reliable, rugged and compact.
- Smooth, silent action.

- High power transmission density.
- 4 Standard spider types available.
- Elastomeric element resistant to heat (-40°C to +90°C), grease, oil and chemical agents.
- Hubs in aluminium and sintered iron.


Size		14	19/24	24/30	28/38	38/45	42/55	48/60	55/70	65/75	75/90	90/100	100/110
Torque (Nm)	Nominal, Tkn	Р	10	35	95	190	265	310	375	425	975	2400	3300
	Max T _{kmax}	Р	20	70	190	380	530	620	750	850	1950	4800	6600
	Vibrating Tkw (10Hz)	Р	2.6	9	25	49	69	81	93	111	254	624	858
Misalignment	Axial (mm)	Р	1.2	1.4	1.5	1.8	2	2.1	2.2	2.6	3	3.4	3.8
Valves	Angular (deg)	Р	0.9	0.9	0.9	1	1	1.1	1.1	1.2	1.2	1.2	1.2
	Radial (mm)	Р	0.2	0.22	0.25	0.28	0.32	0.36	0.38	0.42	0.48	0.5	0.52
Speed	Max (rpm)	Р	14000	10600	8500	7100	6000	5600	4750	4250	3550	2800	2500


Note All couplings use 92 Shore elastomeric element (white) as standard. 80, 98 and 95 available on request.


Maximum torque must not be exceeded during start-up operation.

More accurate alignment will increase coupling life and reduce vibration. Dimensions "E" and "L" must be observed.

P = Consult Power Jacks for more details.







Туре		Hub 'A'			Hub 'B'							Dim	ensions	(mm)					
	Pre Bore	Min Bore	Max Bore	Pre Bore	Min Bore	Max Bore	А	С	C1	L	L1& L2	Е		b	G	F	g		Weight kg
Aluminiu	m Hub (Coupling	gs																
19/24	6	6	19	18	20	24	40	31	38	66	25	16	2	12	20	18	M5	10	0.11
24/30	6	8	24	22	25	30	55	39	48	78	30	18	2	14	24	27	M5	10	0.24
28/38	9	10	28	26	30	38	65	46	61	90	35	20	2.5	15	28	30	M6	15	0.42
38/45	12	14	38	36	40	45	80	64	75	114	45	24	3	18	38	38	M6	15	0.86
Cast Iron	Hub Co	uplings																	
19/24	-	-	-	-	6	24	40	-	40	66	25	16	2	12	-	18	M5	10	0.34
24/30	-	-	-	-	8	32	55	-	55	78	30	18	2	14	-	27	M5	10	0.9
28/38	-	-	-	-	10	38	65	-	65	90	35	20	2.5	15	-	30	M6	15	1.5
38/45	-	14	38	-	40	45	80	66	78	114	45	24	3	18	37	38	M8	15	2.35
42/55	-	16	42	-	45	55	95	75	93	126	50	26	3	20	40	46	M8	20	3.55
48/60	-	19	48	-	50	60	105	85	103	140	56	28	3.5	21	45	51	M8	20	4.85
55/70	-	22	55	53	60	70	120	98	118	160	65	30	4	22	52	60	M10	20	7.4
65/75	-	25	65	63	70	75	135	115	133	185	75	35	4.5	26	61	68	M10	20	10.8
75/90	-	30	75	73	80	90	160	135	158	210	85	40	5	30	69	80	M10	25	17.7
90/100	-	-	-	-	45	100	200	-	170	245	100	45	5.5	34	81	100	M10	25	29.6
100/110	-	-	-	-	45	110	225	-	180	270	110	50	6	38	89	113	M12	30	39

Note Weight of min. bored coupling with standard A/B hub combination. All couplings metric bored and keyed as standard. Consult Power Jacks for standard bore sizes and specials.

Starts/Day

Service Factor S = Ft * Fz * Fs

Temperature (°C)	-30°C to +30°C	40°C	60°C	80°C
Temperature Factor (Ft)	1	1.2	1.4	1.8

Temperature Factor (Ft)	1	1.2	1.4	1.8
Shock Type	None	Light	Medium	High
Shock Factor (Fs)	1	1.2	1.8	2.5


0 to 10 | 101 to 200 | 201 to 400 | 401 to 800

Couplings & Drive Shafts

Flexible Spacer Couplings (Self-Supporting Drive Shafts)

- Compact, light, robust, long service life.
- Split coupling hubs allow shaft installation after main system components in place. Also allows easy replacement.
- Two identical hubs and one flexible element.
- Hubs of high strength Aluminium.
- Two piece clamp hubs with keyway.


- Compensates for axial, radial and angular misalignment.
- Spider inserts made of "92 Shore A" or "98 Shore A" Polyurethane as standard. "86 Shore D" available on request.
- Operating temperature range: -30°C to +90°C as standard



Coupling Performance and Dimensions

	Torque ³	Torque ³		ØE	(H7)					Sp	acer		Weight		DBSE	Cl	lamp Hubs
Size	(Nm) 92 Sh-A	(Nm) 98 Sh-A	Α	Min	Max	N	Р	Y	ØD _t	Inertia ¹	Rigidity 2	Hub (kg)	Spider (kg)	Weight (kg/m)	min (mm)	S	Tightening Torque (Nm)
01 (14)	7.5	12.5	30	6	15	14	12	20.5	30	0.162	1552	0.02	0.005	1.06	58	M4	3.1
00 (19)	10	17	40	8	20	19	16	30.5	35	0.273	2650	0.07	0.009	1.27	95	M5	6.2
0 (24)	35	60	55	10	30	22	18	37.5	50	0.917	8800	0.13	0.020	1.91	113	M6	10.5
1 (28)	95	160	65	14	35	25	20	41	60	2.184	21150	0.26	0.030	3.34	131	M8	25
2 (38)	190	325	80	15	45	34	24	46	70	4.341	42400	0.46	0.060	5.09	161	M8	25
3 (42)	265	450	95	20	50	39	26	49	80	7.418	66850	0.68	0.098	5.94	170	M10	46
4 (48)	310	525	105	25	60	46	28	49	90	11.021	99300	1.00	0.105	6.78	170	M12	80

Cino								Torqu	ie Tra	nsmit	ted (I	Nm) C	orres	pond	ing to	Ø Fin	ished	Bore	Size	(mm)							
Size	6	8	9	10	11	12	14	15	16	18	19	20	22	24	25	28	30	32	35	38	40	42	45	48	50	55	60
01 (14)	6	8	9	10	11	12	14	15	16*																		
00 (19)		14	16	17	19	21	24	26	28	31	33	35	33*	36*													
0 (24)				20	22	24	28	30	32	36	38	40	44	48	50	57	61										
1 (28)							55	59	63	71	75	79	86	94	98	110	118	126	137	128*							
2 (38)								59	63	71	75	79	86	94	98	110	118	126	137	149	157	165	177				
3 (42)												121	133	146	152	170	182	194	212	230	243	255	273	291	303		
4 (48)															217	243	260	277	303	329	346	364	390	416	433	476	520




- 1. Inertia values 10⁻³ kgm²/m (with max bore)
- 2. Rigidity values Nm/(Rad.m)
- 3. Nominal Transmittable Torque Values.
- 4. Max (Peak) Torque = 2 x Nominal Torque
- 5. Total Weight (with min bore) = (2xHub Weight) + (Spacer Weight x (DBSE-2Y))
- 6. Total Length $(L_{tot}) = DBSE+(2xN)$
- 7. *On Request
- 8. All dimension in millimetres unless otherwise stated.
- 9. Designs subject to change without notice.

Steel Gear Couplings

Continuous Sleeve Steel Gear Coupling

- Vari-crown tooth form for improved torque transmission and longer life.
- Strong compact design.
- High transmittable torque ratings.




Full-Flex Gear Coupling

Two flexible hubs and sleeve assembly. Accommodates angular, parallel and axial misalignments.

Flanged Sleeve Steel Gear Coupling

- High transmittable torque ratings and high maximum speeds.
- Accommodates angular, parallel and axial misalignment.
- Strong forged steel hubs and sleeves


- Low inertia and high maximum speeds.
- Steel reinforced high misalignment seals.
- Spacer couplings available on request.



Flex-Rigid Gear Coupling


Flexible and rigid hub assembly. The flexible hub is standard and the rigid hub is splined into the sleeve. Accommodates angular and axial misalignment only.

- Vari-crown tooth from improved torque transmission and longer life.
- Several mounting options available by reversing
- Spacer gear couplings available. Consult Power Jacks



Full-Flex Gear Coupling

Two flexible hubs and sleeve assembly. Accommodates angular, parallel and axial misalignments.



Flex-Rigid Gear Coupling

Flexible and rigid hub assembly. Accommodates angular and axial misalignment only.

Service Factors for Gear Couplings


Nature of Load on Unit	Uniform	Light Shock	Medium Shock	Heavy Shock
Service Factor, S	1.0	1.25	1.5	2.0

Exposed bolt design also available.


- 1. All dimensions in millimetres.
- 2. These couplings are designed for grease lubrication. A list of suggested lubricants and quantities is detailed in the installation manual supplied with each full coupling.
- 3. Where a coupling is exposed to sustained temperatures above 100°C (212°F) a coupling with high temperature seals must be used, consult Power Jacks Ltd.

Couplings & Drive Shafts

Steel Gear Couplings - Continuous Sleeve



Full-Flex Gear Coupling



Flex-Rigid Gear Coupling


o !: o		Full-Flex	CFF022	CFF038	CFF050	CFF065	CFF075	CFF090	CFF100	CFF115
Coupling S	ize and Type	Flex-Rigid	CFR022	CFR038	CFR050	CFR065	CFR075	CFR090	CFR100	CFR115
Rated Torq	ue (Nm)		285	854	2278	3417	5695	9967	14238	20787
Rated Pow	er (kW/100 rpm)		3	8.9	23.8	35.8	59.6	104.4	149	217.7
Maximum S	Speed Unbalanced * (r	rpm)	6000	5000	4200	3750	3000	2800	2400	2200
		Parallel	0.13	0.18	0.18	0.25	0.30	0.30	0.18	0.18
Full Flex	Maximum Misalignment	Angular	1°	1°	1°	1°	1°	1°	1°	1°
riex	Misaligilillelit	Axial (+/-)	0.3	0.3	0.3	0.6	0.6	0.6	0.6	0.6
Flex	Maximum	Parallel	0.5°	0.5°	0.5°	0.5°	0.5°	0.5°	0.5°	0.5°
Rigid	Misalignment	Angular	0.3	0.3	0.3	0.6	0.6	0.6	0.6	0.6
Inertia		(kg m ²)	0.002	0.004	0.010	0.022	0.053	0.112	0.225	0.376
Weight (Ro	ugh Bore)	(kg)	2.3	3.6	5.9	9.1	15	29	41	57
	Bore		31	42	56	70	84	97	111	130
Maximum	Keyway	(b x h)	8 x7	12 x 8	16 x 10	20 x 12	22 x 14	28 x 16	28 x 16	32 x 18
Rough Bor	9		11	15	18	22	30	32	44	60
DD			84	95	121	140	168	191	222	241
HD			51	60	83	100	121	137	159	184
HL			38	46	52	57	67	108	111	127
G			3	3	3	6	6	6	6	6
G1			10	13	13	19	19	19	19	19
OAL			80	95	108	121	140	222	229	260
R			95	117	124	145	175	235	241	264
LS			51	64	65	78	95	102	118	124
DC			3	5	5	6	6	6	6	6
CBD			49	57	76	95	121	140	165	184
SL			25	32	33	39	48	51	59	62

Note *Balanced speed approximately 3 times higher. Draw off holes are optional, consult Power Jacks. All dimensions in millimetres.

Note

1. Dimension 'R 'and 'CAC' are the clearance required to align the coupling when installing.

Steel Gear Couplings - Flanged Sleeve



Coupling Size and Type			FFF022	FFF038	FFF050	FFF065	FFF075	FFF090	FFF100		
Coupling Si	ze and Type	Full-Rigid	FFR022	FFR038	FFR050	FFR065	FFR075	FFR090	FFR100		
Rated Torqu	ıe (Nm)		859	2136	3560	6407	10679	17086	24917		
Rated Powe	r (kW/100 rpm)		8.9	22.3	37.3	67.1	111.9	179	261		
Maximum S	peed Unbalanced * (rp	om)	6000	5500	5000	4400	4000	3500	3000		
		Parallel	1.4	1.5	2.2	2.7	2.9	3.3	3.8		
Full	Maximum	Angular	3°	3°	3°	3°	3°	3°	3°		
Flex	Misalignment	Axial (per hub)	1.5	1.5	1.5	2.2	2.2	2.2	3.3		
Full	Maximum	Angular	1.5°	1.5°	1.5°	1.5°	1.5°	1.5°	1.5°		
Rigid	Misalignment	Axial (per hub)	1.5	1.5	1.5	2.2	2.2	2.2	3.3		
Inertia (kg r			0.006	0.019	0.044	0.100	0.192	0.435	0.80		
inertia (kg r	11-1	Flex Rigid	0.006	0.020	0.044	0.106	0.203	0.446	0.831		
Waiaka (Day	(I)	Full Flex	4	9	15	25	36	59	86		
weight (Rot	Weight (Rough Bore) (kg)		4	8	15	25	39	61	89		
Maximum	Bore		42	56	73	88	107	124	147		
(Flexible Ends)	Keyway	(b x h)	12 x 8	16 x 10	20 x 12	25 x 14	28 x 16	32 x 18	36 x 20		
Maximum	Bore		56	76	95	114	134	150	176		
(Rigid Ends)	Keyway	(b x h)	16 x 10	20 x 12	25 x 14	32 x 18	36 x 20	36 x 20	45 x 25		
Rough Bore		FFF	11	18	24	22	37	46	62		
Rough Bore		FFR	Solid with Centre								
OAL			89	102	127	159	187	219	248		
FD			116	152	178	213	240	279	318		
D			78	101	125	150	176	201	235		
HD			59	76	102	118	143	165	191		
LBT			43	49	62	77	91	106	121		
LTB 1	LTB 1			47	58	74	87	101	113		
BSE		FFF	3	3	3	5	5	6	6		
DOE		FFR	4	4	4	5	5	6	8		
OAL		FFF	89	102	127	159	187	219	248		
UAL		FFR	87	100	124	156	183	213	241		
CAC		FFF	106	121	152	181	207	238	260		
FFR			95	109	137	167	192	222	248		
Flange Thickness per Hub			14	19	19	22.5	22.5	29	29		

Note *Balanced speed approximately 3 times higher. Draw off holes are optional, consult Power Jacks. All dimensions in millimetres.

Couplings & Drive Shafts

Solid Drive Shafts



There are three standard drive shaft sizes offered by Power Jacks with ends machined to suit screw jack system couplings however drive shafts can be supplied to customer sizes with specific end designs

Standard Drive Shafts	Rated Torque (Nm)	Rated Angle of Twist per Metre (Degrees)		
20mm Diameter	85	4		
30mm Diameter	285	2.6		
40mm Diameter	675	2		

Note

- 1. For other drive shaft types and sizes consult Power Jacks Ltd.
- 2. For detailed analysis consult Power Jacks Ltd.
- 3. Dimensions subject to change without notice.

Select Drive Shaft Diameter

Select a standard drive shaft from the drive shaft table and check its torque rating and angle of twist rating against the application requirements.

If Transmitted Torque (Nm) < Maximum Drive Shaft Torque (Nm)

&

If Acceptable Angle of Twist (Deg.) for shaft length < Rated Angle of Twist for Drive Shaft (Deg.) Then drive shaft diameter selected is acceptable.

Shaft Check Drive Shaft Critical Speed

For the unsupported shaft length calculate the drive shaft critical speed for the support conditions required. If Shaft Speed (rpm) < Drive Shaft Critical Speed (rpm) then drive shaft selection and configuration is acceptable.

Plummer Block Selection

If the drive shaft selected is not suitable due to the critical speed reduce the unsupported drive shaft length using plummer blocks. e.g. one plummer block at each end of the drive shaft and one in the middle, reducing the unsupported length to half the total drive shaft length.

Select a plummer block from the table relating to the appropriate shaft diameter size.


Re-calculate the critical speed for the new unsupported length and check for acceptability.


If space constraints restrict the number of plummer blocks and the drive shaft fails on the critical speed try increasing the shaft diameter to the next size up or consult Power Jacks for detailed analysis.

- 1. For other shaft and plummer block sizes and styles consult Power Jacks Ltd.
- 2. For detailed shaft analysis and selection consult Power Jacks Ltd.

Solid Drive Shafts


Drive Shaft Critical Speed Factors, \mathbf{F}_{dcs}





Allowable Drive Shaft Speed (rpm) =
$$\frac{\text{Critical Speed (rpm) for}}{\text{Unsupported Length "L" (from chart below)}} \times F_{\text{dcs}}$$

Drive Shaft Critical Speed Graph (Shaft Whirling)




Unsupported Shaft Length (m)

Based on simply supported both ends and 70% of the critical speed. (The factor of safety allows for couplings and slight misalignment)

— — 20mm Diameter ----- 30 mm Diameter —— 40 mm Diameter

286

One Piece Housing Plummer Block




Model	А	В	С	D	Е	F	G	Н	J	К	L	Weight (kg)
PB1-20	96	127	20.5	32	34	14	10	20	33.33	65	10.5	0.6
PB1-30	121	152	23.5	40	39.2	17	12	30	42.9	82.5	12.5	1.1
PB1-40	136	175	24.5	48	47.7	19	12	40	49.2	99	15	1.9
PB1-50	159	203	26	54	49.7	22	16	50	57.2	115	17	2.8
PB1-60	186	240	29.5	60	60.5	26.5	16	60	69.9	138	21	4.5

Note

- 1. All dimensions in mm.
- 2. Bore diameter tolerances: (H6+H7)/2.
- 3. Material: Cast Iron housing with eccentric locking ring.
- 4. Dimensions are subject to change without notice.
- 5. For other styles and sizes of Plummer Blocks consult Power Jacks Ltd.

Split Housing Plummer Block


Plummer blocks are to DIN736 with anti-friction bearings with tapered bores and adapter sleeve. The housings are made of cast iron and are sealed with felt strips on both sides. The housings are designed to allow floating or located bearings (bearing position set with one or two locating rings). It is recommended when arranging drive systems only one plummer block with located bearing is used in one drive line, to avoid distortion of the drive.



Model	ØD	А	В	С	Е	F	Н	L	М	N	Р	Weight (kg)
PB-20	20	165	46	67	19	40	72	130	M12	20	15	1.4
PB-30	30	185	52	80	22	50	92	150	M12	20	15	2
PB-40	40	205	60	82	25	60	109	170	M12	20	15	2.9

- 1. All dimensions in mm.
- 2. For other styles and sizes of Plummer Blocks consult Power Jacks Ltd.
- 3. Dimensions are subject to change without notice.

Hand Wheels




Model	А	В	С	D	Е	H7 Bore
HW 005	40	14	36	98	24	Ø10
HW 010	50	22	38	157	32	Ø14
HW 025	56	24	43	198	40	Ø16
HW 050	56	24	43	198	40	Ø19
HW 100	66	30	44	247	49	Ø25
HW 200	78	32	56	288	58	Ø28
HW 300	108	40	77	375	58	Ø35
HW 500	108	40	77	375	58	Ø40


Notes:

- 1. Material: Polished aluminium casting and rotating handle
- 2. Bored and keyed to BS4235 Part 1
- 3. All dimensions in millimetres unless otherwise stated
- ${\it 4. \ \ Other\ types\ of\ hand\ wheels\ are\ available\ on\ request.\ \ Consult\ Power\ Jacks.}$

Rotation Indicators








Model	ØA	ØВ	С	D	Е
RI 010	14	25	20	14	13
RI 025	16	29	26	16	14
RI 050	19	32	27	16	14
RI 100	25	50	40	21	19
RI 200	28	50	45	25	22

Notes

- 1. Rotation Indicators RI010, RI025, RI050, RI100, RI200 are suitable for fitment to screw jack worm shafts with the corresponding bore size.
- 2. Material: Composite Plastic
- 3. Bored (H7) and keyed to BS4235 Part 1
- 4. All dimensions in millimetres unless otherwise stated
- 5. Other types of rotation indicators are available on request. Consult Power Jacks.

11

OUR RANGE OF MOTION CONTROL DEVICES ALLOWS YOU TO SAFEGUARD THE OPERATION OF YOUR SCREW JACK SYSTEM AND ENSURES IT OPERATES WITHIN THE SPECIFIED PARAMETERS



RLS-51 Geared Cam Limit Switches

Rotary CAM Limit Switches allow a set of limit switches to be fitted to translating o rotating screw jacks by mounting them directly to the screw jacks worm shaft or in-directly via connecting shafts or gearboxes linking to the screw jacks worm shaft. These limit switches are fully adjustable for position over the entire length of the screw jacks stroke. RLS-51 limit switch features include:-

- Usable revolutions from 4.1 to 16,000
- 2 to 8 position limit switch units
- Enclosure IP66 as standard
- Mounting options for B5 Flange, B14 Face and B3 Foot mounted
- Available in three voltages 250V AC, 24V DC & 80V DC
- Modular design to allow a variety of options
- Operating Temperature: -40°C to +80°C

Illustrated Examples

All units shown are of the 2 limit switch type.



B14 Face Mount





RLS-51 Features

The RLS-51 geared cam limit switches are universal mechanical switching devices that have been designed for use in conjunction with cam discs based on a specific angle of rotation for indication of a large number of shaft revolutions. These cam discs serve to operate mechanical contacts.

Design features include:-

Low friction planetary gearing with irreversible, self-locking worm adjustment of the cam discs.

Fixed cam adjustment in the housing. The adjusting worms of the cam discs are arranged so that they can be accessed from the same direction as the contact connections for optimal accessibility in confined conditions. Adjustment is possible during operation. The simplicity and accuracy of the cam adjustment is unsurpassed.

Block adjustment of all switching contacts jointly is made possible by a single adjusting worm (black) without the switching points of the individual switching contacts being altered with respect to each other.

Large cam disc diameter for good adjustability and high switching point repeat accuracy.

Reinforced polycarbonate housing as standard with IP66 protection and a wide operating temperature range.

Modular design allows adaptation to suit individual requirements via intermediate pieces.

Options

- Position indicating plate for block adjustment.
- Potentiometer feedback drives (2 available) to suit single and multi-turn potentiometers
- Pulse transmitter with 50 pulses per revolution.
- Anti-condensation heater to prevent condensation and excessively low temperatures in the switches.
- Motor driven contact block adjuster.
- Mounting for encoders (incremental or absolute).
- Extended drive shaft for feedback devices.
- Aluminium housing for harsh environments and the fitment of large and heavy encoders, IP65 enclosure.
- Cam discs with a 40° cam angle can be provided at no extra cost. Other angles can be manufactured at extra cost on request.
- Stage technology tested unit can be provided to V8G 70 with test certificates.

RLS-51 Performance

Gear size	Usable rev's. selected	Usable rev's. theoretical with 15° cam disc's	Gear Ratio	Input/output stage	No of interim stages	1 rev. of the drive shaft - corresp. to an ang. mo- tion of cam disc = °	Change - over contact reset rev. at driving shaft	max drive speed (rpm)	min drive shaft speed (only for change - over contact)
	4.1	4.16	4.285	-	1 x 4.285	84	0.00714	1000	0.67
1	6.5	6.88	7.083	1.653	1 x 4.285	50.8	0.0118	1200	1.1
	11	11.23	11.56	2.698	1 x 4.285	31.14	0.0193	1500	1.8
	17.5	17.84	18.361	-	2 x 4.285	19.6	0.0306	1800	2.9
2	29.0	29.5	30.35	1.653	2 x 4.285	11.86	0.0505	1800	4.7
	48	48.13	49.538	2.698	2 x 4.285	7.27	0.0825	1800	7.7
	75	76.45	78.678	-	3 x 4.285	4.57	0.131	1800	12.2
3	125	126.39	130.054	1.653	3 x 4.285	2.77	0.2166	1800	20.2
	205	206.26	212.272	2.698	3 x 4.285	1.69	0.3536	1800	33
	323	327.6	337.135	-	4 x 4.285	1.06	0.5616	1800	52
4	540	541.5	557.284	1.653	4 x 4.285	0.65	0.9284	18 00	87
	880	883.8	909.59	2.698	4 x 4.285	0.4	1.515	1800	141
	1384	1403.7	1444.62	-	5 x 4.285	0.25	2.406	1800	224
5	2288	2320.2	2387.96	1.653	5 x 4.285	0.15	3.978	1800	371
	3735	3787.1	3897.58	2.698	5 x 4.285	0.09	6.493	1800	606
	5900	6014.77	6190.204	-	6 x 4.285	0.06	10.313	1800	*
6	9800	9942.2	10232.407	1.653	6 x 4.285	0.04	17.047	1800	*
	16000	16227.6	16701.17	2.698	6 x 4.285	0.02	27.824	1800	*

*Caution! Due to the slow actuation speed of the switching contacts caused by the high gear reductions, the changeover behaviour of the contacts is affected negatively. From gear size 6 it is therefore recommended to use only the normally - closed contacts of the switches. Before using analog feedback systems (eg. potentiometer) please consult our technical department.


Note: Maximum permissible relative humidity 60%

RLS-51 Switching Contacts

The contacts can either be connected through screw terminals for a cable cross section of $0.75 \, \text{mm}^2$ to $1.5 \, \text{mm}^2$ or through flat plugs $6.3 \, \text{x} \, 0.8 \, \text{mm}$ or through a printed card with cage tension spring terminals for a cross section of $0.14 \, \text{to} \, 2.5 \, \text{mm}^2$. For contacts with flat - plug connection, insulated flat - plug receptacles must be used at voltages above $25 \, \text{VAC}$ and $60 \, \text{VDC}$.

						Electri	cal Data		Mechani- cal life in
Contact Designation	Contact Type	Contact Material	Switch Actuation	Type of Connection	AC	- 15	DC	- 13	millions of switching
					А	V	А	V	operations
9911	Change-Over	Silver	Snap Action	Screw Terminal		230			10
99P ^{1]}	Change-Over	Silver	Snap Action	Flat plug 6.3			0.5	-	
99G ^{1] 3]}	Change-Over	Gold	Snap Action	Screw Terminal					
922]	Change-Over	Silver	Snap Action	Screw Terminal	1.5				
972]3]	Change-Over	Gold	Snap Action	Screw Terminal			-		
962]	Normally Closed	Silver	Push Action	Screw Terminal		_			
99T ^{4]}	Contact	Silvei	r usii Action	Screw lettimat			0.5	60	


- 1. Thermal permanent current Ith = 10A; Reference insulation voltage Ui = 250V at pollution degree 3
- 2. Thermal permanent current Ith = 6A; Reference insulation voltage Ui = 250V at pollution degree 3
- 3. Contacts 99G and 97 for PLC applications (gold contacts)
- 4. For screw terminal admissible cable cross section AWG 22 16
- 5. Positive opening to EN60947T5 1 & IEC947 5 1




POWERJACKS

RLS-51 Dimensions

B14, Face Mount




B5, Flange Mount



295

RLS-51 Dimensions

B3, Foot Mount



Features:

Housing made of glass fibre reinforced polycarbonate with IP66 degree of protection Modular design enables optimal space utilisation. Overall length can be extended as required with 25mm wide intermediate pieces.


		2 Contacts		4 Contacts		6 Contacts		8 Contacts	
Gear Size	Usable Revs	L1 (mm)	No of intermediate pieces	L1 (mm)	No of intermediate pieces	L1 (mm)	No of intermediate pieces	L1 (mm)	No of intermediate pieces
1	4.1 6.5 11	132	0	132	0	157	1	157	1
2	17.5 29 48	132	0	132	0	157	1	182	2
3	75 125 205	132	0	132	0	157	1	182	2
4	323 540 880	132	0	157	1	182	2	207	2
5	1384 2288 3735	132	0	157	1	182	2	207	3
6	5900 9800 16000	157	1	157	1	182	2	207	3

More than 8 contacts on request

Dimensions with more than 8 contacts and with special executions, eg. potentiometer, on request. For any further intermediate piece add 25mm to L1

Proximity Sensors


- Inductive Proximity Sensors.
- Non-contact, so no wearing parts.
- 2 Wire sensor for either Normally Closed (NC) or Normally Open (NO) switching.
- Long sensing range.
- Rugged one-piece Metal housing.
- Optical setting aid with 2 LED colour settings:-Red LED indicates just in sensing range.
 Yellow LED only indicates within 80% safe sensing range.
- M12 Plug in connection for fast change-ability.
- M12 sockets available straight or angled with 5 m cable
- Full 360° visibility for switching with 4 yellow LED's at 90° offset.
- Flush face as standard, non-flush available.
- Housing plated brass, Stainless Steel available on request.
- Operating voltage 10 to 30 VDC.
- Enclosure IP67.
- Operating temperature -25°C to +70°C
- Other types available on request. Consult power Jacks.
- Ideal for screw jack end of travel limit switches.




Sensor	M8	M12	M18	M30
Sensing Range (flush)	1mm	4mm	8mm	15mm
Overall Length, L	69mm	62mm	72mm	72mm

Model	M8	M12	M18	M30			
Electrical Design		DC PNP/NPN					
Output	normally open/closed	nor	mally open/closed programr	nable			
Operating Voltage (V)	5 to 36 VDC		10 to 36 VDC				
Current Rating (mA)	200mA	100) mA	400 mA			
Minimum Load Current (mA)	4		4				
Short-circuit Protection	No		Pulsed	·			
Reverse Polarity Protection	No		Yes				
Overload Protection	No		Yes				
Voltage Drop (V)		< 4.	6				
Leakage Current (mA)	< 0.8	<	1	< 0.5			
Operating Distance (mm)	0 to 0.8	0 to 3.25	0 to 6.48	0 to 12.1			
Switch-point Drift (%/Sr)	-10 to 10						
Hysteresis (%/Sr)	1 to 15	1 t	o 20	3 to 20			
Switching Frequency (Hz)	2700	700	400	200			
Correction Factors (approx.)							
Mild Steel	1	1	1	1			
Stainless Steel	0.7	0.7	0.7	0.7			
Brass	0.4	0.5	0.5	0.5			
Aluminium	0.3	0.5	0.4	0.5			
Copper	0.2	0.4	0.3	0.4			
Function Display							
Switching Status LED	1 x yellow		yellow (4 x 90)				
Setting Aid LED	None	red					
Operating Temperature (°C)	-25 / +80	-25 / +70					
Protection	IP 67	IP 67	IP 67	IP 67			
Housing Material	br	brass; special coated; CO-PC brass white bronze coated face CO-PC					
Connection		M12 connector					








Compact Electro-Mechanical Contact Limit Switches

Compact Contact Limit Switch Overview


- Compact electro-mechanical limit switch.
- Sturdy metal enclosure
- Pre-cabled unit.

POWERJACKS

- High end enclosure protection IP67.
- Available with plug-in connector.
- Other sizes and actuation heads are available on request. Consult Power Jacks.
- Ideal for screw jack end of travel limit switches.








CLS-RPTT (b)


Item	Description
Housing	Metal, compact housing, totally enclosed and sealed
Pre-cabled	2m PVC cable 5 x 0.75mm² (other cable lengths available on request)
Switch type	Single pole, 1 change-over, snap action
Switch actuation	Steel Roller Plunger a Lateral Cam Approach CSL-RPTL b Travers Cam Approach CSL-RPTT
Max actuation speed	0.5 m/s
Mechanical durability	10 million operating cycles
Ambient temperature Operation Storage	-25°C to +77 °C -40°C to +70 °C
Product conformity	IEC947-5-1
Enclosure	IP67
Operating characteristics	AC - 15; B300 (UE = 240V, le = 1.5A) DC - 13; R300 (UE = 240V, le = 0.1A)
Insulation voltage	Ui = 300V




Compact Contact Limit Switch Dimensions









Note

- 1. All dimensions in mm unless otherwise stated.
- 2. Dimensions subject to change without notice.
- 3. For dimensions of other switches consult Power Jacks.
- 4. For a full switch data sheet consult Power Jacks.

E = 8 mm Max, Clearance Diameter Ø12.5 mm (1) = Ø8 mm Cable

Motion Control

Safety Related Electro-Mechanical Contact Limit Switches

Safety Related Contact Limit Switch Overview

- Positive break Normally Closed contacts will not stick or weld shut.
- Watertight design to IP67 washdown requirements.
- Rugged corrosion resistant housing tolerates hostile environments.
- Safety system approved.
- Thermoplastic enclosure. Double insulated.
- Snap action with positive-break Normally Closed contact, approved for use in safety systems.
- Alternative actuators heads are available on request. Consult Power Jacks.
- Actuator heads can be repositioned in steps 4 x 90°
- Good resistance to oil and petroleum spirit.
- Actuating force: Min. 9 N.
- Positive break force: 19 N.
- Actuating speed with actuating angle 30° to switch axis. Snap action: Min. 20 mm/min, max. 1 m/s.
- Cable entry: Long Body 1 cable entry, at end. Short Body 2 cable entries from sides.
- Ideal for screw jack end of travel limit switches.



Safety Related Contact Limit Switch Specification


Feature	Description
Standards	IEC/EN 60947-5-1; EN 1088; BG-GS-ET-15
Design	EN 50047
Enclosure material	Glass-fibre reinforced thermoplastic, self-extinguishing
Protection class	IP 67 to IEC/EN 60529/DIN VDE 0470-1
Contact material	Silver
Contact type	Change-over with double break Zb, NC contacts with positive break
Switching system	A IEC 60947-5-1; B BG-GS-ET-15; snap action, NC contacts with positive break
Termination	Screw terminals for max. 2.5 mm ² cables (including conductor ferrules)
Rated impulse withstand voltage U imp	6 kV
Rated insulation voltage U i	500 V
Thermal test current I th	10 A
Utilisation category	AC-15; DC-13
Rated operating current/voltage le/Ue	4 A/230 VAC; 2.5 A/400 VAC; 1 A/500 VAC; 1 A/24 VDC
Max. fuse rating	10 A (slow blow); 16 A (quick blow), 6 A (slow blow) as positive break position switch
Ambient temperature	-30 °C to +80 °C
Mechanical life	20 million operations
Switching frequency	Max. 5,000/h
Switching point accuracy	-
Actuating speed **	Min. 10 mm/min
Contact break for complete stroke	2 x 2 mm
Bounce duration	< 3 ms
Switchover time	> 5.5 ms


^{**} For the switch plunger.

- 1. Technical Data subject to change without notice.
- 2. For a full set of limit switch details consult Power Jacks.


Safety Related Contact Limit Switch Dimensions

Long Body






Short Body



Switch Contacts/Travel



- 1. All dimensions in mm unless otherwise stated.
- 2. Dimensions subject to change without notice.
- 3. For dimensions of other switches consult Power Jacks.
- 4. For a full switch data sheet consult Power Jacks.


Incremental Encoders

The DFS60 is a high-resolution incremental encoder in a 60 mm design. The encoder is ideally suited for industrial applications including those with harsh environments due to its high enclosure rating, the large temperature range and robust ball bearing mounts.

- Compact Ø 60 mm design
- High-resolution incremental encoder up to 16 bit
- Programming of output voltage level by customer, zero pulse position, zero pulse width and number of lines from 1 to 65536
- Programming using programming tool or machine controller (RS485)
- Plug-in cable output, radial or axial.
- M23 and M12 connector designs, available axial and radial.
- Designs with face mount or servo flange, blind or through hollow shaft.
- Hollow shaft designs up to Ø15 mm.
- Insulated design available for through hollow shaft.
- Remote zero setting.
- Electrical Interface options include:
 - 4.5 to 5.5 V, TTL/RS422
 - 10 to 32 V, TTL/RS422
 - 10 to 32 V, HTL/push pull
 - 4.5 to 5.5 V, TTL/RS422, with 0-set function on the M23 connector
 - 10 to 32 V, TTL/RS422, with 0-set function on the M23 connector
 - 10 to 32 V, HTL/push pull, with 0-set function on the M23 connector
 - 4.5 to 32 V, TTL/HTL programmable
 - 4.5 to 32 V, TTL/HTL programmable with 0-set function on the M23 connector
- Ambient Temperature Range:
 - Working Temperature Standard: 0 to +85°C, Optional -30°C to +100°C
 - Working Temperature Standard: -40°C to +100°C
- Enclosure Rating: IP65 on Shaft and IP67 on housing & connector.
- Standard Shaft Sizes:
 - Blind hollow shaft sizes = 6, 8, 10, 12, 14, 15mm
 - Through hollow shaft sizes = 6, 8, 10, 12, 14, 15mm
 - Solid shaft with flange mount = Ø10 mm
 - Solid shaft with servo flange mount = Ø6 mm



Dimensions - Hollow Blind Shaft




Absolute Encoders

The AFM60 is a high-resolution multi-turn absolute encoder in a 60mm housing design shared with its incremental counterpart. Ideally suited for industrial applications including those with harsh environments due to its high IP enclosure rating, large temperature range and robust ball bearing mounts. The absolute encoders' use the SSI interface as standard but can also be supplied with combined incremental or Sin/Cos interfaces.

- Compact Ø 60 mm design
- High-resolution absolute encoder up to 30 bit
- Up to 262144 steps per revolution
- Up to 4096 revolutions
- SSI / Gray code.
- Programmable resolution and offset (depends on type).
- Programming using programming tool or machine controller.
- Matched programming cable adapter for M12 & M23 connector available
- Plug-in cable output, radial or axial.
- M23 and M12 connector designs, available axial and radial.
- Designs with face mount or servo flange, blind or through hollow shaft.
- Hollow shaft designs up to Ø15 mm.
- Operating Voltage 4.5 to 32 V
- Ambient Temperature Range:
 - Working Temperature Standard: 0 to +85°C, Optional -30°C to +100°C
 - Working Temperature Standard: -40°C to +100°C
- Enclosure Rating: IP65 on Shaft and IP67 on housing & connector.
- Standard Shaft Sizes:
 - Blind hollow shaft sizes = 8, 10, 12, 14, 15mm
 - Through hollow shaft sizes = 8, 10, 12, 14, 15mm
 - Solid shaft with flange mount = Ø10 mm
 - Solid shaft with servo flange mount = Ø6 mm




Dimensions - Hollow Blind Shaft



USEFUL INFORMATION FOR ENGINEERS

303



Length	m	mm	inch	ft
1 m	1	1000	8mm	3.2808
1 mm	0.001	1	0.03937	32.8 x 10 ⁻³
1 inch	0.0254	25.4	1	0.0833
1 ft	0.3048	304.8	12	1

Mass	kg	Tonne	lb	Ton (Short)	Ton
1 kg	1	0.001	2.2046	1.1023 x 10 ⁻³	9.842 x 10 ⁻⁴
1 Tonne	1000	1	2204.6	1.1023	0.9842
1 lb	0.45355937	4.536 x 10 ⁻⁴	1	5 x 10 ⁻⁴	4.464 x 10 ⁻⁴
1 Tonne (Short)	907.185	0.907185	2000	1	0.8929
1 Ton	1016.05	1.016	2240	1.120	1

Force / Weight	N	kgf	kp	lbf
1 N	1	0.1019716	0.120	0.224809
1 kgf	9.80665	1	1	2.2046
1 kp	9.80665	1	1	2.2046
1 lbf	4.44822	0.45359237	0.4536	1

Speed	N	mm/s	ft/s	in/s
1 m/s	1	1000	3.2808	39.37
1 mm/s	0.001	1	3.28 x 10 ⁻³	0.03937
1 ft/s	0.3048	304.8	1	12
1 in/s	0.0254	25.4	0.0833	1

Torque / Work	Nm	kgf.cm	lbf.in	lbf.ft
1 Nm	1	10.19716	8.8507	0.73756
1 kfg.cm	9.80665 x 10 ⁻²	1	0.8679	0.07233
1 lbf.in	0.1129848	1.1521	1	0.08333
1 lbf.ft	1.35582	13.825	12	1

POWERJACKS

Power	kW	Nm/min kgf.m/s		hp	lbf.ft/min
1 kW	1	60000	10.20	1.34	44220
1 Nm/min	1.667 x 10 ⁻⁴	1	1.699 x 10 ⁻³	2.235 x 10 ⁻⁵	0.7374
1 kgf.m/s	9.807 x 10 ⁻³	588.6	1	0.01315	433.73
1 hp	0.7457	44741	76.04	1	33000
1 lbf.ft/min	2.261 x 10 ⁻⁵	1.3566	2.3056 x 10 ⁻³	3.03 x 10 ⁻⁵	1

Inertia	kg.m² (mr²)	kpms²	lbf.ft2 (WK²)	lbf.in2 (WK²)
kg.m² (mr²)	1	0.10197	23.73	3417.2
1 kpms²	9.807	1	232.6	33488
1 lbf.ft2 (WK²)	0.0421	4.30 x 10 ⁻³	1	144
1 lbf.in2 (WK²)	2.9264 x 10 ⁻⁴	0.6192	6.944 x 10 ⁻³	1

Stress / Pressure	MPa (N/mm²)	N/m²	kg/cm²	lbf/inch²	lbf/ft²
1 MPa (N/mm2)	1	1 x 10 ⁻⁶	10.2	145.039	20885.6
1 N/m ²	1 x 10 ⁻⁶	1	10.2 x 10 ⁻⁶	145 x 10 ⁻⁶	20.88 x 10 ⁻⁶
1 kg/cm²	9.807 x 10 ⁻²	9.81 x 10 ³	1	14.2233	2.05 x 10 ³
1 lbf/inch²	9.8947 x 10 ⁻³	6.89 x 10 ³	0.070307	1	144
1 lbg/ft²	4.7879 x 10 ⁻⁵	47.88026	0.488 x 10 ⁻³	6.94 x 10 ⁻³	1

Temperature	
T °F	(T °C x 1.8) + 32°
T °C	(T °F -32) / 1.8

IEC Ratings

	1st Digit : Solid Ingress	2nd Digit : Liquid Ingress			
0	No special protection	0	No special protection		
1	A large surface of the body, such as hand (but no protection against deliberate acces.) Solid objects >50 mm diameter.	1	Dripping water (vertically falling drops).		
2	Fingers or similar objects not exceeding 80mm in length. Solid objects >12mm in diameter.	2	Vertically dripping water when the enclosure is tilted at any angle up to 15° from its normal position.		
3	Tools, wires, etc. of diameter or thickness >2.5mm. Solid objects >1mm diameter.	3	Water falling as a spray at an angle of 60° from the vertical.		
4	Wires or strips of thickness >1mm. Solid objects >1mm diameter.	4	Water splashed against the enclosure from any direction.		
5	Ingress of dust is not totally prevented, but dust does not enter in sufficient quantity to interfere with satisfactory operation of the equipment.	5	Water projected by a nozzle against the enclosure.		
6	No ingress of dust.	6	Water from heavy seas or projected in powerful jets.		
		7	Ingress of water in a harmful quantity not possible when the enclosure is immersed under defined conditions of pressure and time.		
		8	Submersible under defined conditions of pressure and time.		

NEMA and IEC Equivalent Enclosures

Since the IEC degree of protection for enclosed equipment is defined differently from NEMA type enclosure protection, and methods of test are different, exact correlation between IEC IP-type designations and NEMA types is not possible. It is possible to make rough comparisons, which may result in certain applications. The common NEMA type designations compare with IEC designations as follows:


	NЕМА Туре		Nearest IEC Equivalent
NEMA 1	General protection of people from live parts. Protection against falling dirt. Test: 1/8" to 1/2" (3.175 to 12.7mm) rod entry test and rust resistance tests.	IP2X (1)	Protected against solid objects greater than 12mm. Test: Metallic test finger and 12mm sphere tests. No IEC rust resistance test.
NEMA 3	Dust-tight and sleet resistant. Test: Rain, dust, external icing and rust resistance test.	IP54	Dust protected. Protected against splashing water. Test: Dust and oscillating sprinkler tests. No IEC rust resistance test.
NEMA 3R	Rain-proof and sleet resitant. Test: Rod entry 1/8" to 1/4" (3.175 to 6.35mm), rain, external icing and rust resistance tests.	IP34	Protected against solid objects greater than 2.5mm. Protected against splashing water. Test: 2.5mm rod and oscillating sprinkler tests. No IEC rust resistance or icing tests.
NEMA 4	Water-tight and dust-tight. Test: Hosedown, rust-resistance and external icing tests.	IP65	Dust-tight and protected against water jets. Test: Dust and spray nozzle tests. no rust resistance or external icing test.
NEMA 4X	Water-tight, dust-tight and corrosion resistance. Test: Hosedown, corrosion resistance and external icing tests.	IPW65 (2)	Dust-tight and protected against water jets. Test: Dust and spray nozzle tests. No rust resistance or external icing test.
NEMA 7	Hazardous gas.	-	No IEC equivalent.
NEMA 9	Hardous dust.	-	No IEC equivalent.
NEMA 12	Dust-tight and drip-tight. Test: Drip, dust and rust resistance tests.	IP61	Dust-tight and protected against dripping water. Test: Dust and rain simulator tests. No IEC rust resistance test.
NEMA 18	Oil tight and dust tight. Test: Oil-tightness and rust-resistance tests.	IP6X (1)	Dust-tight. Test: Dust test. No IEC oil-tightness or rust resistance tests.

- 1. When only one characteristic numeral is used the second numeral is replaced by an 'X'.
- 2. 'W' inserted after the 'IP' indicates suitable for a specified weather condition (conditions and features specified by manufacturer.


POWERJACKS

Thread Size	Pitch	F	lexagon Bolts & Nu	ts	Soc	ckets Head Cap Scr	ew
D		А	Н	K	R	Т	W
M3	0.50	5.5	2.125	2.4	5.5	3.0	2.5
M4	0.70	7.0	2.925	3.2	7.0	4.0	3.0
M5	0.80	8.0	3.650	4.0	8.5	5.00	4.0
M6	1.00	10.0	4.150	5.0	10.0	6.0	5.0
M8	1.25	13.0	5.650	6.5	13.0	8.0	6.0
M10	1.50	17.0	7.180	8.0	16.0	10.0	8.0
M12	1.75	19.0	8.180	10.0	18.0	12.0	10.0
(M14)	2.00	22.0	9.180	11.0	21.0	14.0	12.0
M16	2.00	24.0	10.180	13.0	24.0	16.0	14.0
(M18)	2.50	27.0	12.215	15.0	27.0	18.0	14.0
M20	2.50	30.0	13.215	16.0	30.0	20.0	17.0
(M22)	2.50	32.0	14.215	18.0	33.0	22.0	17.0
M24	3.00	36.0	15.215	19.0	36.0	24.0	19.0
(M27)	3.00	41.0	17.215	22.0	40.0	27.0	19.0
M30	3.50	46.0	19.620	24.0	45.0	30.0	22.0
(M33)	3.50	50.0	21.260	26.0	50.0	33.0	24.0
M36	4.00	55.0	23.260	29.0	54.0	36.0	27.0
(M39)	4.00	60.0	25.260	31.0	-	-	-
M42	4.50	65.0	26.260	34.0	63.0	42.0	32.0

Hexagon Bolt




Socket Head Cap Screw



- 1. All dimensions in millimetres.
- 2. Sizes in brackets are non-preferrred standards.
- 3. All dimensions are maximum sizes.

Enlarged Detail of Key and Keyways



Syn	nbol	Key		Keyway										
Non	ninal			Width, B					Depth					
1	neter	BxH	Nom		Toler	ance for c	lass of fit						Radi	us, R
	D	width x		Fre	ee	Nor	mal	Close and Interference	Shat	ft, T1	Hub	o, T2		
Over	Incl	thick-ness		Shaft (H9)	Hub (D10)	Shaft (N9)	Hub (Js9)	Shaft and Hub (P9)	Nom.	Tol.	Nom.	Tol.	Max.	Min.
6	8	2 x 2	2	+0.025	+0.060	-0.004	+0.012	-0.006	1.2	+0.1	1.0	+0.1	0.16	0.08
8	10	3 x 3	3	0	+0.020	-0.029	-0.012	-0.031	1.8	0	1.4	0		
10	12	4 x 4	4	+0.030	+0.078	0	+0.015	-0.012	2.5		1.8			
12	17	5 x 5	5	0	+0.080	-0.030	-0.015	-0.042	3.0		2.3		0.25	0.16
17	22	6 x 6	6						3.5		2.8			
22	30	8 x 7	8	+0.036	+0.095	0	+0.018	-0.015	4.0	+0.2	3.3	+0.2		
30	38	10 x 8	10	0	+0.040	-0.036	-0.018	-0.051	5.0	0	3.3	0	0.40	0.25
38	44	12 x 8	12						5.0		3.3			
44	50	14 x 9	14	+0.043	+0.120	0	+0.021	-0.018	5.5		3.8			
50	58	16 x 10	16	0	+0.050	-0.043	-0.021	-0.061	6.0		4.3			
58	65	18 x 11	18						7.0		4.4			
65	75	20 x 12	20						7.5		4.9		0.60	0.40
75	85	22 x 14	22	+0.052	+0.149	0	+0.026	-0.022	9.0		5.4			
85	95	25 x 14	25	0	+0.065	-0.052	-0.026	-0.074	9.0		5.4			
95	110	28 x 16	28						10.0		6.4			
110	130	32 x 18	32						11.0		7.4			
130	150	36 x 20	36	+0.062	+0.180	0	+0.031	-0.022	12.0	+0.3	8.4	+0.3	1.00	0.70
150	170	40 x 22	40	0	+0.080	-0.062	-0.031	-0.088	13.0	0	9.4	0		
170	200	45 x 25	45						13.0		10.4			

Note

For full range and further informtion refer BS 4235: Pt 1: 1972

POWERJACKS

Physical Property Values, at 20°C

Material	Carbon Steel	Aluminium Alloys	Brass 65/35	Copper	Stainless Steel
Density, ρ (kg/m³)	7860	2710	8450	8910	7750
Young's Modulus, E (GN/m²)	207	710	105	105 119	
Shear Modulus, G (GN/m²)	79.3	26.2	38	44.7	73.1
Bulk Modulus, K (GN/m²)	' 177		115	130	178
Poisson's Ratio, v	sson's Ratio, v 0.292		0.35	0.326	0.305
Coefficient of Thermal Expansion x 10-6/K		22	19	17	14
Specific Heat J/kg K 460		920	420	420	460

Note

Values given are representative. Exact values may vary with composition and processing, sometimes greatly.

Standard SI Prefixes * †

Name	System	Factor
exa	Е	1 000 000 000 000 000 = 10 ¹⁸
peta	Р	1 000 000 000 000 000 = 1015
tera	Т	1 000 000 000 000 = 10 ¹²
giga	G	1 000 000 000 = 10°
mega	М	1 000 000 = 106
kilo	k	1 000 = 10 ³
hecto ‡	h	$100 = 10^2$
deca ‡	da	$10 = 10^1$
deci‡	d	0.1 = 10 ⁻¹
centi ‡	С	0.01 = 10 ⁻²
milli	m	0.001 = 10 ⁻³
micro	μ	0.000 001 = 10-6
nano	n	0.000 000 001 = 10 ⁻⁹
pico	р	0.000 000 000 001 = 10 ⁻¹²
femto	f	0.000 000 000 000 001 = 10-15
atto	а	0.000 000 000 000 001 = 10-18

^{*} If possible use multiple and submultiple prefixes in steps of 1000.

[†] Spaces are used in SI instead of commas to group numbers to avoid confusion with the practise in some European countries of using commas for decimal points.

[‡] Not recommened but sometimes encountered.

Limitation of Responsibility

The ratings given in this catalogue were compiled using standard engineering procedures. The ratings are designed to guide the customer in the selection of a unit. We do not guarantee the ratings in specific applications. Prototype testing of every application is recommended before production. Our engineering facilities are available for consultation at all times. Please ask us for assistance with linear motion and drive application problems. This catalogue is designed to assist in the selection of a suitable linear motion or power transmission product for economical, long and trouble free service.

Due to Power Jacks policy of continuous improvement designs may be subject to change without notice. Please ask for certified drawings.

Warranty Definitions

When used in these conditions the following words have the meanings set out opposite them below:

Company: Power Jacks Limited

Contract: The contract between the Company and the Customer for the supply of the Goods.

Customer: The party to whom the Goods are to be supplied under the Contract

Goods: The goods to be provided under the Contract

Writing: Includes facsimile or electronic transmission and comparable means of communication

Warranty Definitions

The Company warrants that any Goods sold by it under Power Jacks standard terms and conditions of sale will be free from defects caused by faulty materials or poor workmanship but gives no warranty and makes no representation whatsoever express or implied as to any other matters including without limitation condition merchantability or fitness for any purpose.

The Company shall incur no liability under this warranty unless:

- The Company is promptly notified in Writing upon discovery of any such defects by the Customer and the Customer forthwith ceases to use the defective Goods unless otherwise authorised by the Company; and
- The defective item is immediately returned to the Company, transportation charges being prepaid by the Customer or the Company is, at its option, given the opportunity to remedy any defect.

The Company's warranty as specified above is limited to a period of 12 months from the date of delivery (ex-works Power Jacks) and its liability shall be limited to replacing, repairing or issuing credit at its option for any Goods returned by the Customer within the aforesaid period.

The Company shall not be liable for consequential loss or damage by reason of any defect in (or failure to comply with any written estimate of performance of) Goods supplied by the Company whether original or substituted.

The Customer will indemnify the Company against all third party claims made in respect of the Goods.



Power Jacks specialises in the design and manufacture of precision linear actuation, positioning and lifting equipment.

Our products are supplied globally across many sectors including Industrial Automation, Energy, Transport, Defence and Civil.

Power Jacks Ltd Kingshill Commercial Park Prospect Road, Westhill Aberdeenshire AB32 6FP Scotland (UK)

Tel: +44 (0)1224 968968

www.powerjacks.com sales@powerjacks.com

PJDG-SJ-EN-05







All information in this document is subject to change without notice. All rights reserved by Power Jacks Limited. May not be copied in whole or in part. © Power Jacks Limited 2025, Aberdeenshire, Scotland, United Kingdom.